


Avenue Heraeum

CWB II







C. W. Blegen

Argive Heraeum 1927

11

~~10~~  
4.6  
~~15~~  
~~6~~ 13

## Tomb

- (16) p 8, 9, 13, 16, 17, 23, (69), 170
- (17) 9, 13, 18, 23, 24, 29, 31, 33, 35, 41, 45, 47, 50  
(69), 81, 87, 91, 99, 170
- (18) 13, 16, 18, 23, 24, 170
- (19) 13, 16, 19, 23, 33, 35, 170
- (20) 15, 23, 24, 32, 170
- (21) 23, 33, 35, 41, 45, 47, 49, 71, 170f.
- (22) 23, 31, 33, 35, 42, 51, 57, 71, 81, 95, 171
- (23) 23, 29, 171
- (24) 23, 35, 42, 47, 49, (55), 61, 76, 171
- (25) 23, 35, 42, 49, 56, 61, 63, 73, 83, 88, 91, 96, 99f.,  
102f., 108, 111, 171
- (26) 23, 36, 42, 49, 56, 62, (65), 74, 83, 88, 92, 96  
172
- (27) 23, 36, 42, 59, (72), 84, 101, 105, 172
- (28) 26, 27, 36, 43, 47, 49, (57), 61, 75, 172
- (29) 27, 36, 37, 43, 45, 47, 75, 85, 87, 172
- (30) 27, 36, 37, 43, 45, (58), 173
- (31) 33, 35, 42, 43, 49, 56, 62, 65, 74, 83, 88, 92, 96  
173
- (32) 51, 56, 76, 84, 89, 93, 97, 101, 105, 109, 173
- (33) 51, 57, 76, 85, 89, 93, 97, 101, 106, 109, 111, 173

(over)

(4) Geometric Deposit 14, 25, 41, 45, 48, 52,  
55, 60, 63, 67, 71, 81, 87, 91, 95, 98,  
99, 103

Neolithic Deposit 23, 27

Grave XI 77

Sunday April 17

This Cox arrives Mycenae by noon  
train from Nemea.

Darbiotis arrives by evening train  
from Corinth

Ch B arrives at 8.30 P.M. by  
train from Athens

Chauffeur Nikolaos Georgiou  
engaged for 1 month at 35000 drs.  
he to look out for his own food etc

Pantelis Christopoulos acting foreman

Tools, etc., shipped down from  
Nemea Friday morning

Monday April 18

(7)

25 men:

Work begins

12 men on Old Temple terrace  
testing at E & W ends for evidence  
~~as to date of placement of~~  
~~platform.~~  
Dabichtu in charge

12 men on West Gerogalatos ridge  
digging trial trenches for tombs.  
Miss Cox in charge.

1 man to Nemea for water casks.

We sent for owner of field about be-  
tween tomb & grot permission to dig

( I left for Athens by 3.30 train  
to see if we can possibly save Monastery garden  
(opp. School) as a park ).

8

Tuesday April 19

32 men

Thursday April 21

9

38 men

8 on Old Temple Terrace

30 exploring for tombs

Exploration for tombs goes on on ridge where the Tholos tomb is - without much luck.

The one fd April 20 = Tomb (16) we chart out dromos to doorway which is walled up with smallish stones. I took 2 photographs of this door.

Wednesday April 20

35 men (for  $\frac{3}{4}$  day)  
on Temple Terrace

on ridge of Tholos Tomb.

Small chambered tomb fd - short dromos &amp; walled-up doorway

301 27-A-① doorway from west shadow on left

302 - - ② doorway as in ① practically no shadow

During day we find what looks like dromos of another tomb ca 10 m to the N of (16)

Ford car to Argos for a screw for carburetor

I returned from Athens by 3:50 PM  
train to Corinth - car Corinth to  
Mycenae at 9:45 PM

Payroll tonight Dr. 5525.

(10)

Friday April 22

(11)

Greek Good Friday - no work

Mrs. Cox & Darbshire leave by morning  
train for Athens.C. W. B. leaves after lunch for Tripoli -  
Sparta - by car10<sup>2</sup>

-50E

(12)

Monday April 25-

Mrs Cox returns to Mycenae by the evening train from Athens.

Chr B arr. Nauplia in the evening  
stays at New Hotel.

(13)

Tuesday April 26

31 men

- 4 E side Temple Terrace
- 2 W " " "
- 1 water carrier
- 24 digging for tombs
- 2 on W. Mycгалас ridge
- 22 n Beehive Tomb ridge.

Tomb 16. We begin to dig it out - removing door. Tomb collapsed we dig down from above. Tomb small.

Tomb 17. Dromos developing

Tombs 18 & 19 2 more tombs discovered higher up on slope

Visitors: A.M. Mrs Komatzis, Mr Stevanić, Dr Benjamić  
for lunch 12.30-1.30

Daboshine returned by car late in evening

(14) Geometric Deposit.

In field of Tholos Tomb  
ca 75 m. west of lathe are 600  
on ledge alone facing wall  
discovered April 21. Find here  
so far report of geometric objects.  
- potsherds, bronze, etc.

Best find is a large sheet of  
bronze, 2 ft. high, of substantial  
thickness, for protection against  
wrest - perhaps against leg of  
a chest. Broken at top &  
bottom but sides marginal. Has  
2 panels separated by guilloche.  
Dec in reverse technique  
2 scenes - above man with a  
swif woman below woman  
stabbing (or thrusting) a stab  
another woman extremely  
fine work; details incised  
very delicately.

Wednesday April 27

(15)

35 men

7 on Temple Terrace

1 water carrier

27 digging for tombs

Tomb 20. We seem to have still  
another tomb on upper part of slope

15) Tomb 16

Skeleton at high level at N E  
(inner) side of small chamber - per-  
haps buried from above after col-  
lapse? Contracted position on right  
side head to west child.  
Photographs.

30327-A-5. Skeleton from SW

3045 6 Skeleton from above from S.

Tomb 18

Dromos cleared of loose stones seems to  
be of broad short type  
Door badly walled with small stones  
Appears to be very irregular in shape

Tomb 19

Dromos cleared. Broad short type  
apparently. Strong slate difficult to  
make out  
Door somewhat more regular than that  
of 18 in shape & walled with larger  
stones. But not symmetrical in dromos  
- comes over against right side

305 Photographs 27-B-1 Dromos & door of 18

306 B-2 Dromos & door of 19

307 3 Door of 19

308 4 Door of 18

Thursday April 29

(17)

36 men & 2 donkeys

George Alexopoulos comes to work today

Bunny the forenoon we were all  
over from the Temple Terrace &  
began final trenches for tombs on east  
side of Bushue Tomb ridge - high  
up slope above fall from Her to Myc

Tomb 16

Cleared down to floor. A second  
skull found. Below it skeleton - per-  
haps buried in sitting position?  
Seems to be of a child - small  
bones. No pottery no objects

On east side of Tomb is a  
small cist covered with a few  
rough stones. Fragments of a  
pot appear.

309 27-B-5-1 Skeleton of child in  
Tomb 16 from SW

310 27-B-6 Cist covered by stone on  
E end of chamber T 16 from W

(18) Tomb 17  
Dromos developing into a very large, deep one.

Tomb 18

We began to open it after  
breakfast. Not collapsed but  
much fallen stucco or plaster.  
In coming down heap of bones  
appears in back center of small  
regular chamber - 2 pots - 1  
L H II - 2 other pots - 2 H III (2)  
to north - a 5-6 pot near  
door - small amphora  
Fine bead at weight of light steatite

Tomb 19  
<sup>(19)</sup>  
we began to open this morning  
runny stones walls up door.  
Behind a solid fill of earth.  
It looks collapsed so we begin  
to dig out from above, but soon  
strike hard rock. So we start  
again from dromos cutting away  
all front up to face edge of rock.

Geometric deposit

Miss Clarke arrived by the evening  
train from Athens

(20)

Friday April 29

(21)

46 men

Holiday of Zoodochon Pigris  
but we work.

Photograph

AK  
311

27-C-1 Bones etc., in air  
in Tomb (16)

CWTS to Athens by morning train

(22) Saturday April 30

Monday May 2

(23)

49 men

Total no. of Tombs now seems  
to be 12.

- Tomb 16 is finished. Plan done  
on ridge of beehive tombs
- 17 ready to open
- 18 almost finished - 23 p.m. (22)  
temply L.H.I. plan done
- 19 work going on inside
- 20 being opened
- 21 we seem to be in chamber  
door & dromos not yet fd.
- 22 Good dromos - no door yet  
ca. 40 m. N.E of Walstein's tomb
- 23 Small - dromos & part of chamber  
S.E of our No. 1
- 24
- 25
- 26
- 27
- on West Yerogalano ridge above  
Tomb 22 we have fd a nestlike  
hollow like that of 225 - on East  
Yerogalano - marked by black earth  
stones & potshards

Sunday May 1

CWTB returned from Atheng - by morning  
train to Comba, evening train to Mycenae

of Mylona am in morning left in  
car in evening for Comba

(24) A.R. Photographs  
31227 - C - 2

Door of Tomb 17

313 C - 3 Door of Tomb 20

One man begins to wash the  
pottery after breakfast, commencing  
with Tomb 18.

Sends to Argos at noon for  
2 barrels of wash basins, hydro-  
chloric acid & borax.

### Photographs

31427 - C - 4 Door of Tomb 17

31527 - C - 5 Door of Tomb 20 after  
removal of stones. Washed at  
top.

### Geometric Terrace.

(25) Some heavy foundations begin  
to appear on the terrace  
above the supporting wall.

16

Still another Tomb no. 26 appears  
on West Yerogalano ridge; has a  
wide dromos.

After work this evening we drove to  
Phrikha where one of our workmen  
Jaunis Danofontes who led us to a  
place to get the clay when good  
Myo. sherd's can be found (Palace style)  
We find some - also M H & F H  
It is a good site with Myo. quarries  
near by - chance for tombs  
Place is above church so come to  
Phrikha - region called Epano  
Chono.

Tuesday May 3

(27)

49 men

About half on West Yerogalano  
ridge & half on Beehive Tomb ridge

On West Yerogalano ridge we  
find 3 more tombs - fairly close to  
one no. 1.

28 Broad dromos

29 Narrow dromos

30 Dromos not yet clear, but pink  
breccia smooth soft rock into  
chamber - looks pretty well filled

Neolithic hollow on West Yerogalano  
We go on clearing the & collecting  
shards - 2nd basket today. Area  
seems to be like the limestone fd  
in 1925 in E Yerogalano & roughly  
of the same size.

Major anniversary from  
Athens.

(28)

Wednesday May 4

49 min

(29)

Tomb 17 most interesting  
development here to appearance  
of a larnax (?)

Tomb 23 almost closed out  
- nothing

BHTH arrives by noon from  
Athens

26

Thursday May 5

(31)

49 min

Tomb 17 Larnax (?) partly cleaned  
Made of coarse green clay. Very  
rotten - & on right hand side of Tomb  
at a high level. Seems painted  
outside. I see a broad band of black  
below rim - inside band of loops  
along rim & a second similar band  
below.

Tomb 22 we find door. Good  
large tomb apparently seems  
not to have collapsed.

BHH leaves by afternoon train

A.H. (32) Photographs

316 27 - C - 6 Tomb (20) from above  
after cleaning

317 27 - D - 1 Doorway of Tomb (21)

318 2 Tomb (20) from W looking through  
doorway

319 3 Doorway of tomb 27

320 4 Doorway of Tomb 22

321 5 Lamas in Tomb 17

322 6 Door & Dromos of Tomb (29)

Friday May 6 (33)

50 men

Tomb (17) Lamas cleaned out  
contains badly rotted bones of  
a child. 4 United brassical beads  
2 almond shaped pieces of glass  
proto. 1 steatite button

Tomb (19) Cleaning almost  
finished. Nothing much new  
seen.

Tomb (21) Digging out upper layers  
of fallen matter in chamber

Tomb (22) Doorway washed &  
cleaned. Well walled up  
photographed - drawn by  
Miss Cox. We open & are  
much disappointed to find  
that Tomb 6 has apparently  
collapsed.

Tomb (37) Bronze spear head  
found - also many frags  
of good LH II pot

Miss Clarke & Mayor leave by  
the morning train

(34) Saturday May 7

(35)

52 more

Tomb (17) clearing outer  
- some traps & bones  
then a high altar pre-  
sumable floor.

Tomb (19) finished to floor  
- ready to be drawn

Tomb (21) Digging in chamber

Tomb (22) Digging in through  
doorway, no hope of  
finding roof standing

Tomb (24) Broad doorway -  
circular chamber - approach  
floor level. Lower part of wall  
of door still standing

Tomb (25) Broad doorway cleared  
& doorway clear. Stones still close  
it, but many have fallen out  
Tomb has collapsed. We are  
not yet in chamber

Tomb (31) No doorway so left  
indirection of (26) re fd stone  
- perhaps will do (?)  
Good potsherds come up  
many fun over 2 & I put  
we are probably in chamber  
of a tomb which has fallen  
in & very tiny & squashed  
into narrow space

46

Tomb 26 Broad dromos - chamber partly dug but limits not yet fd. Lower part of wall blocking doorway still in place but doorway & upper part of wall broken away

Tomb 27 Dromos narrow. Wall closing door removed yesterday. Chamber has collapsed. Bronze knife fd 2 days ago in dromos.

Tomb 28 Broad dromos. Limits of chamber fd almost circular in shape ca. 3-m. in diameter. Part of wall closing door still left. Door seems to occupy almost free width of dromos.

Tomb 29 Narrow dromos slopes steeply downward & tapers sharply. Door fd nicely walled up. Looks as if chamber may not have fallen in

Tomb 30 All collapsed dromos broad but markedly tapering lower part of wall filling door still in place. Door regular - i.e. does not occupy full width of dromos but has good jamb of each side. Chamber seems rather small

37

Tomb 30 (cont.). along left side of dromos is a section of wall with cavity behind. May be like inst in T. ⑥ or perhaps merely a strong type side of dromos as in ⑩.

Tomb 29. At 11:45 we opened door. Chamber has not collapsed - floor covered with 10-20 cm. of very fine silt. Large heap of bones appears at back. Rotted wood in right corner - looks like remains of wooden bier (?) ca. 120 long by 70 wide a pot's apparent. One on each side of bier (?) one in heap of bones at back. Skull appears at C center. At extreme right a deep recess (or small side chamber?) Here some fallen stones. No odor in tomb. I tried a photograph from door 15 min. ago some dark small L stop.

Photographs

AH

3227 - 2-1 Tomb (24) & dromos

324

2 Dromos & door of Tomb (25)

325

3 Dromos & chamber of Tomb (26)

326

4 Dromos & chamber of Tomb (28)

327

5 Chamber of Tomb 29 from  
door. exp. 1.5 min. smallest  
stop.

328

6 Retaining wall of Geometric  
Terrace from W. lys.

Monday May 9

(39)

50 men

Tuesday May 10

50 men

CWB leave for Athens by the  
afternoon train

(40)

Wednesday May 11

(41)

47 men

Geometric Area. 12 men.

work of clearing has progressed considerably. We shall soon get the lines of the platform. Some good finds of broken stel coming out in. of platform.

Tomb (17) 2 men

Very interesting tomb. Many pots have come out (14 all told) in two - possibly 3 layers. Topmost layer even with top sarcophagus. Another one at bottom of sarcophagus. 3<sup>rd</sup> near floor of tomb.

One pot filled with ashes. Common bird of the fd. - half feet - head missing. Some bones & claws possibly L H II (?) others L H III

Tomb (21) 4 men

Cleaning almost done - looks as if has cist at each side. Very rich tomb in pottery - at least 25 pots & almost all of excellent L H II fabric - like pottery & drawings in tomb 505 - a very early Most of pottery on left hand side

(42)

Tomb (22) (4 men)

Digging out chamber from  
above - pit has reached one  
hole through doorway. Work  
progressing rapidly.

Tomb (24)

Ready for digging in  
Tomb

Tomb (25)

Digging out chamber from  
above & making good pro-  
gress.

Tomb (26)

Digging out chamber  
from top - fall of rock  
here this morning.  
We are digging out whole  
space between (25) & (31)  
- perhaps latter or part  
of former.

Tomb (27)

Digging out chamber from  
above - good progress,  
almost down to myc  
level.

Tomb (28)

Ready to dig out knife

Tomb (29)

Ready to dig out with  
knife Mrs Cox has made  
a plan showing state when  
opened.

Tomb (30)

3 men  
Digging out chamber with  
knife.

Tomb layer fd. 5 pots  
already show (or more) One  
is a splendid spherical type  
with wavy leaves & dots L H II  
a I. One is a cup of  
vaphio shape.

Tomb (31)

See (26)

Gold ornaments found here in  
May 9 to.

CW&B returns at noon from Delphi  
having been met at Isthmia by the Ford

(44)

Thursday May 12

(45)

49 men

Tomb 25 Finished for drawing  
at breakfast time. The 2  
men here were transferred to  
No. 28.

Geometric Terrace. 14 men  
Clearing W. end of platform  
& digging to north of platform.  
Frz. of bronze disk ft. at bottom  
of pebbly layer (wash) ca. 2.00 m.  
N. of platform.

Tomb 27 7 men.  
Seems to be L.H. & ca one  
dozen pots so far.

Tomb 29  
We begin digging on 1 chamber.  
In recess to right 2 large pots appear  
also a small cypix.

Tomb 30  
Ready to draw. ca 10 pots all  
in heap of bones to right of door.

46

## Photographs

- A<sup>H</sup>  
32927 - F-1 Lamas in Tomb 17 from above  
 330 F-2 Pots in N part of Tomb 21 from door  
 331 - 3 Pots etc w N part of Tomb 21 from S side  
 332 4 N side of T. 21 from above.  
 333 5 Pots in Tomb 20 from N side of chamber  
 334 6 Pots in Tomb 20 from above

47

Friday May 13

48 men

Tomb 17

Cleared around behind lamas  
Several more pots appear here.

Tomb 21

Drawing by Miss Cox almost done  
+ we began to take out pots.

Tomb 24

we began to find  
pots

Tomb 28

Many pots begin to  
appear

Tomb 29

In recess to right -  
a bronze mirror + a small bronze  
vessel w a long handle come  
to right both well preserved  
Also granite of stele  
buttons + some beads. Legs of  
an ivory comb.Yamaki Bakonlis reports for work  
this afternoon

De Waal left for Compt by afternoon train

(48) Geometric Terrace 14 men  
One force clears SW corner  
of terrace from top. No finds of  
consequence

One gang digging trench along N.  
side of foundation. None bronze  
fd here in layer of brown earth  
below pebble layer.

Bronze:

- 1 Moonphalic phiale - almost entire  
- 0.9 m in diam.
- 2 do. ca .097 m diam. One sides  
part of rim gone
- 3 3 bronze rings - plain wire
- 4 3 bronze pins - a very small & complete
- 5 Small bronze disks 2 or 3 fragmentary
- 6 Fragments of a bird - good? - cut  
out of very thin bronze sheet

At N W angle of foundation we  
find stoneware in a line parallel  
to W end of foundation. E of this  
we dig down along N. side of  
foundation from ca. 60 to 100  
below top of foundation. Here we  
find 2 nests of pots, one near  
wall shelf the other ca 2.50  
N. of wall near E end.

Several more or less whole. pots  
small cups, jugs & one amphora  
Chiefly Comonomic & Protocomonic  
but one too plain glass like  
the Geometric from Hypothecus

Saturday May 14

(49)

49 men

Tomb (23) Pots being taken out  
34 out by mid afternoon

Tomb (28) Large no. of pots now  
appear. Two look like Gray  
Minyan - all the rest seem to  
be LH III. more than 20.  
One amethyst lentoid bead 1/  
no canine. Also one spindle  
Whorl & 1 bead of glass past

Tomb (24) A great many pots ca  
20 in sight - all look LH III.  
Believe seems to be a burial  
layer - like that in Tomb (2)  
in 1925

Tomb (25) For the sake of safety  
for our workmen I decide to  
cut away ca 1 1/2 m. of over-  
hanging rocks east. Good  
progress made.


Tomb (26) Dig here included also  
T (31) which may be a side  
chamber or a separate tomb.  
We are cutting away a large  
projecting mass of rock between  
S.E. two & making fairly  
rapid progress.

(50)

## Photographs

A.H.  
33527 - G-1 Larnax in T. 17 from W

In T. (17) we remove the larnax  
(in fragments) - may fill 2 baskets  
+ proceed to die beneath it. 2  
small jars turn up ca 3 cm. below  
bottom of larnax. Some paste beads  
are also



Larnax made of coarse greenish  
clay with thick walls. Not very  
well baked - very rotten in the  
damp. We have let it dry  
for a week or so. It is  
now much easier to handle  
than at first. It has a  
large loop handle at either  
end & a smaller loop handle  
in the middle of each side  
just below the rim.

Tomb (32)

Dromos of narrow type (?)  
due up to door. Just S. of  
T. (27) Seems small

(51)

Tomb (33)

Dromos of broad  
type we seem to have  
door stone partly fallen out  
as in Tomb (28)

Tomb (22)

Work goes on fairly  
quickly enlarging pit from  
above

At 2.30 PM drizzle begins  
which turns into rain by 3.00 PM  
we stop work. I try to get the  
tombs protected as well as  
possible. Work of rain over  
by 4.15 PM

We pay off early. Total  
pay roll 13992. drachmas

Dark blue barrel by J.J. Evans  
for Randolph's Spotsale

Geometric Terrace

Work goes on here all day  
with 15 men.

Deep trench along north  
side of wall - nothing of  
consequence.

Cleans away top of terrace  
S.W. corner of flat form - layer  
of stone & pebbles - nothing of  
interest.

Sunday May 15

(53)

Settled rate of payment with  
Dimitrios  
110. drs. pension for full time  
85. drs. per day for bed breakfast & dinner

Up to last night have

Full pension:

$$\begin{array}{r} \text{DHC} \quad \text{RSD} \quad \text{CWTB} \\ 4\frac{3}{4} \quad 4\frac{3}{4} \quad 3 \\ \hline \end{array} = 12\frac{1}{2}$$

Part pension b. breakfast lunch

$$\begin{array}{r} \text{DHC} \quad \text{RSD} \quad \text{CWTB} \quad \text{EPC} \quad \text{AHM} \quad \text{BHM} \\ \hline 19 \quad 18 \quad 12 \quad 8 \quad 3 \quad 1 \\ \hline \end{array} = 6\frac{1}{2}$$

Also 3 Sundays = 7 lunates

$$\begin{array}{r} 12\frac{1}{2} \\ 110 \\ \hline 1375 \end{array}$$

7  
21  
175

$$\begin{array}{r} 61 \\ 85 \\ \hline 5185 \end{array}$$

$$\begin{array}{r} 1375 \\ 5185 \\ \hline 6735 \end{array}$$

Total due  
up to evening of May 14

Monday May 16

(55)

45 men

Gee metne Terrace. 14 men

One group digging down above  
"platform"

One group digging out a new area  
north of platform.

Tomb (24) 3 men

Chamber - straight on door side  
fairly regular circular others

Diam - straight ahead from door 3.50  
perpendicular to preceding 3.80

Door ca. .90 wide. 70 deep - all  
filled with wall of stones.

Dromos 2.00 wide outside door  
Sides taper slightly inward toward top

Dromos narrows as goes out  
6.00 " long 1.35 " wide  
at outer end. Steep slope  
down to 2.50 " in front of door

Tomb (25) 2 men

Digging down in rear part  
chamber.

Tomb (31) 5 men

Seems to be separate tomb ~  
think we now have door. Have  
cut away large chunk of fallen  
rock.  
Another bronze arrow head here (broken)

Tomb (26) 5 men

Trying to find back of chamber  
under overhanging ledge of rock  
rest of geometric pot turns  
up here

Tomb (32) 2 men

Have no door. Begin digging  
down to chamber from above  
since it seems to be collapsed

Dromos of narrow type ①

Tomb (33) 2 men

see seem to have door  
chamber probably collapsed  
we began digging down from above

Dromos of broad type

57

Tomb (28) 4 men (sifting)

Great heap at back of chamber  
x to right  
In center at deeper level fd  
Ephydian goblet w. rosette.

Chamber straight front side at door  
fairly regular circle on other sides

Diam from center of door 2.70  
+ plumbic. to above 3.15  
Door ca. 75 cm wide ca. 60 deep

Dromos 1.80 wide at door  
ca. 5.50 long  
1.25 wide at outer end

Door not centered - nearer  
left side

Tomb (22) 5 men

Enlarging shaft above chamber

## Photographs

- A.H.
- |     |         |  |
|-----|---------|--|
| 336 | - G - 2 | Pots in tomb (24) from above & W             |
| 337 | 3       | Litto with Nitso                             |
| 338 | 4       | Pots on right side of Tomb G from other side |
| 339 | 5       | Pots at back of tomb from near door          |


## Tomb (30)

Measured & drawn by Mrs Cox this morning

Chamber irregular in shape - not symmetrical with door - mainly to left.

Diam. along axis of dromos ca. 1.90  
" transverse ca. 2.15"

Front side roughly straight (left side almost straight - then curve to meet right hand front corner)



Door ca. .95' wide ca. .40 + deep

Closed by wall of stones irregularly placed  
ca. .55' thick. Maximum projection  
.25' on inside ca. .20' on outside  
fairly large stones

Dromos at door ca 1.65 wide  
" ca 4.50 + long. but end  
not clear grows narrower toward  
other end

On left hand side of dromos at  
.45' to 1.75' from door jamb is a  
small niche - walled up flush  
w/ side of dromos with fairly

regularly built wall of stones. Niche (59)  
is ca 1.30 m long .80 m deep &  
1.10 m high - arched ceiling. We  
dig & don't find a number of  
heads. No bones at all but  
one small fragment of a tooth.  
Beads: 2 spherical of carnelian &  
1/3 of paste of various sizes - (dark  
in color & fluted, the rest light  
& not fluted).

## Tomb (27)

One man begins digging out  
chamber after lunch

(60)

Tuesday May 17

(61)

45 min

Tomb (28)

Bronze dagger ft in moist just inside door. L H I pottery moist

In afternoon DHC begins to draw the tomb.

Tomb (24)

Drawing almost finished  
in morning + pots numbered &  
taken out in afternoon. 2  
cists still left

Tomb (25)

(66 ft side) On west side of chamber  
at a high level we  
find bones of a skeleton  
stretched out alongside legs  
against side of tomb a circular  
disk of bronze body crushed by  
stone & not well preserved.  
A few frags of pottery about  
bone - look L H III - though  
I thought disk was geometric?  
Diam ca .085. Perhaps a  
mirror

May 17

## Geometric Area

In region n-g in wall of  
terrace is further frags of bronze  
+ several disks etc. ~~nothing~~  
of consequence. One well preserved  
disk with straight sides, 1 good fm  
(now bent), one small stand of sobs

(62) Tomb (31)

Rivet of bronze fd. with gold-plated head  
we were digging out carefully  
a stone layer of sand or  
stones. 5 bronze arrow heads  
fd. of various sizes - some  
heavily broken 2 are complete.  
Also several more frags  
the large place style pot  
we found much in a few  
days ago

(63)

Wednesday May 18

45 men

Geometric Terrace 14 men

Some good bronze vessels fd. in  
on wall of terrace. ~~one~~ ~~one~~ ~~one~~  
~~one~~ ~~one~~ ~~one~~ ~~one~~ ~~one~~ ~~one~~ ~~one~~ ~~one~~ ~~one~~  
mesomphalic phialae. one pin perfectly preserved  
with gold head, + one handle,  
like a drawehole ending in snakes  
head at each end. Also a figurine  
B & C. archaic female

Tomb (22)

5 men

Sides of chamber fd. we  
go down rapidly toward floor

Tomb (26)

Back & right side apparently  
fd. at least at ca 1.00  
above level of floor of chamber  
(interior too) we find in  
the chamber against back  
wall a fairly large bronze  
mesomphalic phiale. in bad  
condition & thin - in pieces.  
Also a white geometric  
pot - broken in reducing

Tomb (25)

Skeleton on left side of chamber  
cleaned & photographed. Also drawn  
by DHC & then removed

On rt side of chamber small  
group of bones fd. also at high  
level but apparently not a  
skeleton in order. These too  
were drawn & removed

Darbhivira returns for breakfast

Photographs

ATT  
340 G - 6 Tomb (26) cleaned view  
from above

3417 - H (1) View through door of Tomb (26)  
showing pots on floor

342 (2) Grave XI (RSD p. 130)  
before removing cover slate.

343 (3) Stela on left hand side  
of Tomb (25) from above

344 (4) Door of Tomb (27)

345 (5) Tomb (26) as it now  
appears - dromos etc

May 19


346 (6) Stones in SW corner of  
Tomb (26) from above  
(from East)

Tomb (26) (65)  
Chamber seems to be  
roughly square.  
Left hand side of door built  
up with stones in good courses.

Left hand corner inside door  
including area ca 2 m square  
filled with loose mass of stones  
many fairly large. Among them  
fragments of bone & pottery. Many  
tips of Palace style pot similar to  
those from (31).

These stones fallen from a wall -  
perhaps along west side of  
chamber to help support roof  
& mark line division between  
(26) & (31). Or perhaps fallen  
from wall along south side  
of tomb adjoining built door  
frame.

Chamber roughly 3.70 fm N-S  
by 4.20 E-W



Thursday May 19

(67)

44 men

Geometric Terrace 13 men  
work goes on in n places & inside  
"terrace" - S. of N. wall. Here  
we have dug through a thick fill  
of stones & gravel up to 60 below  
top of wall. Then come brown  
earthen at depth of 100 below  
top of wall some Geometric sherds  
begin to appear.

Other area is noted "Terrace"  
enlarging on trench here. Many  
fraggs of bronze & gold rings  
one complete mesomphalic  
phiale. Today no bronze  
but a good many pottery  
still coming out - some fair  
large. Seen to be Corinthian  
Protocor & some Geometric D

Photographs

- #T-3471 - 1 Grave II cleaned showing shelter  
 348 2 Door of Tomb (33)  
 349 3 Pier beside door of Tomb (26) & fallen stones to W.  
 350 4 Fallen stones in T. (26) from above

Tomb 16

(69)


oval / irregular chamber roughly square  $1.35 \times 1.35$  with small niche & cist on right side. Niche .55 m long .45 m deep back roughly rounded.

Door - no jambs appear opening full width of dromos = .90 m Dromos 3.50 m long Dromos slightly curved width at outer end about same as at inner. Sides taper slightly toward top

Tomb 17

Chamber fairly regular - front left side & back almost straight w. rounded corners right side curved.

2.60 front to back  
 2.80 front to back  
 2.60 transverse diam



Door .68 wide at bottom  
 ca .60 thick  
 Upper part of door now ca  
 1.05 wide

Dromos 1.50 m wide at door on floor. n. ca. 6.80 m long  
 ca. 1.10 wide at both ends  
 Side of dromos slope sharply in  
 At top at door dromos ca 70 wide  
 & ca 2.40 deep at the pt.

Friday May 20

(71)

44 men

Geometric Terrace  
13 men

We are digging two deep pits - one inside "terrace" & one to north of N. wall.

Inside terrace we have found almost nothing. No bronze, but only a very few pieces below base of fill. In deepest shaft, stem of an unpainted cup-like bowl Mycenaean.

N. of N. wall in deep large pit found conch shells not in great numbers. Seem to be geometric. One piece possibly of a Myc. cup.

Tomb 22

We began digging on floor w - George Almon. Several pots appear - all I & IV

Tomb 21

Six my. cups from cistern & few sherds from top - belong to pots we have partly put together.

Tomb 27

Chamber roughly octagonal

3.70

Ca. 2.50 from front  
to back

3.70 side to side

Door ca. 95 - wide  
ca. .80 thick ③

Dromos ca. 1.00 wide  
at door. ca. 4.50 long  
slopes upward toward  
entrance.

Door badly fallen in.

In chamber in inner left-hand corner is a cut trench, filled with large stones. Outside dimensions  
ca. 2.00 m long 1.20 m wide  
Inside 1.25 m x .70 m.

Heap of bones in outer left corner.

Right side of tomb full of small  
large stone. Look fallen. We  
have them removed. Found many  
bones here's some pottery  
mostly in fragments. One  
ceramic pot unbroken

(73)

Tomb 25

Large pot in inner left corner  
inner part well cleaned; it looks  
like a Matt painted pot of the  
Polychrome group, but without  
one color showing.

Outer left corner very clean  
here in what was probably  
taken to be steps we find close  
against front wall, tomb  
a nest of good L.D. 2 pots  
loaf-shaped with my best design,  
one cup of saucer shape & one  
hole-mouthed jar.

Scanty traces of bones on  
floor of tomb.

In middle of left wall is  
a door (?) walled up with  
stones, well built. Perhaps  
door to a side chamber (?)  
or merely a pier to support  
steep roof? A similar  
construction is indicated in  
right hand wall in the  
middle of the back wall it  
looks as if we have a  
pier. We propose to  
examine them when we  
have cleaned floor of tomb

### Tomb 26

Here we have now cleared away great mass of fallen stone in cold left corner (6-). They seem to have fallen from a doorway once walled up leading to the line of doorway clearly discernable. In a 1.00 m wide wall nearly 1.00 m thick is a door at middle reinforcement side of tomb was a fault in soft rock made a support necessary?

Cleaning more doorway to leave bottom course of stones in place & dug into area of supposed Tomb 31. Here we seem to have thick layer of fallen stones - soft rock - one or 2 pithos in it. How it to be disturbed just before leaving we find a skull under the fallen rock ca. 40 below level of 30 where bronze dress殉葬品 is shield well so we shall go ahead & clear out area 31 to a deeper level. A well made floor (?) of stone (greenish color) appears at ca. 80 below supposed floor of tomb where we digging were found.

### Tomb 28

(75)  
Drawing by D H C finished we proceed to clear out rest - it contained only a few studs & one small pot none or less nearly complete.

Best pot for 24 is an 18 in. jar with huge octopus legs. Have smoking pipe with rings.

### Tomb 29

Cleaning by Bill Johnson finished drawing daily. A good orange digger fit on right had a solid tomb plan arrangement inside. There seem to be at least 7 separate pits all filled with bones. Some polished but not a great many were pots.

In niche to right apparently no bones. 3 pots of clay, 18 flamp? of bronze & a long minor pen; also rings - a gun iron comb & a small stone grinder which looks E H

In pit near back of tomb a big fire & a table with 4 legs - perhaps a bier?

Tomb ④

Drawing by DHC finished  
& Bill Johnson cleans out the  
2 cists. Nothing much here

Potter for ④ washed &  
cleared. One good pot a  
large jar w/ close style  
decoration around base of  
neck.

Tomb ③2

Smallish. We go on down  
into chamber from above. Seems  
to be developing a side  
chamber (or niche) to right

Tomb ③3

Fairly large. We go as  
many men as we can & go  
down into chamber from  
above. Seems to have a  
niche or a side chamber  
to left. Perhaps by some  
in mind from ③2

Grave XI

In field below Tomb ③3 (77)  
Drawn by Mrs Cox  
Grave contains 2 skeletons  
endrunk - heads clear though  
most of other bones badly  
rotted. One head of adult  
one more of a child, but  
who fairly developed teeth  
is not an infant.  
Under child's skull found  
a small ring of bronze wire  
Near shoulder of adult a  
button (oval) of fine  
chitos head behind  
& to W. of adults.

In dirt thrown up from  
trench here DHC noticed  
for a small pot - a  
shallow saucer like imp. wh.  
seems ornate & have had  
a high ribbon like handle  
now missing looks like  
yellow myrrh fabric.

Date of grave ? Probably  
Middle Helladic. Though not  
certain

John Gardner arrives by  
evening train from Athens.  
Large money & some  
supplies.

De Jones arrive by car in  
evening from Sparta.

Saturday May 21

(79)

44 men

Distribution much the same  
as yesterday.

CWB 3 knows by morning  
time - after breakfast at  
dig.

Sunday May 22

EPB & THH arrive from Phnom  
in evening with CWB in car.

Monday May 23

(81)

31 men

Geometric Terrace 12 men  
1. Squad digging out N. triangle

1 Squad digging S. of "terrace"

Tomb ⑯ 1 man with EPB & THH  
2 nests of pots turned up - both  
seem to be good L-H-T. 1 pot  
with heart-shaped leaves

Tomb ⑰

Cleaned & ready for drawing  
All pots seem to be L-H-T. Many  
figures - ca 12 One seated  
in a chair (?)

Photographs

- A.H.
- 351 I - 5 Stones at back of possibly wall of cist. (26)
- 352 - 6 Door of side chamber of Tomb (26) from E (31)
- 353 J - 1 Door in West side of Tomb (25)
- 354 - 2 Pots in SW corner of (25)

Tomb (25) (83)  
 West side cleared & being drawn by DHC. Nest of LH I pots at S end. Matt ptd pot at N end of W. side  
 Traces of bones on floor in W. corner. Big bones run from N-S (parallel to diomos)

On east side of tomb 6 we are examining possible door to E

Tomb (26)  
 This has become clear that (31) is a side chamber of (26). Rather small in area & appears to be rectangular & roughly square.

Against north side of (31) is a platform of stones etc. (perhaps cover of a cist). On this platform (on top) a good many bones & here were found the gold hm, gold plated rivet, 5 or 6 bronze arrowheads, frag of a bronze knife, & shields of Palace Style.

In SW corner of (31) is a good matt ptd jn. Polychrome style. Broken but much of it preserved.

In NW corner (near corner of w. wall & platform) is a second Polychrome matt ptd pot

Tomb 27

Cleaned & waiting to be drawn.

Inside door to left is a large cist - with a heap of bones at back just in SW corner of tomb

To right of door is a large irregular cist with a good many bones

At back of tomb on right side is a long heap of bones

At back of tomb on left side is a deep cist bordered by thick wall of stones - badly built. Some bones in it.

Pots are few in this tomb  
1 figurine appears as bird-shaped basket

Tomb 32

Bones & pots have begun to appear in niche at back of tomb. Pots look L H III

We are digging into niche to right & in course of morning break through a connect w/ side chamber ① of Tomb 33

Tomb 33

(85)

Chamber roughly square  
A large impainted pot has appeared near inner left corner

We are digging into side chambers to left & into with niche from ②. There seems to have been a walled up door from ③ into this side chamber

Tomb 29

Drawing by JSC partly done

7

Photographs

AH  
355 - J - 3 Tomb (31) cleaned (cloudy)

356 - 4 Tomb (31) skeleton of pts  
cleaned (with sun)

Tuesday May 24

(87)

32 men

Geometric Terrace  
as usual.

Tomb (17)  
DTH & DTH dig out most of  
floor. Several more pots appear  
ca 10 all told now visible.  
Seems to be LH II - I very  
fine jugs in good condition but  
badly smashed & rotted.  
A bronze knife or dagger

Tomb (29)

Drawing finished by DHC &  
we dig out all casts. Large  
no. of pots. 1 good Sphy calan  
w. nautilus design

Tomb (25) chamber completely cleared out - spots taken up & washed

We began to open door to N & find at floor level a bronze dagger.

We also began to open north door.

Tomb (26) chamber finished. In side chamber (31), we have cleared floor - skeleton lying in place on floor on back stretched out w. head to S feet to N. Arms seem out of place - on west side of body

To SW of skeleton a simple bronze dagger broad type w. 3 rivets. A 4<sup>th</sup> & larger just loose pot. belonged to hand & no trace of handle. Near dagger a small plain jar

At feet of skeleton 3 small LH I pots - jars. Another small jar under mat with pot in NW corner.

Tomb (32) cleaning goes on nothing special

Tomb (33) Many findings appear all LH III apparently.

To left (post) is a small side chamber we next floor here & find lots. Enclosed area to find sides of this side chamber.

Photographs (May 15)

At 357 J - 5' Built not alone N  
side of T (31) from above

358 J - 6 Do. from above & SE

Wednesday May 15

(91)

32 men

Geometric Terrace

Filling trenches

Tomb 17  
After 9 AM finish cleaning  
during morning

Tomb 25  
In W. door we find a  
skull & below it part of a pot

We begin to open East door  
& find a bronze spear head

Tomb 26 (side chamber 31)

Plan drawn by DHC &  
we remove the pots  
under the matt plst jar in  
NW corner find 2 small bronze  
dishes - probably pans of a  
balance. Each one has  
4 small holes near edge -  
symmetrically spaced.

Clear away top of platform  
find second skeleton under  
first - or perhaps part of  
first (?) very large femurs  
& tibias.  
A small L.H.I pot at  
extreme W end of platform  
at this level.

Below these bones a layer  
of gravel & under that  
slabs of various sizes covering  
a larger cist

Tomb 32

(93)

Tomb 33

Many pots & 9 figurines  
so far.

In side chamber several  
pots appear frags of lead  
wine. A pair of tweezers of  
bronze. A gold gilt  
shenwun standing figure holding  
2 lions

May 26

## Photographs

- Alt. 359K - 1 Chamber of Tomb (22)  
cleaned
- 360 2 Tomb (22) Weather-worn  
of floor of chamber
- 361 3 Stone built cist in Tomb (27)

Thursday May 26

(95)

33 men

## Geometric Terrace

Small force goes over  
digging a trial trench to North

## Filling Trenches

8 men  
All trial trenches filled  
dump day & we began to fill  
W. trench on old Temple Terrace

## Tomb (22)

Drawing finished by DHL  
all pots etc removed. Among  
figures here the most curious  
are 2 chariots - rather  
badly shattered. 2 horses &  
2 drivers

Tomb (25)

We make good progress in  
the three side chambers

(97)

Tomb (32)

Good progress in cleaning  
almost finished for drawing

Tomb (26)

Side chamber finished today  
No cost under platforming stone  
along N wall

Tomb (33)

Good gem fd - showing  
cowork insulating calf fd.  
at N end bronze knife in  
side chamber. The gem fd  
yesterday lay at S end of  
same knife

## Geometric Terrace

Our trial pit made the "terrace" has now been carried further. It reaches a depth of ca. 2.15 below top of North wall. At bottom of this pit just above stone we find along with a few Geometric sherd a piece Mycenean & also a frag of an L & H III (?) figurine.

In the terrace the fill of stones pebbles etc. goes down ca. 70 below top of N. wall. Then brownish earth & stones for 65 more, fairly firm. Then small stones gravel etc for ca. 30; & finally hard brown earth & small stones for 50 or so stones.

Friday May 27

(99)

33 men

## Geometric Terrace

We begin enlarging area to N. of "Terrace" in hope of finding some more bronzes. I allow our pit in terrace to be filled.

## Tomb 17

Drawing finished by D.W.C.  
& pots numbered.  
One new pot discovered

## Tomb 25

Work goes on in all three side chambers.

East chamber - Bronze mirror 16 cm diam. broken but in fairly large pieces. Bones everywhere even at high level. One straight ahead & 2 to right - skull & maxilla. Also a skeleton just inside bronze mirror.

We remove the mirror. Under it find everywhere a dark brown deposit 1 to 2 mm thick. Perhaps remains of leather or wood case for the mirror. We get a few

pieces for analgic. Also some pieces  
of wooden handle.

At inner end of chamber we  
finally get stereo.

A pot fd near it - was intact  
but hit by pick. At a fairly  
high level.

### Central Chamber

We are approaching floor.  
A great many stones here,  
some fairly large - apparently  
fallen from door. We remove  
them. Bones everywhere  
but not in good condition.  
2 pots also appear &  
fragments of others.  
At least 4 skulls.

### West Chamber

Good progress but digging  
is difficult as pile of fallen  
stones is very hard. We are  
approaching floor but have  
fd nothing yet

Mrs Stone arrives by  
evening train from Albany

(101)

### Tomb 27

Drawings by DHC finished  
& pots removed.  
Large cists reveal itself just  
middle down to right

### Tomb 32

Cleaning finished for drawings  
drawings beginning by DHC

### Tomb 33

Cleaning continues. Large  
cist at back of chamber fd  
& most small spherical earthen  
beads begin to appear. 14  
fragments now visible in E  
part of chamber

May 28

The photographs

A H

27 3624 Stone implements in east in Tomb (27)

363 5 Floor of Tomb (33) from SW

364 6 Tomb (26) & door to (31) from above (E)

27 365 1 Dromos of Tomb (25) showing door of central chamber (N)

366 2 Chamber of Tomb (25) showing N & W doors to chambers

367 3 Chamber of No. (32) from East

368 4 Chamber of Tomb (32) from South

369 5 West side chamber of Tomb (25) from East

370 6 Distant view of W. Yerogalan Ridge showing tombs (23) - (35) from S.

Saturday May 28

(103)

33 men

Geometric Terrace

15 men digging in exterior in hope of finding more bronzes.

Tomb (25)

Wall pushed in all 3 chambers

West Chamber

Floor almost reached - On it lies in fragments, a fine L H I spouted jar - fairly large. A small L H I cup further in - also broken.

In extreme NW corner part of a L H I stirrup vase (stirrup) at floor level.

Tomb 25

Central chamber.

Stones cleared out & we clean  
floor of tomb -  
many beads - of paste chiefly  
fluted type - appear, also one  
or two of carnelian.

(105)

Tomb 27

Cleaning of large east cor-  
nices. Found collection of stone  
implements with 4 pounders,  
mallets, & a whet stone. 9  
pieces all told - 5 whet stones &  
4 pounders or girders.

East Chamber

Good progress being made  
This chamber seems to be longer  
than the other two. S E & N  
sides lined out before noon so we  
proceed to dig down

Tomb 32

Drawn by D H C finished  
at noon & tomb cleared of objects  
in afternoon

Tmb (33)

Continue cleaning large dirt  
at back of chamber.  
found many beads - 20 of carnelian  
by 11 AM so many Steatite buttons  
and some good L.H. pottery  
appearing

John Gardner arrived  
by train from  
Athens. Owing money  
on pay roll 24000 L.D.  
left by afternoon train  
for Athens.

Sunday May 29

(107)

Board up to tonight since  
May 14<sup>th</sup> (cf. p. 53)

DHC	RSD	CWTB	EPB	GTH
15	12	14	3	3 =
Total 47				

47  
80  
235  
376  
399<sup>s</sup>

6735  
3995  
10730.

4 Sunday lunches	<u>1 00.</u>
	10830.
3 x 85 for May 30	<u>255</u>
	11085.

13 men at work.

Tomb (25) We go on clearing East side chamber.  
We remove a no. of bones  
& pots appear

In NE corner a polychrome  
pot painted red. Near East  
side (middle) a small cup of  
gray clay has looks like  
gray mica. Close beside  
it has a pot decorated with  
black paint in L H I style (1)

Diggings very hard - fallen  
soaked stones. It looks to  
me as if we clearly had  
two layers of L H II pots  
high (two ft) accompanied  
by bones - at least 4 skeletons  
from 1.00 to 1.40 or so  
above floor of main chamber  
& the second L H I (early)  
& M H II end on the floor.  
The same state of affairs  
I think, in the west chamber.

Another pot appears  
looks like leaf-shaped pot.

Tomb (32)

(109) cleared out during the  
day by Vassili Joannou. He  
finds a large cast at back  
of chamber. Pots in  
the chamber (1) figurine  
seen all to be L H II. But  
in cast we find fragments  
of a vase & it is covered with  
sprinkles

Tomb (33)

L H II works much of  
dag or plain & smooth  
main part of plain. Large  
cast at back not yet done  
on floor of chamber  
alone cast still granular  
Pots ordinary small  
Paste blades

Kurt Müller & Kunze  
visit us during morning  
stay to lunch.

I spent most of day  
packing pottery etc  
for shipment to Wauhpa

Am Stone leaves by  
afternoon train to Wauhpa

Monday May 30

(111)

9 men

Tomb 25 Work going on finishing  
cleaning of east chamber  
The wall painted for  
seems to be similar to  
those in Tomb G (31)

3 more LH I pots  
appear during morning  
small jars like those  
found in Tomb G (31)

Tomb (33)

Being cleaned. Total no. of  
figurines is now 17

CloB leaves for Athos by the  
afternoon train

April 3, 1928

To gilderon for cleaning

1 sword  
1 dagger } from 25 North

1 Saw  
1 tweezers  
1 chisel (broken) } from T 33  
Side chamber

Apr 11

1 mirror  
1 dish  
1 leaf-shaped dagger } T 29

Thursday April 5, 1928

(115)

Photographs

1. Jar # 255 from Tomb (30) d. 9 1 sec.
2. Mattp. jar 386 from T. (25) d. 9 1 sec
3. L.H.I cup 216 from T 18 d 9 1 sec
4. canteen L.H.I. 226 - T 18 d 9 1 sec
5. Chariot 415 from T 22 d 9 1 sec
6. n n n n d 9 1 sec
7. n n n n d 9 1 sec
8. Hedgehog d 9 1 sec
9. " " bright d 12 1 sec
10. Stump base 237 " d 12 1 sec
11. n n 244 " d n 1 sec
12. Beaker 234 d 9 1 sec

PAGES 116 - 121

NOT INSCRIBED

Antimonte & Mye.

Hotel inclusive  
June 18-23

Kosta & Orestes  
+ donkey

Pantelis

Car Combi

RR Fare Ath-Cor & ret.  
n Mye. Cor

900.

1500.

600.

398-

225.

191.

45.

3821.

750

3076

Drs.  
Ded 1/2 Hotel bill  
(= CWPZ's Share)  
plus CWTs

Argine Harem June 18-23, 1930. (123)

DHC & CWTs - train to Corinto  
motor to Mycenae - arr  
evening June 18

June 19 to Heraean w. G Alexopoulos  
+ Kosta & Orestes Taxis

June 20 To Heraean with G Alexopoulos  
Pantelis Christopoulas, Kosta & Orestes

June 21 To Heraean with Pantelis,  
Kosta & Orestes

June 22 To Heraean with Pantelis  
Kosta & Orestes

DHC left by evening train  
for Assos

June 23 CWRB left by morning  
train for Corinto.

(128)

Yerogálaro = yerogalári  
= stone sheep fold  
galári = place for milking

pacapá - small division b/w fields

pigótpaxos - abrupt line of rock


(127)

T 17

- Machine readings:
- 1 outer end of dorms
  - 2 floor of chamber
  - 3 surface of ground at door

2.33  
3.31  
1.01

slope



T 18

- Machine readings:
- 1 outer end of dorms
  - 2 floor of door
  - 3 surface at door

3.05  
3.55  
1.80

T 19

- 1 outer end of dorms
- 2 floor of door
- 3 surface at door

1.85  
2.48  
1.68

T 21


- 1 outer end of dorms
- 2 floor of door
- 3 surface at door

1.18  
2.51  
0.26

T (WI) Dromos ca. 6 m. long

T (1) ca. 22 m. North of  
chamber of T (3a)

T (1) chamber to beginning of  
dromos of T (WI) ca. 6 m.  
Direction NE



SW face drops off  
ca 1 to 2 m.

June 20


129

Ridges - Heraeum & NW -

1. Heraeum ridge - Acropoli - Kastro.
2. next ridge beyond rumator kastro  
(Yerogalano) = devilli VTEBIDI
3. next ridge W Yerogalano =  
Yerogalano Teopasapo  
The ravine is the real Yerogalano  
with caves sheep fold above
4. Before tomb ridge - this region is  
called Anoikia  
"Aroig"
5. Kephalaia - as before. They say  
there was once a spring on  
W side of hill in hollow

Puketown Olds W of 2<sup>nd</sup> Temple

(131)



Basement rooms as  
at Mycenae -  
steep slope

Bukitonic walls below Cyclopean Terrace wall.

Wall analysis - small house "westernmost  
under back wall"

(153)

18 piece mptd yellow Myc. types


incl. 1 cyclo. stem

3 pt bits L H III?

3 black glazed bits L H III

4 coarse nondescript

All Myc. I think



### VII Part of a house.

1 room & part of another fallen away to N.  
to S. is a room & shed between houses rock. rock roughly cut perhaps a porch in front of VII


Neolithic Area "Pyres"  
ca. 14 m. SE of Tomb 14  
ca. 95 m. NW of Neolithic  
Graves.

Altar in front of 2<sup>nd</sup> T.

(137)

ca. 17 m long. <sup>width</sup> top where rock  
appears, but traces of cutting in  
rock go on for ca. 4 m more.

not exactly parallel to facade  
of Temple.




It contained 2 rows blocks may be  
in place above flats - very rough  
look reused. Correspond in level  
with it or course below top of  
Temple platform as measured at  
each end.


trunk 108

Houseworks. - 60 wide  
65 high

Street ca 1.55 - wide




T. (13) levels for section (139)




machine reads

1	3.05
2	3.00
3	2.72
4	1.93
5	1.09




T (44)




machine reads


1	3.225
2	4.79
3	6.13
4	0.25



T. (1)




T (22)



141

House on N. slope of Keptolani

(143)



2.9 + 5.8  
a. 9


~~8.10~~



section

steepish slope with shelf-like cuttings in native rock

Sm. house - must be basement  
rooms as at Mycenae



	Photographs of A H Small plates	Objects from Tomb 13x18 cm.	(147)
601	Two Neolithic pots	198, 197	
602	Pots from M H Graves	XII, XV & XXV	
603	" " "	XIII & XXVI	
604	" " "	XVI + XVII	
605	" " "	XVIII	
606	" " "	XIX	
607	" " "	XXI	
608	" " "	XXIV & XXXI	
609	" a "	XXVIII & XXX	
610	Pot 838 from Tomb	VIII	
611	Pots 811, 834, 835, 842, 843	Tomb VIII	
612	" 833, 831	" "	
613	Pot 888	Tomb XXII	
614	Pot 1048	Tomb XXV	
615	Pots 455, 457, 883	" "	
616	Pots 453, 499, 500, 454/495, 870, 496	" "	E
617	" 885, 439, 884, 1123, 882	" "	
618	" 456, 457, 490, 875/887, 458, 886, 874	" "	
619	a 385, 431	Tomb XXVI	
620	" 1168, 1169, 1170, 1167	" "	
621	" 1175, 1185, 1184, 1172/1166, 1176, 1171	" "	
622	" 1148, 492, 1147/491, 1146, 1122	Tomb XXVII	
623	" 1151, 1153/1152, 1149	" "	
624	" 493, 1150/1198	" "	
625	Stone implements	" "	
626	Pots 337, 876, 1115 (wrong) / 336	Tomb XXVII	
627	" 1156, 425, 423/1160, 1161, 878	Tomb XXIX	
628	Figs 417, 419, 418	" "	
629	Pots 1154, 424	" XXIX	
630	9 pots, 1 fig., 1 table (421)	" "	
631	Pots 434, 422/1165, 1164	" "	
632	" 1157, 1158/494	" "	
633	" 1178, 1177/435	Tomb XXXII	
634	" 873, 437, 436/1193, 1180, 1179	" "	
635	" 1181, 1182/fig 1100	" "	
636	Pot 484, 1092	Tomb XXXIII	
637	" 1087	" "	
638	" 1094, 1072, 1070/1071, 451	" "	
639	" 1089, 1091/1093, 1090, 1062	" "	
640	" 1064/1061, 1065, 1063	" "	

AH

- 641 Fig. 483  
 642 Sixteen TC figs  
 643 Pot 614 Dromos  
 644 Pots 612, 613/674, 549, 548  
 645 { 9 pots: 675, 646, 677, 644, 645 }  
 { 642, 643, 676, 681 }
- 646 Pot 670, 658/648, 649, 654/657, 688, 656  
 647 " 678/679, 682, 680  
 648 " 726, 862, 1055/1054, 861, 826  
 649 " 659, 731, 658/686, 666, 653  
 650 " 696, 1056  
 651 " 536 -  
 652 " 540  
 653 Fig. 527  
 654 Five pots, from TC figs  
 655 Fig. 1145  
 656 Pots 532, 534/508, 533, 535  
 657 Pots 527, 1059, 563/595, 523, 594  
 658 " 505, 615, 530, 504/51x TC figs  
 659 Pots 703, 702  
 660 " 708, 707, 710/706, 711, 705  
 661 " 714, 712, 713/716, 704, 725  
 662 " 717, 720, 709/719, 715, 718  
 663 " 724, 721  
 664 " 722  
 665 " 746  
 666 TC figs  
 667 Pots 506, 510, 509/599, 507  
 668 " 1119/1120, 864  
 669 " 542  
 670 Pots 545, 1118, etc. (Nine pots)  
 671 " 776, 790  
 672 " 774, 791, 775/783, 1103, 1107  
 673 " 787, 741, 788, 740, 786/784, 789, 785  
 674 " 792, 739, 782/779, 777/781, 780  
 675 Nine pots - 1113, 1105, 1110, etc.  
 676 { Pots 1205, 1204, 1203  
 " 911, 912 }

Tomb XXXIIII

Tomb XXXIV

" "

Tomb XXXV

Tomb XXXIV

Tomb XXXVI

Tomb XXXVII

Tomb XXXVIII

Tomb XXXIX

Tomb XL

Tomb XLI

Tomb IX

Tomb XI

AH

- 679 { Nine pots: 801, 902, 802, 903, 904 }  
 { 803, 905, 906, 855 } Tomb XLII  
 680 Pots 900, 901  
 681 { " 804, 899, 860 }  
 { Figs 798, 799, 800, 797 }  
 682 Pots 856, 849/857, 907  
 683 " 620  
 684 " 866/922  
 685 " 930, 958  
 686 " 979, 938/959  
 687 " 935, 934, 944/933, 937, 936  
 688 " 916, 950/951, 948, 949  
 689 Figs 956, 947/955, 946, 867  
 690 Pots 989, 988, 980/978, 990, 977, 976  
 691 " 1020, 1019/996  
 692 " 1034, 1033/1038, 1036  
 693 " 1035, 1034/997  
 694 " 999  
 695 " 1043, 1047, 1045/1041, 1046, 1042  
 696 " 641, 766/767, 640  
 697 " 992, 993  
 698 { Nine pots: 606, 601, 602, 604, 603 }  
 { 608, 995 }  
 { 605, 607 } Tomb XLVI  
 699 Pots 600, 520  
 700 " 617, 616  
 701 " 552  
 702 " { 598, 553, 557 }  
 { 554, 619, 556, 618, 555 } Tomb XLVII  
 703 " 732, 768, 733  
 704 " 736, 735, 737  
 705 " { 1124, 728, 846 }  
 { 734, 1121 } Tomb XLVIII  
 706 " 847  
 707 " 1125/1126  
 708 " 1129, 1139/1127, 1128  
 709 " 894  
 710 " 895, 892/893, 809  
 711 " 984, 982  
 712 " { 794, 1196, 1193, 1186/1185, 807, }  
 { 1195, 1197 } Tomb L1

AH

- 713 Ivory statuette - front view  
 714 " " side views  
 715 " " back view  
 716 Pot 889 Tomb LII  
 717 Pots 914, 810, 845, 808 " "  
 718 " 414 inscribed from Geometric Terrace.  
 719 " 512, 511, 863 from Roman Graves  
 720 " 868, 871 / Fig. 742, 760. Miscellanea

Large plates 18 x 74 cm.

- 721 Pots { 836, 844, 813, 837 }  
 { 826, 828, 827, 812 }  
 { 825, 824, 829, 830 } Tomb VIII

- 722 Pots { 821, 823, 815 }  
 { 820, 839, 840, 832 }  
 { 822, 818, 816, 841 }  
 { 819, 1095, 814, 817 }  
 Pots { 442, 447, 446, 443 }  
 { 445, 448, 449 }  
 { 444 } Tomb XII

- 724 Pots 384, 382, 380, 381  
 383, 343, 344, 345, 342 } Tomb XXVI

- 725 Pot 1199 Tomb XXVI

- 726 Pots { 341, 330, 1141, 340 }  
 { 334, 1137, 1136 (map) } { 1132, 1135 } Tomb XXVIII

- 727 Pots { 346, 413, 1140 }  
 { 1130, 331, 1143, 332, 1134 } { 1131, 1142, 339, 333, 335 } { 338, 877, 1098, 1099, 1144 } Tomb XXVIII

- 728 Pots 1049, 1050 / 350 Tomb XXIX

- 729 Pots 347, 348 / 351, 349 Tomb XXIX

AH

- 730 { Pots 1083, 462, 463, 1081 }  
 { 1085, 485, 1080, 1078 } { 1082, 1084, 1079 } Tomb XXXIII

- 731 { Pots 461, 471, 470, 1068, 481, 1066, 469 }  
 { 482, 1067, 1069, 1076, 1073, 1075 } { 1074, 472, 1077, 476, 480 } Tomb XXXIII

- 732 Pots 550, 551 Tomb XXXIV

- 733 { Pots 647, 672, 669, 667 }  
 { 652, 650, 622, 668, 651 } { 684, 623, 1052, 673 } { 683, 665, 664 } Tomb XXXIV

- 734 { Pots 663, 1053 }  
 { 660, 627, 687 } { 671, 625, 685, 661 } { 662, 624, 621 } Tomb XXXIV

- 735 { Pots 597, 528, 525, 561, 611 }  
 { 562, 529, 1058 } { 564, 596, 524, 526, 593 } Tomb XXXVI

- 736 { Pots 693, 727, 689 }  
 { 690, 749, 728 } { 695, 755 } Tomb XXXVII

- 737 { Pots 701 }  
 { 754, 753, 747 } { 757, 752, 750 } { 751, 745 } Tomb XXXVIII

- 738 { Pots 772, 770, 1101 }  
 { 793, 771, 1102 } { 773, 769, 778 } Tomb XLI

- 739 Pots 941, 940 Tomb XLIII

- 740 Pots 891, 920, 919 } { 928, 890, 921 } Tomb XLIII

A. H

- 741 { Pots 915, 917, 925 }  
       { 924, 918, 865, 923 } Tomb XLIII
- 742 { Pots 926, 932, 929, 927 }  
       { 939, 931, 965, 943, 942 } Tomb XLIII
- 743 { Pots 963, 961, 962 }  
       { 954, 964, 991, 957 } Tomb XLIII
- 744 { Pots 1015, 1014, 1018, 1013, 1012, 1016 }  
       { 1017, 1039, 1010, 1011 } T. XLIV
- 745 Pots 1024, 1025 Tomb XLIV
- 746 { Pots 1008, 1001, 1004, 1021, 1022 }  
       { 1000, 1006, 1007, 1002 } T. XLIV
- 747 { Pots 969, 973, 972, 631, 968 }  
       { 634, 974, 975, 966, 967, 633 }  
       { 971, 638 } T. XLV
- 748 { Pots 983, 981 }  
       { 986, 985 } Tomb L
- 749 { Pots 1192, 1190, 764 }  
       { 805, 761, 1189 }  
       { 1194, 1188, 806 } T. LI
- 762, 1191, 763
- 750 " 1206 - larnax - Tomb XVII
- 751 Small objects - Diomos - Tomb ①
- 752 " " - chamber - " "
- 753 " " Diomos - Tomb ②
- 754 " " Door - " "
- 755 Ivorys - Chamber - " "
- 756 Ivory & bone - " "

A H

- 757  
 758 S  
 759  
 760  
 761  
 762  
 763  
 764  
 765  
 766  
 767  
 768  
 769  
 770  
 771  
 772  
 773  
 774  
 775  
 776  
 777  
 778  
 779  
 780  
 781  
 782  
 783  
 784  
 785  
 786  
 787  
 788  
 789  
 790  
 791  
 792  
 793  
 794  
 795  
 796

S = small plate

- Amber, paste, flint, obsidian - Chamber - Tomb 6 ②
- Carmelian - " " "
- Gold, etc. " " "
- Bronze objects - " " "
- Paste beads - chamber - Tomb ③
- Gold & carnelian " " "
- Amber, bone, steatite " " "
- Bronze frags, arrowhead " " "
- Daggers - 2 (inlaid) " " "
- " other side " " "
- " frags + mesomph phab " " "
- Small objects - Tomb ④ ⑤ ⑥
- " " " " "
- Knife, cleaver, tweezers, arrowhead " Tomb ⑩
- 3 spearheads " " "
- Wool from " & lead " " "
- Small objects - Tomb ⑪
- " " " Tomb ⑬
- Beads Tomb ⑫ & Neolithic beads
- Small objects - Diomos & chamber Tomb ⑭
- " " cists 1 & 2 " " "
- " " floor of chamber " " "
- gold inlaid dagger " " "
- " " other side " " "
- Cleaver, etc. - Tomb ⑮
- Misc. objects M I I Grave IV
- Bronze from Shaft E XIX
- Miscell. " " "
- Bronze from Geometric Period
- Mic. bronze & iron dagger from E XIX
- Egyptian door from pit tomb ⑯ pyxis from over ⑮
- Small objects - Tomb ⑰
- " " " Tomb ⑲
- " " " Tomb ⑳ ㉑ + ㉒
- " " " Tomb ㉓
- Spearhead, mace T. ㉔ E ch. (clamshell from Wch)
- Dagger, disc. sk. Main Ch. T. ㉕ Bone pin frags T. ㉖
- Sword & dagger & mace N ch. T. ㉗
- Beads N. ch. Dagger Wch. T. ㉘

(153)

AH

- 797 { T. (26) Diomos, arrowheads & lead. - Weist, bone bronze &  
steatite. N. cist & bottom  
798 T (26) ch. Shells etc.  
799 T (26) Side ch. Platform - arrowheads, etc.  
800 " " " floor  
801 " " Dagger, gold ear, bronze, spearhead - platform side ch.  
802 Ivory frags. T (26) side ch.  
803 S Small objects T. (27)  
804 " " Tomb 28  
805 Dagger & mirror T. (29)  
806 Frag. of wooden box T. (29)  
807 Small objects from cists T. (29)  
808 " " Diomos, bone heap, sifted T. (29)  
809 S Bronze piping pan from niche T. (29)  
810 Comb beads, buttons " " "  
811 Small objects Tomb 6 (30)  
812 " " (32)  
813 Bronze & seals, Sidech Tomb (33) seal from sifting  
814 Small objects - floor Tomb (33)  
815 Beads, carnelian necklace 3 rosettes - Cist 2 T (33)  
816 S 13 buttons cist 2. Tomb (33)  
817 Knife, bone dice, bronze ch & diomos Tomb (34)  
818 Small objects - right heap " "  
819 Beads, buttons, arrowheads, bronze pins Niche T (34)  
820 S Cist I sarcoph., 1 button. II 1 button I sarcoph., 1 button " "  
821 S Small objects T (35)  
822 Knife, tweezers, bronze pins. T. 1 button - steatite, bone T (36) floor  
823 Paste beads - large - floor T (36)  
824 " small " " "  
825 Small objects Cist T. (36)  
826 Knife from Diomos cist, dagger from chamber T (37)  
827 Beads, bone, steatite buttons. from heap " "  
828 Ovoid pin upper layer. Bottom, shell, wire, pectoral. Gemology T (37)  
829 Long sword T. (37)  
830 Small objects NE quarter & sifting T. (38)  
831 1 button Diomos. bronze casing 5th heap, etc. " "  
832 Knife & cleavers T. (38)  
833 S Small objects Tomb (39) & (40)  
834 S " " from Diomos Tomb (41)  
835 " " Chamber - right & centre " "

S = small plate

AH

- 836 837 838 839 840 841 842 843 844 845 846 847 848 849 850 851 852 853 854 855 856 857 S 858 859 860 861 862 863 864 865 866 867 868 869 870 871 872 873 874 875
- S = small plate (155)
- Small objects chamber - rear. Tomb (41)  
" " Cist I left " "  
" " II right & clearer " "  
2 daggers, knife, tweezers 2, pins Tomb (42)  
Bronze mirror, steatite buttons. Bone pins " "  
Beads, octopuses, etc. " "  
Large string  
Dagger<sup>543</sup>, cleaver, disc 545 Tomb 43  
Dagger 546, dagger 545, knife 545 " "  
Daggers 546 broken, spoon 549, phiale 540 " "  
Beads, carnelian, paste, crystal, ivory disc " "  
Steatite buttons 29 + 7, Ovoid. amber, shell " "  
Diomos, ch. high neck, Laminated Tomb (44)  
Beads, gold, stone, paste. Rough heap lower " "  
muscat?  
Small objects Tomb (45) (46) & (48)  
Gold ring etc. Cist VIII Tomb 49  
Cist VIII. beads, buttons etc. Cist IV. Remnants 1. (49)  
Cist I. amber, arrow, buttons. Diomos door. Sifting " "  
2 beads, bronze ring, buttons. T (50) Knife, etc. T. (52)  
Small objects Tomb (51)  
Dagger & tweezers - T. (51)  
Beads from right niche T. (51)  
Right niche 2 seals, etc. in 2nd Crystal head, Diomos 3 buttons. T. (51)  
Cist III beads buttons. Cist VI carnelian paste beads T. (51)  
Small Objects T. (51) M H Graves XIIII shells, etc. XVIII bronze heads  
M H Graves XX shells & beads  
" " Graves XIV Sherds, xxvi buttons, xxv knife, xxvi ring & pin  
Neolithic. Ovoid & bead longspikes. Ovoid flat, arrow. W Young  
Liberation Table T. (44) from above  
Pot 1212 & Sherd Diomos T. (44)  
Neolithic sherds - coarse - handles, bags  
" " " plastic bands, spiral, rope & coarse  
" " " incised  
" " " polychrome  
E H sherds - coarse  
" " " - patterned  
" " " - incised, etc.  
M H sherds - Minyan, etc  
" " " - Matt painted

A H	S = small plates	A H	(17)
876	Neolithic ware - coarse - W Yirogalano	902	Pots 181, 182/187, 180 T. ②
877	" - drip patt. "	903	{ 114, 121, 125 } Tomb ③
878	Palace style sherds - Dromos T. ④	117, 112 151	
879	" " "	904	{ Pots 135, 122 } Tomb ③
880	Stone implements T. ②	{ Figs 136, 141 133, 132, 97 }	
881 S	Neolithic pots 1208 + 1211	905	{ Pots 142 } Tomb ③
882 S	Water jar 1213 from U. IV	113 115, 111, 154	
883 S	Bronze found pair - side view - T. ⑥	906	{ 124, 138, 130 } Tomb ③
884 S	Liberation (table) " - T. ④	159, 155, 140	
885 S	Cylindrical 271 T. ②	120, 123, 119	
886	Pots 852, 854, 897, 908, 909	134, 116, 118	
887	" 850, 896, 859, 858, 851, 853	907	{ Pots 67 T. ⑩ } 38 T. ⑬
888	{ 1040, 1030, 1044 1027, 1028, 1032, 1029 1023, 1026, 1031 }	89, 88, 90 87, 92, 91 94, 95, 93	T. ④
889	{ Pots 398 T. ⑦ 1209 T. ④ Dromos	908	{ Pots 36, 109, 35 from T. ⑤ } ? WI
	199, 200, 450 T. ②	909	{ Pots 31 } 33, 32, 98 T. ⑥
890	{ Pots 578, 576, 577/571, 574, 572, 572/	910	{ Pots 110, 86, 85 } 100, 84, 99 T. ⑦
	570, 573, 575, 569	911	{ Figs 68, 69, 70, 73, 74, 75, 77, 80 } { Pots 72, 83, 79 } 102, 101 T. ⑩
891	{ Pots 196, 1210/147, 137, 148/	912	{ Pots 82, 81 } 76, 65, 64 T. ⑩
	146, 150, 149	913	{ Pots 71, 78, 66 } 27, 28, 29 T. ⑪
892 S	Pots 145/144, 152, 143	914	{ 25 } 20, 21, 23 T. ⑪
893 S	Pot 193 T. ②	915	{ 15, 18, 16 } 14, 19, 11 { 13, 17, 12 } Pots 51, 52/49, 50/ 39, 37 T. ⑬
894 S	" 194 " "		
895	{ Pots 172, 168 } 163, 176, 159 T. ②		
	158		
896	{ Pots 173, 161, 170 } 186, 160, 185 T. ②		
	167, 165, 188		
897	Pot 178 Tomb ②		
898	{ Pots 175, 184 } 190 T. ②		
	169		
899	{ Pots 166, 171 } 191 T. ②		
900	Pot 177 Tomb ②		
901	{ " 174, 189 } 182, 183, 179 T. ②		
	162, 164		

S = small plate

- AH  
916 { Pots 42, 46, 62, 43 } Tomb 13  
     { 40, 41, 63, 45 }  
     { 47, 48, 108 }  
 917 { Pots 1214, 1212 } Tomb 14  
     { 58, 57, 56 }  
     { 59, 60 }  
 918 { Pots 103, 153 } Tomb 15  
     { 105, 106, 104 }  
     { 157 }  
 919 { Pots 5, 3, 4 } Grave I  
     { 2, 1 }  
 920 { Pots 9, 10 } Grave II  
     { 53, 54, 55 } Grave IV

- 921 S Pot 1009 - Tomb 44  
 922 S Chain from T W.I. points base  
 923 S " " " side view  
 924 S Egyptian bone fig. from Exxix 2 views  
 925 S Sundial from Exxix  
 926 S " " " another view

- Small plates by Petrucciis
- 927 Pots 201, 202, 203, 204, 205 T. 16  
 928 Pots 395-7, 403-5, 497, 498, 881 T. 17  
 929 Pots 371-3, 399-401, 406-409 T. 17  
 930 Pots 412, 440, 441 T. 17  
 931 Pots 388, 389, 402, 879, 880 T. 17  
 932 Pots 390-394 T. 17  
 933 Pots 206, 270 T. 18  
 934 Pots 214-219, 221-226 Tomb 18  
 935 Pots 207-213, 387 Tomb 18

- AH  
936 No. 274-276, 282-287 Tomb 19  
 937 No. 278-281 " 19  
 938 Pots 227-230 Tomb 20  
 939 Pots 231, 233, 267, 268 Tomb 21  
 940 Pots 235, 237-241, 258, 270, 271 Tomb 21  
 941 Pots 259-264, 266, 273 Tomb 21  
 942 Nos. 352-357, 360, 361, 415 Tomb 22  
 943 Nos. 369, 370, 410, 411 T. 22  
 944 Nos. 358, 359, 362-368, 416 Tomb 22  
 945 Pots 290, 298, 299, 302, 306, 308 } 312-315 } Tomb 24  
 946 Pots 296, 297, 304, 307, 309, 310, 328 T. 24  
 947 Pots 288, 289, 291, 292, 303, 316 T. 24  
 948 Pots 293, 295, 318, 319, 320, 322, 325, 329 T. 24  
 949 Pots 294, 305, 311, 317, 323, 324 Tomb 24  
 950 Pots 321, 326 Tomb 24  
     414 (Inscriptions), 438 head of sphinx - Geometr. Temple  
 951 Pots 374, 375 Tomb 25  
 952 Pots 376, 377, 378, 379 T. 25  
 953 Pots 488, 489 Tomb 25  
 954 Pots 452, 869, 872 Tomb 25  
     " 432, 433 Tomb 26  
 955 Pots 249-255, 300, 301 Tomb 30

AH Large plate

956 Pots 246, 243<sup>1443</sup>, R 42, 245 / 236, 248, 272, 284 /  
247, 265, 269, 286 / 232, 257, 286 - T (21)

(161)

PAGES 161 - 169

NOT INSCRIBED

## Pots in Tombs.

Tomb #16

Chamber empty — 1 skeleton <sup>165 cm</sup> abv. floor.  
5 pots in cists. — all small.  
skulls, children's —

Tomb #17

Total number of pots 37  
" " " skulls 13 (12 broken)  
c. 70 abv. fl. 4 pots  
c. 40 (vol w. base of sarcophagus) 8 pots, ashes in one  
Floor level or heap on fl. 25, 1 knife  
14 whorls.

Tomb #18

71 pots (22)  
4 skulls  
54 paste beads  
14 slate whorls  
1 t.c. whorl.

<sup>39cm + 8 cm</sup> → Tomb #19 (Mycenean level)  
6 → 9 pots  
5 animal figurines  
Great quantities of beads

Tomb #20

4 pots other sherds  
skulls in chamber? ? (2)  
" " cist 2. w. paste  
ornament: <sup>F3.27</sup>

Tomb #21

37 pots  
1 stone ball  
7 + skulls  
7 pots in cist to left  
<sup>3.0</sup> on floor & heap (parts of pots  
in heap found in left cist)

Tomb #21 cont.

1 child's skeleton, abv. fl.  
? skulls in cists; ? on floor.

Tomb #22

15 pots all on floor  
1 full skeleton on floor  
8 animal figurines  
2 chariots  
2 extra fin. heads.  
skulls 1 on floor  
7+ in cists

Tomb #23

Animal bones only.

Tomb #24

48 pots  
39 on floor  
4 in cists  
9+ skulls  
7+ in cists., on floor.

Tomb #25

(not seen when  
complete; may change.)  
Main chamber

12 pots  
4 .55m. above fl. level. + bronze disk  
18 on floor  
2' skulls above floor level.

## West chamber

8 pots, 5 above fl. level  
3 + knife on floor

172.

Tomb # 26 (see. 31)

3 pots (see dromos)  
2 on floor, 1 in cist.  
2 skulls (in cists)

Tomb # 27 (sub. to change when washed + mended)  
9 pots  
8 on floor, 1 in cist  
10+ skulls  
5+ cists ? on floor  
1 figurine  
8 stone implements in cist.

Tomb # 28 (sub. to revision)  
33 or 34 pots where washed.  
9 skulls  
2 figurines  
1 bronze dagger.

Tomb # 29 (sub. to revision)  
13 skulls + bone heaps.  
1 on bed  
12 in cists.  
35 ± pots  
6 on floor, 1 on bone heap  
28 in cists  
also on floor  
1 bronze knife  
1 " mirror  
1 ivory comb, 1 marble comb.  
in cists  
3 female figs + animal, 1 bed (t.c.)

(173)

Tomb # 30

10 pots  
5 skulls



Tomb # 31

12 pots, 1 lid.  
12 arrow heads  
1 gold ring  
1 " bar  
2 bronze daggers  
3 skulls

Tomb # 32 (subject to revision)  
12 ± pots all on floor (14)  
12+ skulls  
1 figurine

Tomb # 33

17 figurines



from bone heap

		Tomb	(25)	No. 18	(177)
487	Feeding bottle L H III	"	"	"	
488	Large hole mouth jar, spout L H I	"	"	20	
489	Tea cup w. double base L H I	"	"	21	
490	Unpld. jugs w. 3 holes	"	"	28	
491	Small bird askos L H III	"	(27)	11	
492	Unpld. jugs w. 1 hole	"	"	6	
493	w. handleless cup	"	"	"	2
494	Small squat jar; handle less	"	(29)	"	13
495	• tall jar w. 2 holes L H I	Tomb	(25)	"	44
496	Cups on low stem Gray Minyan	"	"	"	45
497	Coarse handleless cup (fragm)	Tomb	(17)	"	29
498	" " "	"	"	"	33
499	Large matt painted jar	Tomb	(25)	"	37
500	Stem of goblet = lid of 499	"	"	"	"





## Fig. of animal

- 282  
283  
284  
285  
286  
287 Tiny Stirrup vase  
288 Unpainted jug w. 1 hole  
289 " Jfr " 2 "  
290 " jug " 1 "  
291 "  
292 " jar on tall stem  
293 Small jar with spont  
294 Shallow cup w. spont  
295 Unpainted cup no holes  
296 Small "amphora"  
297 " Stirrup vase  
298 "  
299 "  
300 Stem of goblet  
301 Plain cups  
302 Unpainted cylix  
303 " jug w. 2 holes  
304 Jug w. good black pattern  
305 Small red ptd amphora  
306 Red saucer w. 1 hole  
307 Stirrup vase (broken)  
308 Small coarse cup unpntd, 1 hole(missing)  
309 Large jug w. Spont  
310 Red jar w. 2 holes  
311 Unpainted cylix  
312 Large jug w. bands high neck  
313 Amphora w. red decoration  
314 Small stirrup vase (gray)  
315 " cup w. 2 holes  
316 Unpainted jar  
" amphora  
318 " saucer w. 1 hole (frag)  
319 Coarse tray in (fragment)  
320 Tiny squat jar  
321 Unpainted Cylix w. 1 hole  
Small w. saucer

## Tomb (19) No 3

- " " " 4  
" " " 10  
" " " 7  
" " " 8  
" " " 9  
Tomb (24) " 23  
" " " 22  
" " " 14  
" " " 19  
" " " 20  
" " " 25  
" " " 26  
" " " 21  
" " " 13  
" " " 7  
" " " 9  
" " " 12  
Tomb (30) " 4  
" " " 2  
" " " 27  
" " " 36  
" " " 32  
" " " 11  
" " " 15  
" " " 16  
" " " 2  
" " " 1  
" " " 30  
" " " 10  
" " " 5  
" " " 8  
" " " 4  
" " " 29  
" " " 38  
" " " 18  
" " " 17  
" " " 24  
" " " 47  
" " " 28

## 241

- Shallow cup w. 1 hole  
Small shallow cup w. 1 hole  
Tiny crater-like jar w. 2 holes  
Small tall stirrup vase  
" hedge-hog pot  
Tiny crater w. 1 hole  
Stirrup vase  
Unpainted shallow cup w. 1 hole  
Leaf-shaped jar (Good) Tomb (30) " 3  
Small leaf-shaped pot (dot pattern) " " " 5  
Squat jar w. 1 hole (Amphorae)  
Plain straight 3-sided cup no handle " " " 10  
Small goblet + plain outside black inside " " " 11  
Cup of Vasen Shape " " " 13  
Large spherical bottom jar w. 3 holes " " " 1  
Large jug w. bands Tomb (21) " 16  
Large jug w. red spirals " " " 17  
Shallow cup or dish w. 1 hole " " " 9  
Unpainted goblet w. 2 holes " " " 39  
" coarse cup no. " " " 40  
" yellowish " " " 27  
" small " " " 43  
Small leaf-shaped pot red pattern " " " 38  
Shallow cup w. white dots on rim " " " 37  
Part of a jar (top missing) " " " 20  
Jug w. bands " " " 44  
Small stirrup vase " " " 11  
Unpainted cylix " " " 12  
" " " (big shape) " " " 22  
Small cylix (painted) " " " 4  
Very large unpainted cylix " " " 6  
Small squat jar (leaf shaped) " " " 34  
" " " " " " " " " " " 45  
Unpainted jar w. 2 holes (missing) Tomb (19) " 1  
Small fragmentary stirrup vase " " " 6  
Tiny jug w. red bands " " " 2  
Small jug (red & red) " " " 5  
Small amphora " " " 11  
Squat jar w. angular profile " " " 12  
Squat stirrup vase " " " 13  
Fragmentary stirrup " " " 14
- 242  
243  
244  
245  
246  
247  
248  
249  
250  
251  
252  
253  
254  
255  
256  
257  
258  
259  
260  
261  
262  
263  
264  
265  
266  
267  
268  
269  
270  
271  
272  
273  
274  
275  
276  
277  
278  
279  
280  
281

## Inventory of Pottery 1927 Campaign

201	Squat jar w angular profile	Tomb 16 No 1
202	Small plain jug w. bands	" " " 2
203	Shallow cup w 1 handle	" " " 3
204	Small cup without handle	" " " 4
205	Tiny stirrup vase	" " " 5
206	Small 3-handled jar	Tomb 18 No. 1
207	Small cup w. 1 handle (black)	" " " 2
208	Small red jug	" " " 3
209	Plain jug w. 2 handles	" " " 4
210	Jar without handle (e - through's ref.)	" " " 5
211	Plain jug w. 1 handle	" " " 6
212	Squat jar w. floral design	" " " 7
213	Small squat jar i. floral design	" " " 9
214	Small jug w. spirals	" " " 10
215	Striped goblet on stem	" " " 12
216	Cup of graphio shape w. spirals	" " " 13
217	1-handled saucer w. floral patt	" " " 14
218	Plain 2-handled cup w. high handles	" " " 15
219	Jug without holes. bands	" " " 16
220	Small loaf-shaped pot	" " " 17
221	1-handled saucer w. zebra or incised	" " " 19
222	1 " saucer w. line + dots (broken)	" " " 20
223	Shallow saucer w. 1 hole	" " " 22
224	Small jug w. fishnet pattern	" " " 24
225	Tiny black askos	" " " 25
226	Water flask w. 2 handles	" " " 27
227	Large stirrup vase	Tomb 20 No. 1
228	Small " "	" " " 2
229	Squat jar w. stripes & perpendiculars	" " " 3
230	Small cup w. 1 handle	" " " 4
231	Large L-H III crater	" " " 13
232	" unpainted jug w. 1 hole	" " " 26
233	Jug w. 1 hole (unpainted)	" " " 10
234	Beaker w. squat r w. holes	" " " 24
235	Cup w. 1 high hole. dotted rim	" " " 7
236	Shallow cup w. 1 hole	" " " 18
237	Small stirrup vase	" " " 8
238	Unpainted cyl like	" " " 1
239	Small red loaf-shaped jar	" " " 2
240	Small jug w. 1 hole	" " " 3

George Papadopoulos

18

George Alouhos

19

Vassilis Joannou

20

Nikos Manos

Ioannis Papadopoulos

Georgios Barali

Evangelis Kalichas

Dimitrios Skinas

Makis Yannikos

Dimitrios Skinas of Phichtia  
Stone smasher

Nikolaos Antonopoulos  
married Fair Helen

Tipto q. Alacopulos

(187)

128068.75

500.



19 26.6"

✓ 9628.10  
19 25.60  
7702.50

On s. side of road near 29<sup>th</sup> kil stone  
between Tripolis & Megalopolis is a hill  
called Phoukalikara. To N. is village  
of Sialesi to S. Tsiaopoga.  
On the hill some pottery also  
tracing of Hellenic walls.

79135

20000

240000

4309.  
125443

May 20

May 26

Ret by Cook

May 14	Payroll May 9-14 Guard for 2 yrs Dinysalis 2 sieves 14% other hydrochloric 11 handles 6 knives 11 picks uprooted Bengme Supplier chiefly 2 men working Adv to Niko Chauffeur concert Yannakis Bill traps & supplies To Niko Cook on acct String of 50 bags	5421438 13992 675. 85. 74. 261. 165 150 225 135 555 310.50 750. 233. 750. 112. 13075.50 250 2000 1015. 88892.85 9507. 60. 15. 10 6680.60 200. 1100. 750. 5. 107219.95 3000. 62. 691. 25. 3760. 11605.50 195. 634.50 Service Advance to Nander Coffee bacon 128068.70
May 21	Payroll Doctor savings for Panteli Niko Cook advance Niko Chauffeur	13075.50 250 2000 1015.
May 23	Payroll Bags, sewing 16 Repair of pick Payroll book Cook's Acc't May 1-28 Damage to Capt. Olof Damage to chimney (land tools) Damage to land granite terrace Nails	9507. 60. 15. 10 6680.60 200. 1100. 750. 5. 107219.95 3000. 62. 691. 25. 3760. 11605.50 195. 634.50 Service Advance to Nander Coffee bacon 128068.70
	Foreman Panteli Am 17- May 30 Trip to Corinth for hardware Niko Chauffeur bill String To Dr. Cox Board Am 17 & date <del>16 Feb 17 to April 18</del> 18 boxes Service Advance to Nander Coffee bacon	3000. 62. 691. 25. 3760. 11605.50 195. 634.50 675. 197.80

Panagiotis Palassis  
Paliochini } friend of phil  
Davies

(191)  
Minneapolis

Anastasios G. G. m.

104 So 7 Street

Anastasios Yannoulopoulos

104 So. 7 Street?

Brother from Liguria

Sparta 8. 3 8

21. 4

Montemarina 12. 0 5

81. 8

(96 kilometers)

(97 to gate)


16 ✓	Apr 17 - 30	=	14
17 ✓	to Easter	<u>4</u>	10
18 ✓		10	10
19 ✓			
20 ✓	May 1 - 30		
21 ✓			
22 ✓			
23 ✓			
24 ✓			
25 ✓			
26 ✓			
27 ✓			
28 ✓			
29 ✓			
30 ✓			
31 ✓			
32 ✓			
33 ✓			

April 16 Coffee 250. —  
 17 Benzine: 1 tin 180.  
 Cotton, full boxes, paper 92.  
 Tags & pencils 25.50  
 21 Payroll Apr 18-21 40 hours 552.5.  
 { To Harland - Nemea 30.00.  
 " Vasiliki - Nemea 52.50.  
 Athens - automobile bills 46.25.  
 Niko - chauffeur 7.50.  
 29 To Niko - cork 112.5  
£ 112.5  
 208.19.50

butter, bacon 1.50.  
 2 days wages putting ceiling 1.30.  
 Wood for ceiling 17.10  
 " " 217.-  
 Pay - Roll April 25-30. 9.717.75  
 Wagons cork April 1.60.-  
 Cork's food etc. 6 April 30. 1.282.-  
 Cloth for bags 345.-  
 Cork's transport 30.-  
 " food 5 days 150.-  
 Chauffeur " normal wages 1.750.-  
 " expenses rope 15.-  
 " 2 tins benzine 370.-  
 " repairs 50.-  
 558.-

May 7 Cork's w/ a/c. 14.082  
 Pay 20/21 May 2-7 2000  
 Return to G. Alex 428.  
 Barrels, etc. 150.  
 Damage to grain 1000.  
 Adv to Niko - Cook 753  
 542.435.

From Athens 21000. —

Returned advance Cork 1.125.-  
 " " chauffeur 750.-  
 From G. S. I. 2.875.-  
 May 4/5 From Athens 20000.  
 { From G. Alex 2000.  
 " " " 135.-  
 From Min. Com \$110.  
 May 11 From Athens 561.35.  
 1000.  
 2 20000.  
 771.35.-  



To Athens 103  
 10  
 103  
 224  
 24  
 10  
 526.  
 To Athens 112.  
 Apr 21-May 1 45.  
 10.  
 76  
 33  
 40  
 5  
 10  
 331  
 To Athens 112.  
 Apr 21-May 1 45.  
 10.  
 76  
 33  
 40  
 5  
 10  
 331  
 112.  
 45.  
 10.  
 76  
 33  
 40  
 5  
 10  
 331  
 112.  
 45.  
 10.  
 76  
 33  
 40  
 5  
 10  
 331  
 112.  
 45.  
 10.  
 76  
 33  
 40  
 5  
 10  
 331

2,000 Always  
using telephone

AMERICAN SCHOOL  
OF CLASSICAL STUDIES  
ATHENS, GREECE

Microfilmed : 14 NOV 1972





0 1 2 3 4 5

2,000 advance  
428 barrels eth  
150 gasin.

2,578  
135 over

2,443. to George May 2  
50 cr.

1,000 - to Nills

20 - to CB. given for change

753 - gasoline.

4266

CB's 50 from Nills

13.00 25<sup>r</sup>s.

13.  
1. 10  
---  
75<sup>r</sup>s.  
5-

14. 10

10 00

14. 95<sup>r</sup>

2424.95 cash



## Bronze

S/S "PATRIS II.,"

(29) dagger 35 pots  
minor  
caddle

(28) dagger 34 pots

(27) knife (9 pots) if fig  
~~dagger~~ (dinner)

(26) 4 arrow heads 3 pots

(25) spear head 30 + pots

W 1 minor

W 1 dagger

N 2 daggers

E 1 Spearhead

E 1 minor

(24) Tweezers 43 pots

(33) saw  
tweezers 17 figs  
chain  
needle

(32) ring 12 pots

(31) balance pans  
dagger  
Knife (?)

17 arrow heads

tweezers  
flags of knife

spear head 12 pots

Knife (?)

dagger

Tweezers

ring 10 pots

15 pots  
8 figs  
clawds

Gems

(33) 2

(32) 1

(21) 37 pots

(20) 4 pots

(19) 9 pots 5 figs

(18) 21 pots

(17) dagger 37 pots  
tweezers

(16) 5 pots

1 caddle  
arrow head

21 arrow

10 daggs

3 spears

5 tweezers

3 rings


Townsend Close  
173 Weston  
Worwickshire

$$\begin{array}{r} 125-443 \\ 117219.95 \\ \hline 8223. - \end{array}$$

Cash 88.84.

May 29 1927

WIELEN



<u>MTC</u>	<u>RSD</u>	<u>CWB</u>	<u>EPC</u>	<u>AHM</u>
<del>5</del> 4 $\frac{1}{4}$	<del>5</del> 4 $\frac{1}{4}$	1 2		

12 $\frac{1}{2}$  pensions @ 110. drs

April

BHK

May 5 14	4 14	3 6 3	2 6	1 3
19	18	12	8	1 3

18

12  
8

1  
3

61 b. Breakfast + d. @ 85. drs.

Up to May 14<sup>th</sup>

12.5-  
110  
12.5-0  
12.5-  
137 5.00  
51 8.5-  
65.60

61  
85 7.5-  
30  
48 8  
51 8.5-

# American Philological Association

TO THE SECRETARY:-

I nominate for membership in the Association

(*Name in full, with title, if any*)

(*Permanent address*)

The candidate is qualified for membership and will accept an election.

Signed,

.....

Date .....

Nominations may be made at any time by persons already members of the Association. Dues, five dollars for the first year, and three dollars annually thereafter. Life membership, fifty dollars.



HOLLAND-AMERICA LINE

ROTTERDAM.

S.S.

LH I	1	nd
LH II	2	nd
LH III	3	nd
LH IV	4	ineg
LH V	5	ineg
LH VI	6	ineg
LH VII	7	anom (G) nd
LH VIII	10	sgm.
LH IX	11	sgm
LH X	12	ineg
LH XI	13	nd
LH XII	14	ineg nd
LH XIII	15	ineg

① 23. 4. 13  
 ② 23. 4. 13  
 ③ 5. 6. 7. 14. 15 (Walters)

④ 16. 17. 18. 19. 20. 21  
 ⑤ 22.

23. 4. 13  
 Sq. 1 4 5  
 2 10 6  
 3 11 7  
 12  
 13 14 15

1 LH I  
 13 14

LH II 4 5 6 7 10 - K 12 14

Def. Kronos  
 tapering downwards

1	7
12	10
15	①

Broad open

2
3
4
5
6
11
13
14

- ① 10<sup>10</sup> Beads Bronze knife  
 ② 38 pots 2 gold necklace carnelian beads  
 2 silver bracelets iron  
 paste beads seal stone Bronze knife  
 ③ 26 fm 2 figs 2 cattle Bronze dagger w. inlay  
 carnelian beads. Gold chain plain " " " "  
 seal, elephant head of moment  
 ④ 5 cows 5 pots  
 ⑤ 4 pots  
 ⑥ 3 pots + 1 (cut down) 1 steatite seal  
 ⑦ 5 pots flag. of bronze knife arrowhead  
 ⑧ 14 pots 8 fig. bronze  
 ⑨ 20 pots (cut down) beads seal stone  
 ⑩ 7 pots  
 ⑪ 18 pots dagger knife head  
 ⑫ 5 pots knives dagger w. inlay iron wattle comb  
 bronze mirror seal  
 ⑬ 6 pots bronze cleaver



light  
 heavy  
 very  
 iron  
 glass  
 seal

of great value for the study of the  
text.

1870-1871

1870-1871

