

Argive Heraeum

CWB III

80
1920

11

10
11

10

10

10

10

10

10

10

10

10

10

Carl W. Blegen

Archive Herbarium

1928

March, April 27 1928

Argive Heraeum

1928

C. W. Blegen

(1)

951	Small beaker w. side hole & spout	LH III	Tomb	(43)	No	49	
952	Black cylix stem	"	"	"	"	60	
953	Wapt cylix stem	"	"	"	"	61	
954	Small amphora	"	"	"	"	62	
955	Small pygmae disc	"	"	"	"	67	
956	" " "	"	"	"	"	68	
957	Wapt cylix	"	"	"	"	35	
958	" " 2 high holes	"	"	"	"	77	
959	Sm alabastion	"	"	"	"	73	
960	Sh cup stepped	"	"	"	"	31	
961	Large unpt. jug 1 hole	"	"	"	"	33	
962	" jug 1 hole	"	"	"	"	34	
963	Amphora red netw.	"	"	"	"	53	
964	" red pt. d.	"	"	"	"	45	
965	Small amphora	"	"	"	"	39	
966	Small alabastion	"	Tomb	(45)	"	12	
967	Small jug 1 hole	"	"	"	"	18	
968	Shallow cup	LH I-II	"	"	"	19	
969	" " unpt.	"	"	"	"	23	
970	V. small alabastion	LH III	"	"	"	30	
971	Shallow cup unpt. 1 hole	"	"	"	"	6	
972	Large jug 1 hole	"	"	"	"	7	
973	Smaller jug 1 "	"	"	"	"	9	
974	Squat jug - spirals	LH I-III	"	"	"	13	
975	Ephyraean goblet ansletts	LH II	"	"	"	22	
976	Small red cup 1 loop hole	"	Tomb	(43)	"	sh 2	
977	Small beaker w. spout (frag)	"	"	"	"	"	
978	Small alabastion (frag)	"	"	"	"	"	
979	Small stirrup vase (frag)	"	"	"	"	No. 43	
980	Longish alabastion	"	"	"	"	sh 5	
981	Alabastion (frag)	LH II	Tomb	(50)	"	2	
982	Unpt. jug 2 hole (frag)	"	"	"	"	6	
983	Clayish cup (frag)	LH II	"	"	"	7	
984	Black bowl 2 loop holes	"	"	"	"	8	
985	Alabastion (frag)	LH II	"	"	"	9	
986	Cylix coated inside (frag)	"	"	"	"	10	
987	Fine alabastion (frag)	"	"	"	"	11	
988	Sm. cylix ang. w. 1 hole	LH III	Tomb	(43)	"	sh 5	
989	Unpt jug 1 hole	"	"	"	"	"	
990	Come red holeless cup	"	"	"	"	"	
991	Fragm bl jug w. side spout	"	"	"	"	29	
992	Small unpt. cylix 1 hole	"	Tomb	(46)	"	20	
993	" alab. but sides - deto	LH II	"	"	"	18	
994	Lge unpt. cylix 2 high holes (frag)	"	"	"	"	"	
995	" jug comme de. but red	"	"	"	"	521	

No	Description	LH III	Tomb	(44)	No
996	Squat stumpy vase	LH III	"	"	1
997	Coarse flaring lamp	"	"	"	3
998	Sm. unpt'd cylix ang. prof.	LH III	"	"	11
999	" " (frag)	"	"	"	6
1000	LH I cup - spind. 2 holes	LH I	"	"	9
1001	Small handleless jug - im. leaves	"	"	"	10
1002	Conical filler? (frag)	"	"	"	11
1003	Double eye pot (frag) jug	"	"	"	12
1004	Spouted jug 1 hole	"	"	"	14
1005	Squat jar or alab. 2 holes	"	"	"	15
1006	Tall jar 2 holes spout spind.	"	"	"	16
1007	Unpt'd handleless cup	"	"	"	17
1008	Small tall jug 1 hole	"	"	"	18
1009	Large amphora	LH III	"	"	19
1010	Coarse shallow cup (frag) 2 pinched out fls	"	"	"	20
1011	Unpt'd. cylix (frag)	"	"	"	21
1012	" " red coarse	"	"	"	22
1013	" " 2 high holes	"	"	"	23
1014	" " reddish (frag)	"	"	"	24
1015	Thin jug or pitcher	"	"	"	25
1016	" coarse cup on 3 legs	"	"	"	26
1017	Small alabastron	"	"	"	27
1018	Unpt'd. cylix	"	"	"	28
1019	Thin stumpy vase	"	"	"	29
1020	Unpt'd. cylix 2 high holes	"	"	"	30
1021	" jar 2 holes	LH I (?)	"	"	31
1022	Sm alabastron im. leaves	"	"	"	32
1023	Unpt'd cylix 1 hole	LH III	"	"	33
1024	Large pt'd amphora	"	"	"	35
1025	" unpt'd stumpy vase	"	"	"	36
1026	" pt'd stumpy (frag)	"	"	"	37
1027	Unpt'd handleless cup	"	"	"	38
1028	" shallow "	"	"	"	39
1029	Kammos - triplet alabastron	"	"	"	40
1030	Unpt'd cylix 2 high holes	"	"	"	41
1031	" " 1 hole	"	"	"	42
1032	Thin Ming an like cup 1 hole	"	"	"	43
1033	Unpt'd cylix (frag)	"	"	"	44
1034	Fin. jug w. 3 pt. rosettes	LH II?	"	"	45
1035	Small stumpy	LH III	"	"	46
1036	Unpt'd cylix (frag)	"	"	"	47
1037	" sh. cup 1 hole	"	"	"	48
1038	" amph 3 holes	"	"	"	49
1039	" coarse sh. cup 2 pinched holes	"	"	"	50
1040	" " " " " "	"	"	"	51

Index

Tomb 8	118, 127, 130, 135, 139, 145, 170
9	130, 135, 148, 156
25	156
34	26, 33, 44, 48, 52, 60, 72, 78, 89, 97, 105, 114
35	22, 27, 32, 45, 72
36	14, 33, 45, 48, 52, 61, 72, 78
37	25, 40, 48, 53, 62, 69, 76, 81, 90, 97, 105, 114, 135, 138, 139
38	40, 49, 53, 62, 69, 76, 81, 90, 97, 127
39	40, 49, 53, 63, 76
40	37, 41, 49, 54, 63, 76, 81, 89, 97
41	41, 54, 63, 68, 73, 78, 93, 98, 105, 109, 114, 119, 123, 127, 130, 134, 145, 148, 157
42	58, 73, 78, 98, 101, 105, 109, 115, 119, 123, 127, 130, 134, 138, 139, 142, 145, 148, 157, 170
43	85, 104, 108, 115, 118, 122, 126, 131, 134, 138, 140, 142, 145, 148, 157, 158, 160, 162, 166, 168, 170, 173, 177
44	102, 125, 42, 93, 98, 127, 131, 134, 140, 141, 148, 154, 156, 160, 162, 166, 168, 170, 172, 173, 174, 176, 180, 184
45	25, 42, 64, 74, 79, 84, 89
46	42, 65, 74, 79, 84, 89
47	43
48	43, 64, 69, 74, 80, 84, 94, 98

- (49) 92, 96, 102, 104, 108, 115, 118, 122, 126, 131, 135, 138, 142, 144, 148, 160, 163
- (50) 118, 122, 126, 131, 135, 138, 142, 163
- (51) 127, 132, 141, 144, 148, 157, 160, 163
- (52) 14, 18, 21, 145, 149, 163

M.H. Cemetery 84, 90

MH Graves:

- XII 186, 23
- XIII 28, 58, 62
- XIV 28, 68
- XV 64
- XVII 75
- XVIII 75
- XIX 75, 80
- XX 80
- XXI 84
- XXVIII 116

E H Cairns 25, 36

E H Tomb hunt 141, 148, 162

E H Tomb (9) 166, 168, 173, 177, 181, 184

(7)
Trial Trenches: 13, 68, 73, 78, 85, 116

E XIX 89, 92, 96, 101, 104, 119, 123, 128, 132, 149, 152 f.

- | | | | |
|------|--|-----------|------------|
| 1087 | pt. amphora small | Tomb (33) | No 58 |
| 1088 | cup w. black stripes (frag) | " " | " 70 |
| 1089 | Tall cup w. 2 high ledges | " " | " 77-81 |
| 1090 | stirrup vase - red bands | " " | " 78 |
| 1091 | tall cup w. 1 ledge | " " | " 79 |
| 1092 | sh. cup w. 2 high handles | " " | " 73 |
| 1093 | Sh. bowl (2 ledges) black stripes | " " | " 82 |
| 1094 | Small red striped stirrup vase | " " | sherds. |
| 1095 | pointed jug | Tomb (8) | No. 27 |
| 1096 | T.C. figurine (smaller) | Tomb (33) | " 15 or 24 |
| 1097 | " " larger | " " | " 15 or 24 |
| 1098 | T.C. " cross " | Tomb (28) | No. 28 |
| 1099 | T.C. " smaller | " " | " 29 |
| 1100 | T.C. " disc small | " (32) | ? Box 108 |
| 1101 | red pted. Cyprus - cross at. stirrup (cf. 854) | Tomb A | R.C.D. 103 |
| 1102 | Small stirrup vase (frag) | " " | No. 35 |
| 1103 | unpainted cup with black bands | " " | No. 39 |
| 1104 | Red pted. small stirrup vase | " " | No. 18 |
| 1105 | fine gray Mycenaean jug | " " | shards |
| 1106 | fin. stirrup vase - painted green | " " | " |
| 1107 | unpainted cup w. stem | " " | No. 37 |
| 1108 | unpainted lidless cup | " " | sherds |
| 1109 | small pointed jug with 3 high loop handles | " " | " |
| 1110 | red cup | " " | " |
| 1111 | Small stirrup vase (frag) | " " | " |
| 1112 | like 1109 (frag) | " " | " |
| 1113 | fin. striped saucer - fragmentary | " " | " |
| 1114 | Small amphora | Tomb 28 | No. 11 |
| 1115 | shallow cup - black dec. bell shape LIII | " " | No. 4 |
| 1116 | wide shallow lidless jug - frag | Tomb 40 | No. 11 |
| 1117 | wide cup | " " | No. 8 |
| 1118 | wide - flg | " " | No. 6 |
| 1119 | Tripartite clayton red (frag) | " " | sherds |
| 1120 | " black (frag) | " " | sherds |
| 1121 | shallow cup | " 49 | No. 35 |
| 1122 | figurine disc type | " 27 | No. 10 |

No.	Description	Material	Tomb	No.	Shd
1041	Unpt cylix (frag)	LH III	Tomb	(44)	No. Shd
1042	Small stumpy vase	"	"	"	Shd
1043	" " (frag)	"	"	"	Shd
1044	Shallow cup pinched at hole (frag)	"	"	"	44
1045	" " "	"	"	"	Shd
1046	Sm. cup w. 1 high hole	"	"	"	Shd
1047	Unptd cup ang. prof. (frag)	"	"	"	Shd
1048	Large Mattpt jar 4 holes	MH	Tomb	(25)	" 6
1049	Tall jug 1 hole slender base	LH III	Tomb	(29)	" 1
1050	Lge " 1 " spiral	"	"	"	" 2
1051	Coated few fig. of TC (Gumtree)	"	Tomb	(19)	" 16
1052	Sh. cup w. 1 high hole	LH III	Tomb	(34)	" 43
1053	Lge amphora	"	"	"	" 65
1054	Sm. obabahan vertic ribs	"	"	"	shd
1055	" unpt 2 holed amphora	"	"	"	"
1056	" oval rhyton	"	"	"	" 92
1057	Mattpt jug green hole	MH	grave	XXIV	" 2
1058	Coarse per. furcated pt. hole (cup shape)	"	Tomb	(30)	" 11
1059	Unpt handblown cup	"	"	"	" shd.
1060	" cylix (rim only)	"	"	"	" 17-24
1061	" cylix	"	Tomb	(33)	" 1
1062	Shallow cup 2 pinched out holes unptd	"	"	"	" 2-76
1063	Unpt cylix	"	"	"	" 3
1064	Small coarse cup side rim hole	"	"	"	" 4
1065	" stumpy vase like pt	"	"	"	" 5
1066	unpt cylix	"	"	"	" 7
1067	red feeding bottle	"	"	"	" 8-13
1068	tall red pt cylix	"	"	"	" 6-11-16
1069	green pt stumpy vase	"	"	"	" 17
1070	Small black pt squat jar	"	"	"	" 18
1071	stumpy vase	"	"	"	" 19
1072	large jug 1 hole	"	"	"	" 21
1073	Small cylix	"	"	"	" 22
1074	Sh. small saucer dec. fine lines 3 holed	"	"	"	" 25
1075	small red pt. pitcher with bridged spout	"	"	"	" 26
1076	grey cylix ang. profile	"	"	"	" 28
1077	unpt stumpy with holes & bridged spout	"	"	"	" 39
1078	red striped saucer sh cup 1 hole	"	"	"	" 49
1079	Large pt & unptd 1 hole	"	"	"	" 50
1080	2 holed green goblet cylix	"	"	"	" 51
1081	sm. red striped stumpy hole	"	"	"	" 54
1082	red dish cylix unpt	"	"	"	" 60
1083	str. sided cup no holes unptd.	"	"	"	" 61
1084	jug. large w. black stripes	"	"	"	" 64
1085	low stemmed cylix	"	"	"	" 65
1086	cylix - fragments	"	"	"	" 66

Argive Heraeum Campaign of 1928

Staff CWB, DHO, M. Spitzer, N. Bester at the beginning.

Foreman George Alexopoulos

Chauffeur - Sotirios Plegmenos @ 9000.
 dacha per month including everything
 car - oil repairs - his own food &
 lodging, etc. we agree to pay
 6 dr. per kilometre for anything in
 excess of 40 per day.

Hotel - New Hotel Nauplia at the
 beginning we pay 100 dr. per
 for room & dinner. Breakfast
 & lunch at dig.

Equipment - tools, etc bought in
 Athens.

10
1259 Body of horse - ribs missing
1260 " " " " "
1261 Head of " (?)
1262 " " "
1263 Small cup w. holes
1264 Black glass shard - incised

Geom. Terrace

" "
" "
" "
" "

11
Tuesday April 17

Spitzer + I leave Athens by car
at 6:05 AM.

Stop at Corinth + get drawing board

Stop at Mycenae + see Georg
Alysonelos. See candidate for
cook + order some equipment
plates, cups, glasses, kitchen utensils, etc.

Arr. Nauplia 7 P.M.

DH Cox arrives by train

New Hotel - Nauplia

1213	Large water jar from Mya ^{CH III} House on Acrop. U IV	
1214	Small cup L II	Armos Tomb (14)
1215	Half of geometric bowl	Tomb (26)
1216	Small crater like cup - geometric shapes u	" "
1217	" cup 1 hole u	" "
1218	" bell shaped cup 1 hole u	" "
1219	" sh. cup 2 horiz loops u	" "
1220	largest cup 1 hole - tea-cup geom	" "
1221	Yell. Min. sh. cup - 1 high hole missing	Grave XI
1222	Geom. crater w. knob - frag	Tomb (50)
1223	Cup deep flared black 1 hole	Geom Terrace
1224	" Protocor 2 holes	" "
1225	Sm cup 1 hole E red br wash	" "
1226	Pyxis - cup - 2 loops holes	" "
1227	" - shallow - 3 loops or holes	" "
1228	Thin votive unptd	" "
1229	Sm jug - trefoil lip - unptd hole	" "
1230	" " " " " "	" "
1231	large " " " " " "	" "
1232	Sm. " " " " " "	" "
1233	Sm jug - wire lip - hole unptd	" "
1234	" " " " " "	" "
1235	Sm. jug w. collar & flat rim	" "
1236	Sm flat-bottom, oenochae unptd	" "
1237	" " " " " "	" "
1238	" " " " " "	" "
1239	" " " " " "	" "
1240	" " " " " "	" "
1241	" " " " " bld & mused	" "
1242	" " " " " "	" "
1243	" " " " " Protocor	" "
1244	" " " " " "	" "
1245	Large shallow cylix 2 holes	" "
1246	1/2 very small Protocor - skyphos	" "
1247	2-handled bowl - lay. Geometric	Tomb (25)
1248	cylix - red-br glaze class	E XIX
1249	dimin. votive cantharus	" "
1250	" " " " " " " " " " " "	" "
1251	T C fig seated nearly complete	Geom Terrace
1252	" " " " " upper half	" "
1253	" " " " " " " " " " " "	" "
1254	" " " " " " " " " " " "	" "
1255	" " " " " " " " " " " "	" (20 p 20)
1256	" " " " " " " " " " " "	" "
1257	" " " " " " " " " " " "	" "
1258	" " " " " " " " " " " "	" (to 6 10)

Wednesday April 18

(13)

27 men report for work
DHC, Spitzer & Curtis

Began a trench eastward
from Tomb XXXIII just below
conglomerate ledge.

Another trench 25 m. further
down hill.

Another trench N.W. ward
from Tomb XXX

Also start 1 game cleaning
E. chamber of Tomb XXV which
is collapsed & is in bad state

DHC takes charge of game to
work on E. Myzagalari ridge below
Tomb II

Car to Argo for supplies with
foreman.

Bastos arrives at Naupha in the
evening

(14)

Trench E of Tomb XXXIII

At pt. 9. in E of door of XXXIII
we find stone at 0.35 below surface
under stones - ca. 65 - below surface
a yellow goblet & some bones & frags.
frags. of a skull & 1 tooth.
Probably a tomb here though
the burial seems very high
The stones may be from door

(15)

Ca. 11.00 am. east of goblet mentioned
above we find soft earth & at depth
of 1.00 m. below surface an apparently
completely unparieted one. Probably a
tomb here too. Jugs smashed.

(15)

AH Photographs Film pack A

- 401 Yellow goblet in trench E of XXXIII
402 Trench E of XXXIII from West

April 19.


- (7) View from ^{lure} S. face wall of 3 cones
possible ~~remnant~~ of wall of a
door (cf p. 18)
- 403 View from SW of same wall
boulders beneath cf p. 18
- 404 Grave covered with slabs from
N.W. cf p. 19
- 405 Overview of grave (?) & door (?)
from N.E. from top of ledge.

(18)

Area East of Tomb XXXIII

A second trench has now been dug here ca 3 m south of the first. In it a group of large stone slabs - perhaps a grave (M.H.?) - comes to light - ca 7 m E of XXXIII at ca. 0.45 m below surface of ground. We clear away earth to see what it is.

During morning we clear whole area between two trenches for distance of ca 3.50 m. Some yellow Myrica shrub.



slabs covering possible grave


In N. trench we find 3 courses of built stone - do not like wall closing door of tomb - but no sign of door appears. These stones rest on two huge boulders or partly on them & partly on crack between them.

Photographed 4 p 15

(19)

Grave XII

The grave (?) seems oriented ca E-W covered with 3 large slabs & several smaller flat stones. ca 2.00 m long. largest slab - in middle - is 1.50 m long = (width of tomb) & .70 m wide.



Photographed see p. 15

Apr 20

A# Photographs Film Pack A

406 Tile grave in trench on East Yuzgalans Hill below Tomb II = A 3 in DHC p. 4

407 Similar tile grave farther South much deeper in ground = A 2 in DHC p. 4

Film Pack B

408 Tile grave - southernmost of series in final trenches on East Yuzgalans Hill = A 1 in DHC p. 4

409 grave's door (?) E. of XXXIII from above (East)

4103 Grave A 3 cleaned from West

4114 Grave A 2 cleaned from West

4125 Grave A 1 cleaned from West

Friday April 20

(21)

41 men

Trials continue on East Yuzgalans ridge & around NE side of Kephalans Hill

DHC draws plan of slab-covered grave & door-wall (?) E of Tomb XXXIII & yellow Minyan pot

In afternoon transfer a number of men high up on E Yuzgalans ridge toward houses of Navdaganis

2 more MH graves to No. XIIE = ca. 6 m. south of XII

No. XIV ca. 10 m. SE of XIII

22

XXXV

In area east of T XXXIII I
began to dig out a possible chamber
as indicated by hollow in ledge
of conglomerate. It has a
square plan. The roof has collapsed
& we have only back of chamber
preserved in ledge.

I call it provisionally XXXV
as there is a space for another
tomb between this & XXXIII

8 men here

In course of afternoon at depth
in belly surface we find
large fragmentary pot & some bones
appear. Stop pickmen & wait for
knife man.

Pickmen transferred farther
west to site of possible XXXIV
just east of XXXIII

(23)

M. H. Grave XII

At 11:30 AM we removed the three
big slabs covering the possible M. H.
grave E of XXXIII. One was very
large & heavy. All of limestone
and very rough - unworked.
We began digging down with
knives in brown earth which
appeared underneath the slabs.

In the course of the afternoon
an irregularly oval pit develops
cut in brown stone & skeleton
in bad state of preservation
comes to light.

Body seems to have lain on
right side. Head to west, feet to
east. Just in front of head is
a small, Matt-painted jug.
Semi-crouching position; legs bent
forward at hips & knees bent.
Skeleton of adult individual.
Left arm at side bent at elbow
& forearm over abdomen.
Right arm under body & hand over
abdomen. - finger bones preserved.

24 Photographs

Apr 21 Film Pack B

4136 AH. M H Grave XII from N cleaned

414 M H Grave XII from S cleaned

Apr 23

4158 Trench F on Keptalarn Hill showing
dromos of Tomb XXXVII from NW

4169 Cairn D on E Yezogalarn from W
of DHC p. 16

4170 Cairn E on E Yezogalarn from W
of DHC p. 16

4181 Cairn A on E Yezogalarn from NW
of DHC p. 17

4192 Chamber of Tomb XXXV from
SW (p. 32)

Saturday April 21

25

41 men

Most of force trial trenching
high up on E Yezogalarn ridge

9 men in region of XXXIV - XXXV

Grave XII cleaned for photographing
Photographed at 1:10 PM. (p. 24)

Work on NE side of Keptalarn
ridge goes on & shortly before
noon we find what appears to
be dromos of a tomb. We give
it No. XXXVII

44 In afternoon we find dromos
of a tomb high up on E Yezogalarn
in same ridge where tomb XII was
discovered in 1925.

45 Much higher on E Yezogalarn ridge
we seem to have yet another dromos

In field high on E Yezogalarn
we find some E H pottery here &
there & 5 cairn like heaps of
stones - grass?

26

Tomb XXXIV (?)

7 men at work here. Possible tomb chamber against vertical scarp of ledge of rock. Directly toward rock face door wall mentioned on p. 18. We are digging down from surface in this area.

At depth of ca. 1 m. being to find some fragments of pottery.

Tomb XXXV

27

2 men with knives. Bones & pots appear at high level & we are certainly in some kind of a chamber though we have found no drums yet.

The pottery looks fairly late LH III. Large part of large stumpy vase (?)

28) Grave XIII (ca. 6 m S. of Grave XII)

Covered by 3 slabs (2 large & 1 small) running roughly from SE to NW, filled out by smaller stones & water approximately rectangular 1.50 m (SE to NW) by 1.35 m.

Drawn by D.H.C.

Grave XIV (ca. 10 m. S. of Grave XIII)

Covered by 3 largest slabs of limestone. Ca. 2.00 m. long by 1.15 m. wide. Slabs run crosswise. One is very large. On slabs found 2 fragments of yellow Mycenaean ware.

Drawn by D.H.C.

Sunday April 22

(29)

Morning in Nauplia Museum.

Talk to members of Roman School.

Borrow tools from Bertis - knives, etc.

Recon. to arrive by evening train. Mrs. Hack & Mrs. Rawson.

P.M. Excursion in car to Belesi. We explore prehistoric sites & find 4 of E.H. Period.

- ① "Mazonka". To left of road just beyond 6 km post. Small rocky mound. A good many E.H. sherds, no later prehistoric & some medieval.
- ② "Skala". To right of road just before 7 km post. Above Chadi. E.H. sherd fairly plentiful on N slope of hill. Distinctive to branch road which leads to Malakidion. No late prehistoric sherds, but some medieval.
- ③ above 8 km post. To right of road just above 8 km post. A fairly high hill. E.H. sherd fairly numerous on N & E sides of hill. Also some medieval. No later prehistoric.
- ④ "Makryvouni" or "Korfovouni". A long low hill above Chagora river, West of Assis. Seems to be an important E.H. site of very great size. Much E.H. pottery, no later prehistoric.

1123	loaf pot	Tomb 25	No. 1-
1124	shirrup vase	" 49	No. 12
1125	"	" "	No. 33
1126	loaf pot L.H. II (frag)	" "	No. 32
1127	unpainted cylix frag	" "	sherds
1128	"	" "	"
1129	Small loaf pot red (frag)	" "	"
1130	Small fat pitcher Dark paint.	Tomb 28	No. 42
1131	" amphora	" "	No. 44
1132	pink unguated cylix - frag	" "	No. 14
1133	Small red frag (look like)	" "	No. 5
1134	pinkish bell-shaped cup	" "	No. 26
1135	" unpainted cylix	" "	No. 8
1136	Taphio cup L.H. I - II	" "	No. 24
1137	Foot of cylix	" "	No. 43
1138	Coarse pink cup hollow	" "	No. 12
1139	Torso i.e. figurine base decorated	" 49	sherds
1140	Large potted frag	Tomb 28	No. 30
1141	" unpainted	" "	No. 2
1142	goblet unpainted cylix L.H. II	" "	No. 37
1143	Cup unpainted base, 1 hole	" "	No. 39
1144	2 sherds of cylix with unusual pattern	" "	sherds
1145	sherds of cup L.H. I	" 34	sherds
1146	frag. i.e. figurine disc type	" 27	"
1147	unpainted cylix	" "	No. 16
1148	goblet unpainted cylix L.H. III	" "	No. 14
1149	frag. red stripes, short - 1 hole	" "	sherds
1150	round-mouthed squat jar unpainted	" "	No. 1
1151	wide cylix - frag	" "	sherds
1152	handle of the pot & rim of feeding bottle	" "	No. 30
1153	frag with spirals - 1 hole	" "	No. 15
1154	Cup with 1 hole, red paint	Tomb 29	No. 58
1155	small unpainted goblet	" "	No. 48
1156	Small alabastron unpainted pattern	" "	No. 2 on 24
1157	large unglazed cup goblet L.H. II	" "	No. 28
1158	frag unpainted 2 handled frag (frag)	" "	No. 29
1159	base red hollow cup - small	" "	No. 44
1160	frag unpainted frag 2 handles	" "	No. 14
1161	shallow saucer - red & black spots hatched	" "	No. 23
1162	gray frag unpainted - 1 handle	" "	No. 43
1163	red & black hatched 2 handled frag (frag)	" "	No. 54
1164	shallow cup, basal, 1 hole, no rim	" "	No. 133
1165	cylix unpainted pinkish (frag)	" "	No. 34
1166	Deep bowl with 2 handles - sherds	" 26-31	No. 11
1167	loaf pot - large wave pattern	" "	sherds

back to p. 16.

St. George's Day

42 men

10 on W. Yurogalare ridge

on N & E sides of Kephalaris Hill


2 on E Yurogalare below Tomb II

on Upper E Yurogalare - Terrain -

1 water carrier

Mrs & Mrs Sample arrive by evening train

Clearing with knife nearly finished. Seems to be a small chamber at very high level. Roughly semicircular in shape with straight front. Whole front apparently collapsed & front line barely recognizable. In middle of front line some scanty remains of door. Lower course of door wall still in place. Mass of stones from upper part fallen into chamber.



Remains in chamber are to left of door.

2 large bones & 1/2 pot farther in toward back more frag. prob. of same pot.

Farther to left - maybe in a sort of cist - 2 skulls & a few other bones. Also a figurine of T.C.

In corner to right of door prob. a small cist.

Chamber photographed (p. 24)

In cist just inside door is another cist. It contains several pots & at least 3 figurines. Also a pierced plectrum head of steatite & one lump of shell.

Upper layer of earth removed & area now ready for more careful examination with knife etc. Some potsherds appear.

I move the gang (& men) after breakfast to area east of ~~XXXV~~ looking for a possible XXXVI.

On slope below of XVI of 1925
campaign 2 men have been
making this since last Thursday
I have to pay soil & arrange
ment apparently in stereo.

Cutting in stereo here led us
to believe we had a dromos,
but it proved not to be of usual
kind.

At this level we find series
of 4-5 slabs on edge which look
as if blocking a doorway. Very
poorly laid. There are really 8 or 9
of slabs in the construction
0.55 m high. Then top is 1.20 m
below surface of ground.

Inside these slabs (to N.W.) we
find to right a bath, another pot
lying in greenish packed stereo.
It is a small coarse vessel of red
clay with a loop handle.

Tuesday April 24

43 men.

- 10 S of T. XXXIII
- 12 on Kephalaria Hill
- 18 on Kephalaria
- 1 hauling water
- 1 setting up shelter
- 1 acting foreman (Pantelis)

Uncle George away for the day.

Mrs Ransom takes charge of Tomb XXXIV

Mrs Hack takes charge of Tomb XXXVI

Open E.H. came on upper slope
of Eryogalare. Packed with large
stems & debris of ca. 1 m. from
yellow earth's clay
one Hellenistic sherd among
lower stems. all other sherds
are E.H.

- (45) (46) (44) 3 tombs now contain
on upper slope of Eryogalare
(27) (28) (29) (40) 4 contain on Kephelari
(34) (35) (36) 3 contain (1) E of T XXXIII

Rain at 2 P.M. but not very
sinous - work stopped ca 1 hour

Wednesday April 25

41 men

Heavy rain last night filled all
our drains with water

Men used the morning for
trial trenches in dry places

One new tomb on upper slope of
Eryogalare

Slight drizzle from time to time
during day

open tomb (40) - seems fallen

Mr & Mrs simple come out to dig
Also Bertoz
2 cists to dig today
(1 = our own
(1 belongs to hotel)

- 30
AH Photographs Film pack C.
420 Stone fill inner end of domos T. XXXVII
421 Stone fill in domos of Tomb XXXVIII
422 Door & wall closing of Tomb XL
423 Door of Tomb XL cleaned
424 Central cut in Tomb XXXV from above
425 Chamber of Tomb XXXV from SW

April 26

- 426 Door of Tomb XXXVIII
427 Burial in domos of Tomb XXXIX from E
428 Burial & door in domos of Tomb XXXIX
from NNE

Thursday April 26

39

45 men

14 on West Yuzgalari

20 ~~19~~ men East Yuzgalari

10 men on Keplalari Hill

1 water carrier

2 cars today to dig
1 is our own
1 belongs to Hadjiko

Tomb (37) Dromos nearly clean out. Smaller and filled with a mass of large stones reaching from surface almost to bottom of dromos & occupying practically whole width of dromos. I don't think this is the door itself. It looks more like a fill of stones. Some goats' skulls in dromos almost all. L.H. III

Tomb (38) Dromos nearly empty. Short narrow steeply sloping tapering sides. Door begins to appear at inner end. Perhaps chamber has not collapsed. There was a heavy fill of large stones in part of door. Freshen door.

Tomb (39) Very short dromos & broad. In outer part is apparently a small cut-grave against left side. Made of rough unworked slabs set on edge. Not parallel to side of dromos, though latter follows one side of it. In this wall is cut apparently the bones of an infant. No pottery yet.

At inner end of dromos on floor (or in it) is evidently another cut containing numerous bones. One pot was smashed, second is intact. Relation to door not yet clear.

Tomb (40) Opened yesterday. Chamber full of earth & stones. Main part of roof seems not to have collapsed but part side probably gone so earth etc. has got in. We began to dig down from above over chamber but found hard conglomerate & then stopped.

Working through door we get into chamber. At high level found a good many pieces of Proto-Corinthian pottery - several skyphos represented.

Also a few bones here - of some animal - teeth suggest a dog.

Also a small bronze bowl - evidently contemporary with Proto-Corinthian pottery.

On west side of index opposite Tomb (2) we have found what seems to be dromos of another tomb. Very narrow but widens toward outer end and toward bottom well cut. Looks like tomb of type of Tomb (7).

(41)

Red rosette for here in afternoon - at top of dromos.

44 Tomb (44) on East Yozogalari

long narrow dromos with well cut sides - fairly sharp inward inclination. Steep floor slope steeply downward. Dromos nearly cleared & stones of door begin to appear

Tomb (45) High up on E. Yozogalari

Dromos developing. Proved to be much wider than at first suspected; but stone had not yet been found on left side

Toward outer end mass of stone or stones in dromos - probably fallen

At inner end some stone appear - may belong to wall closing door

Tomb (46) 3 m. south of (45) Has broad dromos. sides show slight inward inclination. Width at door now 1.60 but stone floor not yet reached

Stones of wall closing door appear - chiefly small flat slabs

Chamber probably collapsed

43 Tomb (47) ?

Ca. 10 m SE of (46)

Looks like a dromos, on one side (right) at least. On other a line of stones behind them soft earth and on poor pot appears perhaps a cut in side of dromos

The difficulty is that we find apparent stones at inner end of dromos & no sign of a door in it. Still wet from rain of Tuesday night. We leave for examination later when dry

Tomb (48)

Mrs. Semple in charge

Dromos developing - fairly wide few shreds. Some large stones at inner end may belong to door or to fill in front of door

44

Tomb (34)

We have now opened up the dromos for most of its length though the staid floor has not yet been reached. It seems to be long & broad & it looks as if (34) is a large tomb.

Near onto end of dromos a line of stones appear along left side - perhaps the left side was built for strength as the earth & stone here appear soft.

Good pottery in dromos - fine Lft III style.

The door at inner end seems centered. Width of dromos here now 1.80 m (not on floor).

The chamber must be further back partly under the ledge of conglomerate. We are cutting away a layer more yellow stone and rock up to the sound face of the ledge.

45

Tomb (35)

J.H.C. draws the plan this morning.

Pots taken out & bagged.

Tomb (36)

We have now dug out most of area above probable chamber and are approaching level of tomb (?). Above this is a thick layer of blackened earth & stone containing lots of bronze & geometric pottery.

46 Photographs Film Pack C

- A.H.
 429 Door of Tomb (46)
 430 E.H. (?) cairn F (DHCP 22)
 431 E.H. (?) cairn D, cleared, showing
 circular pit in stereo.

Film Pack D

- 432 Door of Tomb (37)
 433 Cist on left side of dromos of
 Tomb (39)
 434 Dromos of Tomb (44)
 435 Steps in dromos of Tomb (46) from above
 436 Dromos of Tomb (48)
 437 Dromos of Tomb (45)
 438 Steps in dromos of (48) from above
 439 Step in dromos of (45) " "
 440 Dromos + door of Tomb (48)
 441 Cist in front of door in dromos of
 Tomb (45)
 442 Door of Tomb (46)
 443 Door of Tomb (37) with big slab

Friday, April 27

(47)

- 43 men
 8. in Tomb (34) clearing chamber
 4 " " (36) " "
 3 (37)
 3 (38)
 1 (39)
 1 (40)
 2 (41)
 5 (44)
 2 (45)
 3 (46)
 2 (47)
 3 (48)
 2 digging trial trench NE of (15)
 2 setting up shelter
 1 water carrier
 1 clearing E.H. (?) tomb on F. Perogalans

2 cans
 1 = our own
 1 = Habik's
 2 used on salt & Argo in morning

Tomb (34)

Good progress made in removing mass of fallen rock above chamber. Outline of latter begins to appear. I think looks fairly large.

Tomb (36)

We have reached floor level of the tomb & begun to clean it with two knife diggers. Some beads of paste appear & frags of pots.

Tomb (37)

Dromos cleared in left inner corner to l. of door. A small pit cut into side of dromos. It contains bones, 1 fragment of pottery & a bronze knife. Latter broken by workman.

Large stone at inner end of dromos. Real built door prob not yet in sight. Door jams beginning to be recognizable. Left is much wider than right.

Photographed. We remove large stone

Tomb (38)

Work goes on all day digging out chamber. Slow job. Hard packed clay.

Tomb (39)

Large pit in doorway under wall of stones. 2 skulls appear & far in a large pot. We cover these remains with earth preparatory to removing stones above. Proceed to remove stones.

Tomb (40)

Digging out chamber proceeding slowly.

- Photographs Film Packs E
- 444 ① Tomb (37) door & dromos
- 445 ② Tomb (38) Dromos & door
- 446 ③ Tomb (40) Dromos & door
- 447 ④ Tomb (47) wall at left of dromos
- 448 ⑤ Tomb (47) Pots alongside wall
from above
- 449 ⑥ Cairn A skeleton in contact
position from above
- 450 ⑦ Dromos & door of Tomb (44)
- 451 ⑧ Door of Tomb (44) walls etc.

Saturday April 28

(51)

45 men

- 9 incense Tomb (34)
- 3 " " " (36)
- 2 " " " (37)
- 2 " " " (38)
- 1 " " " (39)
- 2 " " " (40)
- 4 " " " (41)
- 2 " " " (44)
- 1 " " " (45)
- 3 " " " (46)
- 1 " " " (47)
- 3 " " " (48)

4 in trial trench on upper Grogalaris

2 " Cairn E

2 in trial trench S of (4)

2 building shelter

1 sword box

1 water carrier

2 ens: our own & Hadjlers.

George Mylonas arrived from Athens
with money.

(52)

Tomb (34)

Work of digging down into chamber goes on rapidly. Most of fallen rock now removed. Chamber begins to take shape. Seems to be a very large one ca. 4.00 m deep from front to back by ca. 2.30 wide.

One or two late (classical) shards found among scattered rocks & earth.

Now about 3.75 m deep below top of conglomerate ledge. Latter overhangs chamber ca. 2.00 m.

Tomb (36)

Cleaning of floor proceeding. We seem to have two chambers or chamber & end chamber (?) separated by narrow piece of rock-stone in which there is some evidence of a door-stone of a wall. This door was ca. 0.85 m wide to judge by the length of the stone wall which is 0.35 m high & ca. 0.45 m thick.

In west chamber at back - with - we have great heap of bones & some pottery. Latter looks early Mycenaean L.H.II or III.

In east chamber are 4 small pots all L.H.III & near alleged door mentioned above.

? Which was main chamber & which side chamber? or are they 2 separate tombs.

Boundaries of neither chamber clearly defined yet.

Tomb (37)

(53)

Door cleaned & photographed. Made of small stones & chunks of stone. The wall closing door, that is wall removed & we proceed to enter chamber is full of earth stone, etc.

In domos before door is a fairly broad deep groove - a small one in the middle - not like two lateral grooves in T. (2).

Tomb (38)

Cleaning of chamber proceeding. Stone on sides apparently found & chamber seems to be ca. 2.70 m wide. We have gone in about 1.60 m inside door. No pottery but we are digging at ca. 70 above stone.

Tomb (39)

Seems to be only a small recess at inner end of domos without a real chamber. The bones found before in what we thought was a pit continue inward. Two skulls at least. Further in is a mass of bones & pottery. 4 pots at least - all jugs one with 2 holes & with 1 hole. former unpainted latter painted. We go on clearing with one workman.

Tomb (40)

Cleaning of chamber proceeding we have now advanced ca 1.45 m inward with a width of 1.90 m. But since no door has yet been found. Huge slabs of conglomerate above is cracked off from ledge over tomb & workmen fear it may fall. So we begin to dig out a small hole down to floor with intention of putting in a wooden support.

A few small sherds, only found today.

Tomb (41)

4 men

Dromos very well cut & regular nearly 10 m long. rock floor at inner end. Ca 1.00 m fill of stones in front of rock.

Sides have regular inward inclination & top of dromos is very narrow. Breadth below steep downward slope. Stone floor floor at outer end.

At outer end dromos ca 1.05 m wide.

Sunday April 29

Spitzer & George Mylonas left by the morning train

At 10 AM we leave in 2 cars for Nemea. Stay there until ca 3 PM. Lunch from hotel.

Then go to Mycenae & stay until dark. Show acropolis & Treasury of Atreus to Beroplos

Return to Naupha in evening.

Party: Mrs & Mrs Sample

- ⊙ H C
- A H
- M R
- CWTS

2 cars: our own & Hadjiko's

56 Photographs Film pack E

- 452 (9) M H grave XIII from NW
 453 (10) Tomb (34) from W
 454 (11) M H grave XIV from NW

May 1

- 455 (12) Bonespots in heap in West area of Tomb (36) from SW

Film Pack F

- 456 (1) Bonespots in Tomb (39)
 457 (2) Dromos of Tomb (41) stone full at back
 458 (3) Bones of goat in chamber of Tomb (48)
 459 (4) M H grave XVI from NW

Monday April 30

(57)

43 men

11 in Tomb (34) 2 in chamber
 7 " dromos
 2 moving dump

3 " " (36)

2 men " (37)

2 men " (38)

2 " " (40)

4 " " (41)

4 " trial trenching lower E of gully

4 " " " upper " "

2 " in E H wall

2 " in E H corners

2 " " (46)

2 " " (48)

1 washing pottery

1 roping baskets

1 water carrier

2 cans - amara & Habylcos

Tomb (42) just 3 m n. of wald stems Tomb II we find diagonals of another tomb, running diagonally in toward ridge we call this Tomb (42)

In afternoon I start one man opening N.H. Grave XIII. This grave had got covered up by dump from Tomb (34) & had to be re-excavated.

Looking for beehive on top of W. Yrogalaro. Nothing definite yet but some of the timber east of some slopes down hill to N.W.

Tuesday May 1

43 men

- 2 men exploring north of W. Yrogalaro
- 6 men in Tomb (34)
- 3 " " " (36)
- 1 " " Grave XIII
- 2 " " Tomb (37)
- 2 " " " (38)
- 2 " " " (40)
- 3 " " " (41)
- 2 " " " (42)
- 2 exploring in field N. of Camp
- 1 pot washed
- 1 roping baskets
- 4 tunching on Upper Yrogalaro
- 4 in Tomb (45)
- 4 " " (46)
- 3 " " (48)
- 1 water man

2 cans: our own & Hadjicos

60

Tomb 34

Dromos now cleared out to stereo floor ca. 9.50 m long; ca. 1.05 m wide at outer end ca. 2.00 m at door. Floor slopes downward toward door. At door ca. 3.75 m deep below surface of ground.

Sides of dromos have slight inward inclination.

Door jamb roughly at 90° with side walls. ca. 0.50 m wide. Door roughly centered ca. 1.00 m wide. Preserved height 2.20 m. Filled with a stone wall made of small unworked stones, substantially built but not very neatly.

- Slight suggestion that door was arched at top.

Chamber. Apparently very large. We are still ca. 1.50 m higher above level of dromos at door.

At this level we find skeletal remains of small animal (dog?) in central area. Other animal bones to right. 2 very large jaws to left. Litter hyacinth near side at back right. At extreme right an ostracon. Just inside door a small jar. All these pots apparently of geometric period. A small bronze bowl of same period just inside door at same level.

Tomb 36

61

Still very puzzling, but clarifying. Seems to be a small chamber (over western chamber) long & narrow. In door in SW narrow end.

ca. 2.00 m wide at entrance narrowing to ca. 1.75 at inner end. ca. 3.70 m long. Rectangular at outer end rounded at inner.

Whole rear part for distance of ca. 1.20 is a bonepile with many pots. Next come 2 or 3 pots.

Floor appears in front part, on it only 2 pots, 1 figurine & some fragmentary bones. Also one long vase, 1 jug & 3 figurines & small jar.

Indication of a door roughly centered in outer short end wall still in place ca. 1.00 m wide 0.75 m high.

No dromos to get.

Side door in this chamber leading to east. Perhaps to side chamber in this direction. Here we have in a small area near door 4 pots on floor & a plain jug to be in our trial trench April 18 (cf p 14) also belongs here.

62) M.H. grave XIII

Opened yesterday afternoon - i.e. cover slabs removed. We tried to dig out today. Turn out to be a nicely made rectangular cut out in stereo. ^{in line} wide. Bone in bad condition. 2 good pots appear. a small goblet or calyx apparently in Gray masonry. a cut with side handle in masonry was.

Tomb (37)

Cleaning chamber proceeding slowly. Filled with hard packed stereo like that in No. (17). Right side apparently found, but not left or back.

Doorway ca. 75" thick from front to back.

Tomb (38)

Work proceeding slowly in chamber. Back wall to. Depth of chamber front to back ca. 3.00 m. Side to side the same. Somewhat rounded corners.

Doorway ca. 1.00 m thick from front to back.

Tomb (39)

63) Drawn by D.H.C. Today
Photographed by C.W.R.
Described by M.R. p. 30 ff
Pots removed.

Tomb (40)

Work inside goes on with good speed. Stereo side to in right also at back. Not get at left. Floor of chamber reached.

At right of door some bones and 1 chalice mtd just on floor. At left, bones on floor.

Chamber ca. 1.80 m front to back.
Doorway ca. 95" m ^{width}

Tomb (41)

Dromos nearly cleaned out. Stereo floor to almost up to door. Step descent - almost step like in middle part of dromos. Sides beautifully cut regular taper. Mass of stone in front of door ca. 1.65 m high. rest on earth apparently at least 1.00 m above floor. They are fill not sand itself.

In trench across field below
 E. N. field on upper E. Myrogalina 3
 11th grave is One small one
 in middle between other two had
 no cover slabs (Removed in flow-
 line?) above bones are broken
 with pits of 1 yellow Myrogalina
 of D.H.C. p 41 Grave XV
 Two others are slab graves

Tomb (48)

Bones of a goat to be seen
 center of chamber. Attempt
 to photograph them to D.H.C.
 draws them
 Good progress being made
 in cleaning out chamber
 no finds yet

Tomb (45)

We dig down from above &
 go through local stone fill which
 may or may not be dolo
 Chamber above are very small
 but all collapsed and we
 may not have original order yet

Tomb (46)

Rapid progress in cleaning
 chamber from above. Sid & Ed
 cut in stereo. A small rect-
 angular chamber with slightly
 rounded corners
 By 5:30 PM we reach final
 dirt. Bones begin to appear
 along left side of chamber
 Chamber measures roughly 2.40
 by 2.40 m

- Photographs Film pack F
- 460 (5) Dromos + door of Tomb (36)
- 461 (6) Bones & 2 pots in Grave XIII
- 462 (7) Dromos + door of Tomb (34)
- 463 (8) Dromos + door of Tomb (36)
- 464 (9) Side Chamber + door of Tomb (36)
from South
- 465 (10) Two large pots in Chamber of T. (34)
- 466 (11) NH Grave XVI on Upper E. Yperogalano
after cleaning
- 467 (12) NH Grave XVII slabs covering it
in place from East

Wednesday May 2

(67)

45 men

- 3 men in Tomb (34)
- 3 " " " (36)
- 1 " " Grave XIII
- 6 trial trenching on upper W. Yperogalano
- 2 in Tomb (37)
- 2 " " (38)
- 2 " " (40)
- 2 basket carriers
- 3 men in (41)
- 2 " " (42)
- 2 trial trenching on lower Yperogalano
- 1 pot mender
- 1 water carrier
- 1 man in Grave XVI
- 5 in Tomb (45)
- 2 " " (46)
- 5 " " (48)
- 2 trial trenching

Kephelano Hill

upper Yperogalano

2 cars: our own + Hadjidakis

Tomb trench in field west of
Tomb 37 2 men working
all day digging a long trench
in red earth. At ca. 25 below
surface in east part of trench
found 2 pieces of bronze & some
beads. The bronze pieces include
fragments of a guffin's head, end of
of a very thin sheet of bronze,
scale disc below neck. Egyptian
style. Small piece

Tomb 41
Two gold beads from dromos
today. They may be a small
one in front of door.
Monk and 2 of diggers spent
in tent with one other man
with knife. More gold beads found.
2 kinds: hly-shaped & melon
shaped

Grave XIV cleared today.
Nothing except a potsherd
& an oval piece polychrome pottery
at the small oval from Sixth
Shaft Grave at Myrae

Tomb 48
Very deep chamber far below
level of floor of dromos. Today
we finally reach remains. Great
heap of bones and pottery to
left. At least 8 or 9 pots appear
in course of the day. All seem
to be L.H. III mostly unpaired.
Bones mainly in bad con-
dition. Traces of at least
three skulls so far, but none
at all preserved.

Tomb 37 3 men in dromos
Progress slow. Have advanced
a little more than 2 m but
back not yet found

Tomb 38
All side of dromos we are
slowly going down. Still ca.
35 to go to floor. Bones appear
at this depth under a large
stone removed

70 Photographs Film Pack of

May 5

- AH. 468 ① MH slab covered grave below Tomb
 ④① poor S ~~XX~~
- 469 ② MH grave slabs to West of the
 ceiling - from ~~E~~ ~~XIX~~
- 470 ③ MH Grave XVII showing pots
 & shells - cleared

May 6

- 471 ④ Door of Tomb ④① (poor light)

Thursday May 3

(71)

46 men

- 3 men in ③④
 1 sifting earth from T. ③⑤
- 4 men Upper W. Yperogalero
- 3 37
 3 38
 2 40
- 2 trial trenching near Kephalaria
 1 in E.H. M.H. grave
- 2 men in ④①
 2 ④②
- 2 trial trenching on lower E. Yperogalero
- 1 man in Grave XVII
 2 trial trenching on slopes E. Yperogalero
 2 digging caurns of
- 5 men in 45
 2 46
 2 48
- 4 exploring for beehive tomb
 1 pot mender
 1 water carrier
 1 sent to Argos for oranges

Mr & Mrs Sample left by the morning train

12 Tomb (34)
Work goes on in chamber. A
human skull appears to left center.
Photo continues past to right center.

Tomb (35)
Earth from chamber sifted

Tomb (36)
Drawn by JHC in forenoon
Begin removing pots after lunch

73 Tomb (41)
3 more gold beads from east
at inner end of dromos. The
cut appears to continue on under
stones left in front of door. So
we proceed to remove some
of stones & look for wall
closing door behind them.
Some of stones fairly large.
A hole appears above door into
tomb - very small, but mortar that
roof has not fallen.

Door jambs finally appear.
Large chunk of stone on left side
of dromos at door appears to have
fallen & pushed out stones of
door wall.

Tomb (42)
Dromos being followed out.
Seems to be a fairly big
one & some good pottery
comes out of it. Practically
all LH III & end of Mycenaean
quality.

Trial Trench in field west of
Tomb VII

Here we strike an red con-
glomerate stone a cutting of
sort filled with dark earth
& some Mycenaean pottery.
Begins to take shape like
cutting of dromos (?) Now
ca. 1.30 deep below surface
(ca. 1.15 below stone) & ca.
2.00 in wide. We go on
digging down.

(45) Tomb (45)

Digging down from above we are approaching floor of chamber. Nothing to see. Back of tomb cut in stone is clear, but neither side yet revealed. Whole forward part of ledge over tomb has fallen & we have loose stones on either side.

Tomb (46)

We are slowly digging out floor with knife & find quantities of bones on left side of chamber, but no pots yet. A few good sherds very tantalizing.

Tomb (48)

Floor being cleared slowly. Great heap of bones at back of left. Bones also to right. 10 or 11 pots now visible - none of special merit apparently.

M.H. Grave XVII

75-

Very interesting small pot practically no bones but 2 small pots, some large scapulas, (knives) & beads of a necklace? beads of bronze, & of crystal.

One more M.H. Grave to just SW of Grave XVII. No cover slab. This is grave XVIII. It contains at least 5 small pots.

Grave XIX. Down slope west of Tomb (2) in pit. Photographed. Slab removed & 1 man begins digging out the grave. Finds 3 small pots by evening.

96

Tomb (37)

Work proceeding in chamber.
Steps for all the way around
now. Chamber is 2.70 m
deep front to back & 3.25 m
wide. We are still to be
in above floor of drums outside
door.

Tomb (38)

We are nearing floor. There
seems to be a heap at each
page of a pot appear and a
few figs of animal.

Tomb (39)

Finished

Tomb (40)

Steps now for all the way
around. Work goes on toward
floor. Apparently a heap on
left side.

Friday May 4

97

45 men

5 in Tomb (34)

1 " " (36)

4 trial trenching upper w. of pyramid

3 in Tomb (37)

3 " " (38)

2 " " (40)

2 trial trenching near Kephalar Hill

1 in grave XIX

1 in Tomb (41)

2 " " (42)

2 trial trenching w. of Tomb (9)

4 trial trenching upper E. of pyramid
1 cleaning grave XVIII

4 in Tomb (45)

2 " " (46)

2 " " (48)

4 trenching for beehive tomb

1 vase mender

1 water carrier

40 Trial trench in field west of Tomb (7)
We enlarge our trench to west to
examine further the cutting we have
fd. in rocky red siliceous
Near surface *Prolocombina* shells
also two complete bronze pins connected
by a fine bronze chain with 18 links

Tomb (36)
Measured & drawn by JHC chamber,
heap, cist, side chambers & all
All pots out by evening

Tomb (34) Work goes on steadily
JHC draws upper level & all
geometric pots taken out

Tomb (41) Dromos & door finished
for drawing or photographing

Tomb (42)
Following out dromos - it is
becoming a large one. Got
shells L.H. III

Tomb (45) 79
Sides now fd & chamber seems
to be approx. square ca 2.25 m
front & back by 2.60 m side to
side.
At ca. .30 above level of dromos
(outside door) we begin to find
bones. A skull directly inside
door. At back of chamber
straight ahead of door a large
pot appears - Tell el Amarna
style.

Tomb (46)
Floor almost cleared. A great heap
of bones along left side of chamber
At least five skulls in unsorted
state.
Central part of floor empty of
bones.
Along right side one skull &
4 leg bones - perhaps remains
of last burial in tomb.
In outer right corner a small
cist along side wall, full of
bones.
One to two fig of animal & 1 pot
finally appear in heap to
left.

(30)

Tomb 248

Finished for drawings

A great heap of bones on left but does not reach to front wall. At least five skulls appear in the heap, all in bad condition, but there must have been more.

9 or 10 pots appear in the heap along front wall to left of door, and two pots

In center of chamber bones of one skeleton, possibly in order. 1 skull badly crushed

To right of door one pot - a plain jug

Grave XIX: Below T. (2) cleaned, finished this morning. Has 8 small pots - chiefly with painted

Grave XX just E of XIX. partly cleared by evening. got produces 17 small pots - mostly with painted - some beads. There are also some sea shells.

Tomb 37

Steady progress during day, but somewhat slow going

(81)

Tomb 38

Digging down to floor. Great heap on left with many pots.

At back also a heap probably; a fine long slender bronze knife here also a bronze cleaver. Just inside door a huge amphora shattered.

Tomb 40

Along left side a heap of bones, etc. is developing. Making pots here

82 Photographs Film Pack G

- A.H. 472 (5) Door of Tomb (34)
 473 (6) E.H. cairn (?) on upper terrace (T.H.) E Yuzgalano
 = Cairn G
 474 (7) M.H. grave XVIII 5 pots from NW
 475 (8) M.H. grave XXI bones & slabs from W
 476 (9) M.H. grave XXII slabs from W
 477 (10) M.H. grave XXIII " from NW
 478 (11) M.H. grave XX cleaned with 12 pots
 showing
 479 (12) M.H. grave XIX cleaned with
~~12~~ 8 pots visible

Film Pack H.

- 480 (1) Door of Tomb (41) (Failure?)
 481 (2) Door of Tomb (41)

Saturday May 5

83

45 men

- 6 m T. (34)
 3 m T. (37)
 3 " " (38)
 2 " " (40)
 3 " " (42)
 1 " Grave XX
 6 trial trenching lower E Yuzgalano
 2 " " " W of T. (7)
 8 trenching upper E yuzgalano
 1 cleaning M.H. graves
 2 m T. (45)
 2 " " (46)
 4 trial trenching on W Yuzgalano
 1 pot mender
 1 water carrier

84

Tomb (46) finished for drawing.

Tomb (48) also ready for drawing.

Tomb (45)

Many pots are beginning to appear in rear part of chamber.

Chief interest today in opening up M.H. cemetery on upper E. slope. At least ten graves now found very close together but irregular. Some covered with slabs some have none. Apparently all contain pots. Some beads also & shells.

5 small pots in grave XXI

Trial trench in field west (85) of Tomb (1). Here we are gradually finding what appears to be a dromos. Some few large potsherds come to light.

T (43) Trial trench between Tombs (3) & (4) for a clearly marked dromos in NE of (3)

Sunday May 6

In the afternoon we drove to Kephalaria, SW of Angos to see prehistoric site mentioned by Anagnostopoulos. There is a low mound on a sort of island between two streams that issue from the Kephalaria. I could find no prehistoric sherd on it, though it is pretty well buried in sand & gravel & there may be prehistoric remains underneath.

Along the road across the stream on the south side of half a dozen small sherds that look to me like "Walkline" - corresponding to Second Period Thessalian Hat 6

Monday May 7

44 men

6 men in Tomb (34)

3 " " Tomb (37)

3 " " Tomb (38)

2 " " Tomb (40)

2 in field W. of (39)

2 in Tomb (42)

4 trial trenching on lower E Myzogaluro

4 in Tomb (45)

8 in NH cemetery on upper E Myzogaluro

4 trenching on lower W. Myzogaluro

4 trenching for shaft grave below Temple

1 vase mender

1 water carrier

88 Photographs Film Pack #

- AH.
- 482 ③ Bone heap on left side of chamber of Tomb (46)
- 483 ④ Bones in Grave XXI NEE rd - from North
- 484 ⑤ Dromos + door of Tomb (48)
- 485 ⑥ Bone heap + pots on left side of Tomb (48)
- 486 ⑦ Bones + pot on right side of Tomb (48)
- 487 ⑧ Left side of chamber of Tomb (48) from door

May 8

- 488 ⑨ Dromos of Tomb (42) as it now appears

May 10

- 489 ⑩ Interior of Tomb (40)
- 490 ⑪ Right skeleton in Tomb (37) (failed) upper layer
- 491 ⑫ Same as ⑪

Film Pack 9

- 492 ① Left skeleton in Tomb (37) upper level
- 493 ② MH grave XXV cleaned from above
- 494 ③ MH grave XXIV " " "
- 495 ④ MH grave XXIII " " "
- 496 ⑤ MH grave XXIV " + door

Tomb (46)

DHC begins drawing this morning
Pots etc taken out in afternoon. Deep cuts to left + right remain
Lentoid seal of steatite.

89

Tomb (45)

Note fragment of Ephyraean pot in middle of chamber

Before breakfast I start 4 men enlarging SE ward our old Trench EXIX looking for another shaft grave on slope below Greek Temple. Add 2 more men after lunch.

Tomb (40)

Finished for drawing today

Tomb (34)

Digging down in chamber we reach level ca. 0.90 m above floor of dromos outside door.

(90)

Tomb (37)
 Good progress made in chamber

Tomb (39)

Floor reached on half of chamber. Some fine beads of paste from right side.
 A dentoid seal of stibite in worn condition.

Made the Hadic cemetery on Upper E. Yuzgalar.
 It seems to be petering out
 2 or 3 graves contain no bones
 and other bones.

Tuesday May 8

(91)

45 men

6 in Tomb (34)

5 in Tomb (37)

3 " " (38)

4 " " (42)

2 " " (43)

2 trial trenching below Tomb (2)

6 in M.H. cemetery on Upper E. Yuzgalar

2 in Tomb (45)

2 " " (46)

7 digging for shaft grave below temple

4 trenching for beehive on lower W. Yuzgalar

1 pot menders

1 water man

92

Shaft grave trench.
 7 men work proceeds fairly rapidly. Bronzes & pottery beginning to appear.
 Part of a large amber bead

Trial trench below Tomb (2)

Here we find at a depth ca. 1.20 a cutting masonry with right angle turn within a Mycenaean fill. Maybe some soil of shaft grave? So far only a little of it shows in our trench. 1.30 trench enlarged toward south



Beehive tomb chases work all day on W. Mycenaean far down slope below our Tomb (1). Nothing

Tomb (44)

93

This morning we opened (44) & found a difficult problem. The rest of conglomerate has partially collapsed & fallen into the chamber in large chunks - not easy to remove. It looks as if we shall have to dig down first above & break up conglomerate for safety.

The chamber is fairly large & the surviving part of the roof does not look any too safe. It has split into sections & fragments which may easily fall. The chamber may have collapsed fairly recently.

Tomb (41)

After lunch we open door of (41). The greater part of the roof is still intact & looks perfectly sound. But the lower part of the front portion have fallen into the chamber & the anterior part of my chamber is full of loose conglomerate. This heap of debris slopes gradually down to a rear of chamber ca. 2.00 m high at front.

Chamber is a large one, at present with a niche or an enlargement at back as was the case with (29)

94

Tomb (48)
Drawn by D.H.C. & photo ready
for removal

Wednesday, May 9

95

.47 men

- 6 in Tomb (34)
- 3 " Tomb (37)
- 3 " " (38)
- 2 sifting (39 & 40)
- 4 in Tomb (41)
- 4 " " (42)
- 2 " " (43)
- 2 " trench below (2)
- 4 " Tomb (45)
- 3 in M.H. cemetery
- 4 on lower W. Yungulaw trenching
- 8 diggers for shaft grave below temple
- 1 pot mender
- 1 water carrier

96)

Trial Trench below (2)
 I spend most of day here trying
 to find limits of possible shaft
 grave. It finally proves to be
 ca. 1.50 m wide from N to S.
 + considerable more in length. We
 cut the north of S side out in
 stone but actually rock covers
 W end & we can't tell how long
 it is. Some stone in middle
 of end suggest a door &
 it is possible that we have
 only the drums of a chamber
 tomb. If so the drums run
 in a queer direction (W to E)
 with reference to the existing ledge
 of rock. very queer.

XIX

K

Trench below Temple Terrace
 Work goes on all day up &
 we reach top of the
 wall uncovered in 1928 in Tr.
 E XIX. It goes on in
 ward. Skids on both sides
 of wall geometric & Mycenaean
 also some M.H.
 On N side of wall earth is
 brown in color & firm. On
 S side much darker & looser

Tomb (34)

(97)
 Today we finally strike pay
 dirt. Large heap of bones to left
 in niche in side wall & left
 of door.

Tomb (37)

Two practically complete skeletons
 now cleared. They evidently
 belong to an upper layer. We
 sweep them & plan for drawings
 & wait.

Tomb (38)

Finished for drawing by
 evening.

Tomb (40)

Drawn by D.H.C. this morning
 waiting for a photograph

Tomb (41)

4 men removing fallen rock
from chamber make good progress

1 man sifts earth from cut in
dromes piles up old beads,
paste & fragments of bronze
arrowheads.

Tomb (42)

Dromes. 4 men digging
Dromes seem to be very large
& long. Good prospects.

Tomb (44)

After lunch put 8 men
on digging down from above
on chamber.

Tomb (48)

Pots removed this forenoon

Thursday May 10

47 men

6 in Tomb (34)

2 " " (38)

5 " " (41)

5 " " (42)

2 " " (43)

2 below Tomb (2)

3 in NH cemetery

4 in Tomb (45)

8 " " (44)

8 trenching for shaft grave

1 pot mender

1 water man

100 Photographs. Film Pack 9

AH
497 Drama of Tomb (42)

May 11

498 Skeleton in Tomb (38) from door.

499 Heap of bones & pots in outer left corner of (38) from inner right corner.

500 Door of Tomb (42) with wall still in place

501 Gen view of heap of bones & pots in Tomb (45) from door

502 Skeleton in dist to right in Tomb (45)

503 Bones etc in Tomb (45) from above.

Tomb (42)

(101)

Doors nearly finished. At inner end is a considerable fill of stones. Some very large ones but not properly built. Pushing stone floor. Look like fill or like displaced remains of built wall of door. We take these out & then behind them find proper door wall.

Shaft grave trench below Sanctuary. Our trench is going down rapidly. Size roughly 5 x 6 m. runs SE.

ZZ



The upper wall from E XIX continues right across outer trench. Lower wall not yet to very far.

We now have brown earth on S as well as W side of wall. On S side we brown earth & pebbles some good Mycenaean sherd. There late. So far as I observe fine little stratum (?) we have reached a depth of 1.60 on S side of trench at (X)

Trial trench below Tomb (2)

our "shaft grave" (p 96) now
begins to look like mass burials
of a regular chamber tomb. We have
dug down deeper & find well laid
stones of a door to East.

(49)

Dug a cross trench ca 7 m west
to see if we can pick up dromos.

K

No definite result
So far as digging down in
area we have ^{so far} dug up
west to follow up as far as cutting
goes.

Photographs May 11

Film (1) (3 A size)

- AH 371 Dromos of Tomb (43)
- 372 View of Kephalaria Hill from dump
above Tomb (2)
- 373 Slab in field betw. Lykos & Kephalaria
possibly corner of a grave
- Max 374 Door of Tomb (42)

45 men

- 6 in Tomb (34)
- 2 " " (37)
- 4 " " (41)
- 5 " " (42)
- 2 " " (43)
- 4 trenching below Tomb (2)
- 5 in Tomb (44)
- 1 sifting - Tomb (46)
- 4 trial trenching upper E. of Lykos
- 2 " MH cemetery
- 8 Shaft grave trench below temple
- 1 pot menders
- 1 water man

104 Shaft Grave Trench E XIX

5 men go on here digging down. We have reached sterile line & then on S side of the long wall. It is rock which slopes down from E to W.

Shortly after 2:30 P.M. whole area is cleared down to rock. A fairly deep depression along S side of trench but seems natural.

I shift our gaze to N side of long wall & with another start a long trench to west.

Tomb (41)

Down below (2) This now seems certainly a dromos & I start to open toward west & to dig down into chamber E of door. I call this tomb (49)

Tomb (43)

Good progress during day. The dromos is almost finished. I put 4 men on pit over collapsed chamber.

Tomb (41)

105 Pot (LH III stirrup vase) & some bones found at back. We clear out dug earth & begin with knives. At back in niche Elmore finds heap of bones & pots. Just before evening found 2 small bronzes ones a javelin point, and a small wing comb.

Tomb (42)

Dromos finished this morning. Ca 12.50 m long ca 1.10 m wide at outer end 1.90 at door. 4.70 m deep at door. Floor slopes steeply but irregularly. Sides incline inward considerably & were well cut though now somewhat damaged.

Tomb (34)

Almost finished full of pots, bones & cists. Second knife today. Very deep cist just inside door. Lots peculiar marks an earlier level below over a good part of chamber.

Tomb (37)

Two complete skeletons in upper layer removed & digging goes on below. Some good pots begin to appear.

106
A.H.
504

Photographs Film Pack J
Door of Tomb 42.

May 14
505

Stone fill at inner end of door of
Tomb (43)

Saturday, May 12

107

47 men

- 3 in Tomb (34)
- 2 " " (37)
- 3 " " (41)
- 6 " " (43)
- 6 " " (49)
- 4 trial trenching S of (49)
- 2 trial trenching between (7) & (14)
- 5 in Tomb (44)
- 3 " " (45)
- 2 trial trenching on W side E of pyramid
- 1 in MIT cemetery
- 8 trial trenching below Temple E XIX
- 1 post box
- 1 water carrier

108

Tomb (49)

Very queer. Dromos now appears to be only ca. 2.75 m. long. Are it has steps (?) First is 0.55 m. broad (or rather second).

A small button of stucco on the long side face of second step. Most of heads here are MH (yellow Myanmar's type)

Tomb (43)

Dromos nearly finished. Ca. 11.25 m. long ca. 1.50 m. wide at outer end 1.65 m. at door in floor. Floor at door 2.70 m. deep below present surface. Broad type of dromos. Sides regularly & well cut. Have slight inward inclination.

Above door at inner end of dromos are two great boulders reaching present surface of ground we remove them & dig in to find door.

One gang digging down above chamber which had collapsed.

Tomb (41)

109

Cleaning back of chamber with knife. Near left corner find a skull. Near it a bronze pin (?) & not far away a small wavy (?) comb. Yesterday on other side of skull a small gold ornament of bracket type & a stucco button.

Tomb (42)

After breakfast we open door. Upper part fairly loose & projects from doorway. Includes one very large stone (possibly a lintel of some period). Among stones & earth here we find several fragments of a large amphora of the Palace Style (Kakorath type).

The lower part of the door is somewhat recessed in the doorway. Looks fairly rough of small stones but is solid. Lintel. This evidently belongs to an earlier period than the upper part. We are leaving it in place to be photographed.

The chamber is ca. 4.50 deep by 5.00 wide. Looks roughly circular. Front part above door has collapsed & chamber is pretty well filled with loose fallen rock.

Door wall lower part 2.05 high ca. 1.00 wide at bottom ca. .75 at top. Smallest stone except at bottom where it projects into dromos.

In the top course of the wall was a small flat piece of stone apparently shaped - looks like quarter of a circular disk.

In afternoon we drove to Asine thence to Kardari & on to Iria. Fine drive - road mostly good & fine along cliff above sea. The village of Iri or Iria stands on a hill above. Mycenaean shreds have been found. Good site for a Myc. town.

112 Photographs May 14 Film Pack J

- 506 ③ Slabs covering grave XXVIII ca.
12 m. S. of domos of ④④ from E.
- 507 ④ Door of Tomb ④⑨
- May 14
- 508 ⑤ Door of Tomb ④③
- 509 ⑥ View from above of outer left corner
of Tomb ③④ with cists
- 510 ⑦ View of heap in rear right corner
of Tomb ③④ from above
- 511 ⑧ View of rear right corner heap
from West Tomb ③④
- 512 ⑨ Cist in side wall outer left
corner Tomb ③④ from E
- 513 ⑩ Skeleton in rear left corner of
Tomb ③④ from S.

Monday May 14, 1924

- 44 men
- 2 in Tomb ③⑦
- 4 " " ④①
- 5 " " ④②
- 3 " " ④③
- 4 " " ④⑨
- 6 trenching near ④⑨
- 2 " " ④⑤
- 5 in T. ④④ ④⑤
- 2 " " ④⑤
- 1 sighting
- 2 " Tomb —
- 6 shaft grave hunting below temple
- 1 water man
- 1 pot mended

114

Tomb (34)

No work here. All ready for photographing & drawing

Tomb (37)

2 men cleaning lower level in chamber. 7 skulls to det. Pottery fragments seems very good. 2 H. etc.

Tomb (41)

4 men slowly cleaning floor of chamber. 13 at night in morning. One small piece of gold leaf found in dump - prob from dials. A bronze cleaver in good shape for near center of tomb. Fragment of worked bone or ivory handle.

Tomb (42)

5 men. Removal of fallen rock goes on fairly rapidly

115

Tomb (43)

3 men digging down in chamber. getting fairly deep, just before noon. & photograph stone fill making door & begin to take it out & reveal door wall itself.

Door wall cleared & cleaned for photographing. Fairly regular. Ca. 1.07 wide on floor. increased to height of 1.40. 88 wide at present top. Ca. 6 courses smallest stones. One course larger stones near bottom - then earth for 0.25 - & 1 course on floor.

Tomb (49)

Dromos finished & men join others in digging down in chamber.

Door now 1.30 m high .80 m wide at bottom. .65 m at top. Upper part regularly built of small flat stones. Lower more rough of larger stones than latter ca. 0.50 above floor.

Dromos short & has two steps. Lower step 2.10 m from door is .50 m high faced on top is .60 m deep. Upper step is .40 m high.

Sides of dromos fairly well cut with very slight inward inclination.


Floor below lower step has trifling slope down to door. When it is 2.45 m deep below present ground level.

Original extent of dromos beyond top step uncertain.

116

M H (?) grave XXVIII ca 12 m S of
end of domos of Tomb (44)

Marked by two large stones, one a slab
set on edge, the other a rough unworked
chunk of limestone.



Slab is 95
long ca. 20
thick
reached surface
of ground
ca 0.45 m high

Trench below Tomb (49)

Has now become very deep
main stone appears on the edge
mostly sterile & sterile & sterile pretty
generally. Protoconchid shells &
brometric shells some iron
fragments also some

A rather nice small thin
bone or stone dish with punched
ornamentation for use as a
two handles present.

Tuesday May 15

117

46. men

1 sifting T (34)

2 in Tomb (37)

2 " " (41)

5 " " (42)

4 " " (43)

2 " " (49)

4 trenching near (49)

3 " " (45)

5 in Tomb (44)

1 digging M H grave XXVIII

2 " " (45)

2 sifting

2 in Tomb on the hill

8 tamping shaft graves below temple

1 potmender

1 water man

118 Tomb (43)

Photograph done this morning. Preserved well to a height of 1.40. Some stones left to a height of 1.30. We remove upper part of door & chamber through dromos. In east fill between stones at level ca. 1.05 above floor & ca. 30 m from face of door wall for a complete brick lamp.

In the collapsed rock filling the chamber top of Greek tiles have also been found. Excellent Corinthian type. Good progress in chamber. By evening we get down to ca. 1 m above floor of dromos.

Tomb (49)

Progress slow. We remove upper part of door & carry out earth from chamber through dromos. By evening we get down to ca. 0.50 m above floor of dromos. First pot found broken.

Tomb (30)

Ca. 5 m to N.W. of (49). We find another short dromos, apparently with steps.

Tomb (8)

A new tomb found just N.E. of gymnasium. Grave VIII of 1925.

Tomb (41)

Cleaning progresses more than half of chamber now done. Bricks cleared removed.

119

Tomb (42)

Good progress removing fallen rock. By tomorrow we shall be approaching floor of chamber.

Shaft Grave Trenches E XIX

Two long trenches being dug westward from E XIX.

In southern one we find several Greek blocks & a spherical sundial of marble diam. ca. 0.50 m. It bears a dedicatory inscription as follows:

ΗΡΗΣ ΠΡΟΠΟΛΟΣ ΜΕΘΕΝΣ ΑΝΕΘΗΚΕ ΘΑΛΕΙΑ
ΗΛΙΑΚΩΝ ΝΩΡΩΝ ΑΠΤΕΛΟΝ ΗΜΕΡΙΟΥ

Also the name of the tribe sign of the Zodiac arranged among the feet of stones the hours - 1 on each side of the centre.

Κ Α Ρ Κ Ι Ν Ο Σ Δ Ι Α Υ Μ Ο Ι
Λ Ε Ω Ν Τ Α Υ Ρ
Π Α Ρ Θ Ε Ν Κ Ρ Ι Ο Σ
Ζ Υ Γ Ο Σ Ι Χ Θ Υ Ε
Σ Κ Ο Ρ Π Ι Υ Δ Ρ Η Χ Ο
Τ Ο Σ Ο Τ Η Σ Α Ι Γ Ο Κ Ε

AH
May
514
515²

Photographs Film Pack J

Cut in outer right corner of Tomb (34)
from NW
Tomb (34) Cut in outer right corner
from NE

Film Pack K

516 ① MH grave covered by slabs (NE of
Tomb (9) with EH wall (B) behind)
= grave XXIX

Wednesday, May 16

(121)

46 men

- 2 in Tomb (34)
- 2 sifting in Tomb (37)
- 2 " " " (41)
- 2 in Tomb (41)
- 5 " " (42)
- 6 " " (43)
- 4 in Tomb (49)
- 2 " " (50)
- 5 " " (44)
- 2 " " on the Hill
- 2 in Tomb (8)
- 2 trial trench near Tomb (9)
- 8 in shaft grave Trench E XIX
- 1 pot mender
- 1 water man

Mrs H. Talia chg of Tomb (8)
Mrs Kawa " " " (42) + (50)

Saturo, the chauffeur left this evening
after 1 month's service. Paid up.
Asanasi gets us another man for
tomorrow.

3TH & 2DB arrived this evening

122

Tomb (43)

Digging out of chamber from above progressing. Shape of chamber not yet clear. Possibility of a side chamber to right. At least fallen stones extend in two directions & some stones appear which may belong to a wall closing a door but are obstructed & cut away considerably on hanging rock to right. All fallen debris under it. At ca. 1.00 m above floor of dromos find a small bronze Euxine amphora & a phiale & a few fish shreds & shells.

Tomb (49)

Work with knife cleanup down toward floor. A second pot appears - like the first Mycenaean. 2 sides of chamber apparently found but back not yet certain.

Tomb (50)

Working down above chamber. Its size not yet clear though two sides seem to be found.

123

Tomb (41)

cleaning of chamber goes on - only front part left to do. Lower part of a well preserved skeleton appears directly in front of door. Many pots in tomb - chiefly cubes on high stem. Some tall albanian style pots also. Returning earlier than 1/4 the has appeared yet.

Tomb (42)

Good progress in getting down in chamber. In afternoon we reach ca. 0.60 m above floor of dromos. Nothing found yet.

Shall grave trenches in a. E. XIX

Good progress made in both trenches going down to strata. Brown earth with Mycenaean shreds reached in S trench by end.

Bronze fibula found in east part of S trench, flattened back which turns into wire for pin 0.06 m long. Pin is a small thin bronze disk.

124
May 17

- Photographs Film Pack K
- 517 (2) Door of Tomb on the Hill (51)
- 518 (3) Door & chamber of Tomb (50)
- 519 (4) Stones on right side of chamber of Tomb (43) door to side chamber (4)

May 18

- 520 (5) Stones in chambers of Tomb (9) from NW

May 19

- 521 (6) Door of Tomb (8) with wall
- 522 (7) Door of Tomb (9) " "
- 523 (8) Bones etc on heap on left side of Tomb (37)
- 524 (9) Spotted
- 525 (10) Stones built up on right side of chamber of Tomb (43)

May 22

- 526 (11) Stones covering E.H. grave (?) near T (10)

May 24

- 527 (12) Pot fragments & base of pot containing burnt bones in door of Tomb (41)

Thursday May 17

(125)

- 47 men
- 2 in Tomb (34)
- 1 sifting from Tomb (37)
- 2 in Tomb (41)
- 2 sifting " (41)
- 5 in Tomb (42)
- 6 " " (43)
- 4 " " (49)
- 2 " " (50)
- 5 " " (44)
- 2 " Tomb on the Hill
- 2 trial trenching below (44)
- 4 in Tomb (8)
- 8 in shaft grave trenches
- 1 pot member
- 1 water man

First trip with new chauffeur van today

Tomb (43)

Cleaning down in chamber we make good progress. Great mass of stone appears in middle of right side of chamber. Probably at door to a side chamber to NE. I photograph stone.

In chamber we have reached level ca 1.0 above floor of dromos. Some green sherds & tiles appear here - below fallen conglomerate.

Tomb (49)

We begin to clear floor & pots have now come to light. But we find that chamber is much larger than we had at first supposed & suspend digging down in order to cut away large mass of earth & stone covering much of right corner. Chamber seems to be approx. square.

Tomb (50)

Large mass of stone at back of chamber. Geometrical & Corinthian arches among them show they are late. I photograph & then authorize their removal.

Tomb (41)

Work progresses slowly clearing floor. In outer right corner find good lintel and seal of earthenware (?) & Sifter continues to find paste beads & gold sequins.

(127)

Tomb (42)

Working with brush we go down in chamber. Ca. 40 above floor of dromos.

Tomb (38)

Diana by DHC & pots removed by JTH SED JS

Tomb (44)

Work in dromos today. It is much deeper than we thought. Stereo not yet found. Bill the potter, who dug this was deceived.

Tomb on the Hill (51)

Don photographed this morning & opened chamber. Prove to be almost intact except right front, but very nearly full of earth. Also looks deep like chamber of (48).

Tomb (8)

Two tombs apparently developing here, one under our Geometrical Grave, and one further NE.

128
Shaft Grave trenches.

Getting down toward stereo.
North trench almost finished
above rock brown earth with
8000 Myc pottery
3 trench not so far along
but stereo for 1/2 or 3/4 of way
Myc pottery here too in similar
brown earth

Friday, May 18

129

47 men

6 in Tombs 8 & 9

1 sifting in Tomb 37

1 sifting from " 41

2 in Tomb 41

5 " " 42

6 " " 43

3 " " 49

3 " " 50

4 " " 44

4 " " on the Hill

2 looking for E.H. Tomb

8 searching for shaft grave

1 pot mender

1 water man

Tomb 8

Dromos cleared to door. Has steps
& is of broad short type. Some pretty
good pottery for one large has seems
to be of Palace Style.

Tomb 9

Dromos cleared to door. Short
broad steep. A list covered with
7 flat stones on left side of dromos
just outside door.

Work in chamber goes on side
not yet to all around.

Tomb 41

cleaning goes on two seal
stones - entered - this morning.

Tomb 42

We reach tomb level today &
many pots begin to appear ca
& all told by mid afternoon
It looks as if (from 2 small
holes dug) as if there is a
burnt layer as in Tomb 7

Tomb 43

Cleaning chamber with knives
work all day, we are still ca
above floor of dromos but some
LH at short appear & most of a
small stumpy vase. Great number
of flat stones - prob. fallen from
door ways they go a long way
into chamber.

We also make good progress
digging down into southern side
chamber.

Tomb 49

Work all day with knives (9TH
& 10TH) nothing much by mid-
afternoon though bones have at
least at several places.

Tomb 50

Digging with knives slow pro-
gress. Many stones removed
with geometric pottery.

Tomb 44

Work all day in dromos. Starts
not yet to. Seems to be very
deep.

Tomb on the Hill. (51)
Cont. progress in cleaning south
of fallen rock from chert
Pty evening ready for knife work

Shaft grave trenches N of E & X
First trench finished today to
rock no sign of a shaft
2nd trench not yet finished
in middle. steno ft at both
ends.

A new trench begun on 6 m.
north of northern trench & roughly
parallel.

Saturday May 19

46 men

- 4 m Tomb (8)
- 2 " " (9)
- 1 " Tomb (37) sifting
- 1 " " (40)
- 3 " Tomb (41) sifting
- 5 " " (42)
- 6 " " (43)
- 4 " " (44)
- 3 " Tomb on the Hill
- 2 fuel trenching for 2H grass
- 2 m Tomb (48)
- 3 " " (50)
- 8 trenching for shaft grave - E & X
- 1 job tender
- 1 water man

Payroll Tonight

Tomb (43)

At a level ca .50 above floor of dromos we find great mass of stones spreading almost over entire area of chamber. Many fallen from above - look so. Mostly small rough stones but some flat.

At this same level we find a layer of remains chiefly in center left corner. Some bones & L.H. III photo

I am digging into west side of chamber cleaning up about the bases of stairs here to see if there really is a door to a side chamber. The stones look built as if a better constructed but geometric shape. I photograph & remove upper stones. This is ca 2 m. above floor of dromos.

Tomb (42)

This seems to be a layer of black earth & charred matter over whole floor. In & above it numerous pots & fragments have been found. Some good flat wares & pots from back center. Large round one from right back.

Tomb (41)

Almost finished. cleaning down way - some bones & a good many frags of large pots

Tomb (44)

Work in dromos - it seems to be a very large one.

Tomb (3)

Dromos door cleaned & photographed. Upper part of door removed. One or two more out chambers. Sides not yet fit all around.

Tomb (4)

Dromos door cleaned & photographed. Work goes on in chamber & stored pots in right - all around now except under right corner.

Tomb (47)

Being drawn by S.H.C. one photograph taken. A bad mess of bones & frags of pottery.

Tomb (49)

Cleaning goes on. several new pots now in under right corner.

Tomb (50)

2 pots come to light during morning.

Sunday May 20

Afternoon - excursion to Dendra with
Bestos 2 cars
Afterward drove to Kephalaon & picked
up prehistoric shards above S of the
same. Mostly neolithic - walkway, but
2 mile some Early Helladic

Monday May 21

39 men

- 4 in Tomb (8)
- 2 " " (9)
- 1 " " (37)
- 2 " " (41)
- 4 " " (42)
- 2 sifting pan (41) + (42)
- 1 " Tomb (43)
- 2 " " (49)
- 2 " " (50)
- 4 " " (44)
- 2 trial trenching above (19)
- 3 in Tomb on Hill
- 8 in shaft grave trenches E XIX
- 1 ad-mendh
- 1 water man

Tomb 43

On north (right side) of chamber we have now cleared away all fallen stone (perhaps some built into a sort of bench) to a level of ca. 65" above floor of dromos, & we have revealed here a well constructed wall extending along cavity the side of the chamber, apparently walling up a side chamber or niches. This wall starting at outer right corner is 1.80 m long 0.53 m thick. The chamber behind appears to be merely a small niche but we can tell better when we get deeper. The wall is carefully built of small flat stones. Its present top is only ca 1 m above floor of dromos. Great mass of stones in chamber doubtless fallen inwards of upper part of this wall.

Tomb 37

cleaning out chamber after drawing - of a long sword - 3 gold plates, necks, gold wire on hole.

Tomb 49

Progressing rapidly. Many bones - few pots yet.

Tomb 50

Good progress. Since floor pt to right. Cist to left. Good potsherds.

Tomb 42

good progress. Many pots now appear.

Tuesday May 22

42 men.

- 2 m Tomb 8
- 4 " " 9
- 1 " " 37
- 4 m Tomb 42 1 sifting
- 4 " " 43 1 sifting
- 2 " " 49
- 2 " " 50
- 4 " " 44
- 1 exploring for E H Tomb
- 3 " Tomb on the Hill

- 13 exploring for shaft graves below temple
- 1 pot on end
- 1 water man

Tomb 5

cleaning chamber. large no of pots also heads of parts.

Tomb 37

rough work removed

Tomb 42

great many heads of pots coming to light

140

Tomb (43)

Good progress. Remove many of
fallen stones in chamber. Pottery, the
gumms, & appear

Tomb (44)

Beads found in dromos - 1 of earthen
3 of faience. Stone floor of dromos not
yet found.

Wednesday, May 23

141

40 men

2 in Tomb (8)

1 " " (37)

4 " " (42) 1 sifting

3 " " (43)

2 " " (49)

2 " " (50)

1 sifting " (49)

1 in Tomb (44)

2 " M.H. - E.H. area below (44)

2 " " on the Hill

12 " E.X.IX

3 " filling trenches

1 mended

1 water man

E.H. - M.H. grave S of (44) is good cutting
in stone & full of stones. A few pits here
E.H. - M.H.

Tomb (44)

Gold plates next pm days found in dromos.
Stone floor not yet reached.

Tomb on the Hill. (51)

almost finished channeled. Has bronze dog
& amethyst bead

142

Tomb (43)

Good progress. We have now removed most of fallen stone except in center right corner. More large pieces under & among stones. Much pottery - but seems badly shattered.

Tomb (49)

Good progress. Rejuvenating ready for drawing & photographing. Col. of successive interments.

Tomb (50)

Almost ready for drawing

Tomb (47)

Cleaning progressing. Bronze mirror for

Thursday May 24

143

4:2 men

- | | | | | |
|----|--------|--------------------------------------|------|--------------|
| 2 | in | Tomb | (9) | |
| 2 | " | " | (9) | |
| 1 | " | " | (37) | |
| 4 | " | " | (42) | (1 sighting) |
| 3 | " | " | (43) | |
| 1 | subter | " | (49) | |
| 2 | " | " | (49) | |
| 2 | " | " | (50) | |
| 4 | " | " | (44) | |
| 2 | " | Tomb on the Hill | | |
| 2 | " | E.H. - M.H. grave | | |
| 4 | | filling trenches | | |
| 12 | | trial trenching for shaft grave Exix | | |
| 2 | | washing pottery | | |
| 1 | | water man | | |

Miss Haight & party visit dig today

144

Tomb in the Hill. (51)
 Chamber cleared for drawing. Roughly rectangular ca 2.50 m sqm. Ht. in center 1.40 m. ceiling on right side partly broken away. Shape of ceiling roughly, vaulted from side to side.

Floor not smoothly levelled. In chamber great mass of bones across back - most in inner left corner. About 10 skulls appear here & some no. of pots. 1 bronze dagger & 1 small head along left side from outer corner appear a complete skeleton - latest interment in chamber. Lay on right side w. head to NE feet to SW. (head toward inner corner) left arm at side w. arm bent at elbow, over bust. Legs prob. sharply bent at knees. One femur only preserved & 1 tibia. Bones seem small. Skulls badly eroded. Some ribs preserved.

In outer at corner a small narrow cist m. long m. wide. Contains bones of 1 skeleton & 1 skull. Heaped up over cist.

Ht. of heap at left back ca 60 cm. Nothing just in front of door.

Door ca 75 wide outside 90 inside & ca 0.90 deep from front to back. Tapered toward top but upper part is gone.

Tomb (49)

D.H.C. draws plan in morning. Photograph after lunch. 5

Tomb (41)

Lower part of door removed. Made of good large stones built right through doorway. In inner side. Cylindrical stem on outside. Large pot in inner side.

Tomb (42)

Clearing goes on slowly. In outer right corner some very perishable remains of wood associated with bones - perhaps trace of a bed.

Tomb (43)

Clearing progressing. In inner right corner we clearly have heap of remains. Many bones & fragments of pottery. A bronze cleaver here & 2 fragmentary (or maybe complete) knives or daggers. Also a good many beads - 5 round ones of carnelian, 6 (4 round 2 olive pits) & 3 frags of paste.

Tomb (6)

Ready for drawing.

Tomb (52)

New tomb found between (34) & (35) at a high level. Very small chamber apparently. The door will meet at # 18 belongs to this tomb.

145

- 46) Photographs Film Pack I
- 528 ① Chamber of Tomb (49) from above
- 529 ② Chamber of Tomb (49) from door
- 530 ③ Dome & door of Tomb (49)
- 531 ④ Center back of chamber of Tomb (41)
- 532 ⑤ Skeleton inside door of Tomb (41)
- May 20
533 ⑥ Tomb (50) chamber left back (ruined)
- 534 ⑦ Right front corner of chamber of Tomb (50)
- 535 ⑧ Left back of chamber of Tomb (50)
- 536 ⑨ Stones covering cut along left wall of chamber of Tomb (9)
- 537 ⑩ Stone slab covering cut along left wall of dome of Tomb (9)
- 538 ⑪ Mass of stones in trial trench for L.H. tomb of (44)
- 539 ⑫ Pots & bones on left side of Tomb (8)

Film Pack II

- 540 ① Heap of bones & pots on right side of Tomb (8)
- 541 ② Pots etc in Tomb (52)
- 542 ③ Tomb (52) from South

Friday May 25

147

41 men

- 1 sifting from Tomb (34)
- 2 digging near (34) & (35)
- 1 sifting from Tomb (8)
- 3 in Tomb (9)
- 3 " Tomb (42)
- 3 " " (43)
- 7 " " (44)
- 4 trenching for E.H. tomb
- 2 filling trenches
- 12 trenching for shaft grave
- 2 pot washers
- 1 water man

Professor & Mrs. Rosterhoff visit day & breakfast
& lunch with us.

Tomb (44)

Good progress going down to drums

E H Tomb S of (44)

We work rapidly today enlarging area toward the west. Find line of stonework deposit to NW. A good many sherds here - chiefly E H

Tomb on the Hill (51)

DHC begins drawing

Tomb (41)

DHC finishes drawing the AM & we begin to take things out. 14 more gold beads from cist and 1 roselle

Tomb (42)

Work goes on slowly & carefully cleaning front part of chamber

Tomb (43)

Work still slowly before noon then men worked to (43) & clean out

Tomb (49)

We begin to remove objects

Tomb (9)

Ready for drawings

Tomb (52)

Small chamber. It contains at least 2 skulls & 5 pots. 1 large grey or 3 hole looks like fabric of polychrome mottled ware. A small jar also looks M H or yellow Mm jagged. Collet removed Apr. 18 (p. 17) belongs here. 2 pots dec. in Myc style. pot L H I, 2 think. 1 is a squat jar w vertical side & angle at shoulder

Trenches for shaft grave

Work goes on in 4 trenches above E XIX section r. to E. 4 long parallel trenches numbered from below 4 to 7. Good Mycenaean sherds coming from all of them

Photographs Film Pack M

- 543 (4) Door of Tomb (44)
- 544 (5) Heap at back & left of chamber of Tomb (51) T on the hill
- 545 (6) Heap at back & right of chamber of Tomb (51)
- 546 (7) Diagonal door of Tomb (51)
- 547 (8) Steps in door of Tomb (48) from inside
- 548 (9) Bones outside chamber between Tombs (8) & (9)
- 549 (10) Stone smashing technique - two crew outside Tomb (44)
- May 30
550 (11) Bones & pots right back of chamber of Tomb (42)
- 551 (12) Heap of bones & pots left side of chamber of Tomb (42)


Film Pack N

- 552 (1) Heap of bones spots on left side of chamber of Tomb (42) from side of door
- 553 (2) Skeleton on bier in outer right corner of Tomb (42) from above
- 554 (3) Pots etc to centre & right of chamber of Tomb (42) from left

- H1 men
- 3 in region of (34) (1 sifting)
- 1 sifting in Tomb 8
- 3 in Tomb (42)
- 3 " " (43)
- 1 " " (49)
- 8 " " (44)
- 4 diggers for 44 tomb
- 4 trial trenching below (10)
- 11 trenching below temple
- 1 washing pottery
- 1 pot mender
- 1 water man

JTH & EDB left for Athens this morning

Trenches about E XIX looking for shaft graves



Test Trenches for Shaft Graves (153)

Trench (4) At S. end we seem to have room of a house. Geometric pottery & some bronzes come out here.

In middle of trench is a sort of hollow filled with whitish earth - looks like stone to me.

At N. end of trench is a fill of dark earth containing good medieval/late-late shreds.

Trench (5)

S. end shallow stereo (d). In middle we get same debris as in (4) filled with white stereo.

At N. end dark ashy earth goes down deep. Some fine Myc pots/shards in it, esp. Ephyraean.

Trench (6)

Parallel to (5) & similar. Dark earth at N. end with good Myc shreds. Here we find a high wall running horizontally & trench at extreme N. end.

(154)

Tomb (44)

By a great effort we finally
reach floor. Stone on side door
of tomb. It is 2 m below
the point called stone by Vasili

(155)

Monday, May 28

30 men & 1 technician

4 in Tomb (25)

2 " " (9)

4 " " (43)

6 " " (44) & 1 technician

2 filling trenches

1 potting

1 water man

10 trial trenching for shaft graves

Rain before breakfast disturbs work, but
we go on. Fine afternoon

156

Tomb 44

Clearing doorway. The walls
still in place to a height of 2.30 m.
Lower part made of small, large stones
mixed of thin flatish. Upper part
of smaller rounded, fairly smooth
standing wall but not so neat.
At bottom of wall is a large heap
of stones in drums - extending ca
1 m into drums ca 50 - 60 cm high.
All the part of wall below the
steps originally got by Bitt the
pottery.

The door is ca 1.50 m wide at
bottom & narrows to .80 at a ht
2 m. Door jams on each side built
int in stone, not quite symmetrical
but in same plane.

We remove part of wall in door
& work mainly inside chamber. 2
men work all day breaking up the
huge fallen chunks of stone. Half
done by evening.

Tomb 45

In 2 side chamber we clear
down to floor & remove first
boulder from SE corner. Then
dig on both sides.

Tomb 46

All exists cleared. Absolutely
nothing in them.

Tomb 43

4 men digging. Fragments
of pottery & bones appear everywhere
also more beads of paste & 1 of
carnelian & 2 bronze rivets
prob from a sword handle.

Tomb 47

Sifting. 1 more gold bead

Tomb 42

D.H.C. draws plan

Tomb 51


(on the hill)
we photograph & begin to remove
pots.

157

158

Tomb (48)

At the back of the chamber seems to be a continuous heap all the way across - brown pottery. On the left a good many beads appear. A new shape - sort of hairy of parts. 4 of them in a row.



Tuesday May 29

159

32 men & 1 technician

2 in Tomb (25)

1 " " (49)

1 " " (41) sifting

1 " " (42) "

4 " " (43)

2 " E H Tomb

6 & 1 technician in Tomb (44)

1 in Tomb (51)

10 trial trenching below temple Kaplan

2 filling trenches

1 mending pottery

1 waterman

(160) Tomb (44)

After great efforts yesterday & today by the recruits & George along with the finally succeeded in breaking up the huge piece of fallen rock in the chamber. A keelson fragment to the right was quickly disposed of. A third large chunk then applied to the left very large but broken up during afternoon.

Tomb (43)

Cleaning over on all day.
Pebbles: 9 shiny, sharp, one round
2 sunburnt, 2 small bronze
nests all from back centre of
chamber.

Tomb (51)

Pis mostly removed & lower
layer cleared. A fine huge crystal
head of. Also amethyst head &
some of amber.

Tomb (49)

Cleaning of lower layer over on
Great many fine parts head
round & pendants, 2 fragmentary
silver pins, one with traces of
wavy head held on by gold
head nail.

Wednesday, May 30

(161)

30 men

8 in Tomb (44)

4 " " (43)

1 sifting in Tomb (42)

2 " H Tomb ?

2 trial trenching below T. (10)

1 in Tomb (49)

1 " " (51)

8 trenching for shaft grass

1 washing pottery

1 pot mender

1 waterman

162 Tomb (44)

Today we broke up the last of the remaining fragments of fallen rock + began to dig down in chamber through fairly loose caked duruloo clay stones. Good progress. The chamber is evidently a large one but sides not yet clear.

We remove a few more courses of stone from wall closing door to make access easier. Among stones for a couple of cubic stems + fragments of a large L.H. III but with red bands.

L.H. Tomb 506 (44)
Give up today. Only stones transfer into niches to re-examine.
L.H. Tomb (4) of 1925

Tomb (43)

3 men with knives all day + 1 sifting. Back of chamber practically cleared for drawing that is, the upper layer. A great many frags of pottery all L.H. III. A short bronze sword in heap at back on right side near door + clear to the other day. Many beads - past + chamber on right side - round shape. Saw also on left side chuffly pots flat daises + round. 1 copper (11 I think) fragment of amber bead from left side.

Tomb (49)

163
Clearing with one man progressing.

Tomb (50)

Drawn by D.H.C. + begun to take out pots etc.

Tomb (52)

Drawn by D.H.C. + pots removed.

Tomb (51)

Removal of duck gun or another huge object. Chief find is a female figure of ivory - in a flounced skirt + not in very good condition. Beak + broken but perhaps can be restored. Lay face down in rear central part of chamber w. head toward door.

164 Photographs. Film Pack N

- AH
555 (4) Bones on left side in centre of Tomb (49) from door
- 556 (5) Bones on left side of Tomb (49) from right side
- June 4
557 (6) Contracted skeleton in Tomb (8) upright
- 558 (7) Contracted skeleton in Tomb (8) (horn) from opp corner
- June
559 (8) Tomb (49) Dromos door & chamber all cleaned out
- 560 (9) Tomb (50) Dromos door & chamber cleaned out
- 561 (10) Gen view of Kephalaro Hill
- 562 (11) Gen view looking up E Kephalaro ridge from below
- 563 (12) View of Heraion Hill across Tomb (49)
- Film Pack (13)

- 564 (1) Dromos + door of Tomb (43)
- 565 (2) Objects in chamber of Tomb (43) from door.
- 566 (3) Heap of bones etc at right back of chamber Tomb (43) from above
- 567 (4) Door + side chamber & right side of chamber of Tomb (43) from above

Thursday May 31

165

- 36 men
- 14 in Tomb (44)
- 3 in Tomb (43)
- 1 sifting " "
- 1 sifting Tomb (9)
- 1 in Tomb (49)
- 2 in EHTomb
- 1 in Tomb (51)
- 10 trenching for shaft graves
- 1 washing pottery
- 1 measuring " "
- 1 waterwadi

166 Tomb (44)

With 14 men we are making rapid progress downward in chamber. The latter is now taking shape. Looks roughly rectangular (or maybe near to curving) ca. 5-35 m wide by 4.60 deep from front to back. Side is not yet absolutely certain. We find yet another chunk of fallen rock, but break it up quickly.

E H Tomb (9)

With 3 men we go on re-investigating this region. Begin just NE of pit over chamber of Tomb (10) & work north eastwards. Found an overhanging ledge of rock - very thin; it dips into earth below. 10 sheets of H wall. A line of small stones in a row gives some encouragement.

Tomb (43)

Good progress clearing down in chamber. At NE corner (outer right) we seem to have reached floor. 3 feet at back of tomb near middle of back; 1 of cambrian, 2 flat daisies & 1 bowl-shaped of past.

Friday June 1

167

38 men

3 in Tomb (43)

1 " " (49)

15 " " (44)

1 sifting in (51)

3 in E H Tomb (9)

2 filling trenches

10 searching for shaft-gave below Temple

1 washing pottery

1 pot mender

1 water man

Tomb (44)

with 15 men we dig down rapidly in the chamber. Still another chunk of fallen rock broken up & removed. Sides of chamber now appear all around. It is curved not rectangular. chamber a little more than half a circle. ca. 4.80 m deep from front to back by 5.20 m. from side to side.

Just before closing this evening we found (a broke) a skull - ca. 35 to 40 cm above floor level. Dug 2 pits to test depth - one in outer right corner one on left side & found floor. There seems to be a thick layer of ashes & charred matter on floor. Fragments of an unglazed cup w. high hole found in pit on left side.

E.H. area (former 9)

We spent all day exploring here & found even more pits - E.H. & realistic. curious place different to understand - layer of earth beneath ledge of rock.

Tomb (43)

3 men working steadily. we clear floor in front part of chamber. learn all objects of higher levels on pillars. Nothing much found in the part of chamber.

Saturday, June 2

39 men

- 2 in Tomb (8)
- 3 " " (43)
- 15 " " (44)
- 3 " E.H. Tomb (9)
- 1 sifting Tomb (51)
- 2 filling trenches
- 10 trial trenching about Temple
- 1 washing pottery
- 1 pot mender
- 1 water man

Tomb (44)

Work with kumbis all day 3 men
+ 2 or 3 carriers.

Ed. complete skeleton along right
side of tomb - lying flat on back
head to outside of tomb. Feet broken
off by pickmen yesterday. Beyond
feet seems to be a heap of pots -
stirrup base large - cup - eight, etc.

2 or 3 ink left corner apparently
early remains. Some fragments of
LH - II pottery.

Another gang of men all day
in dromos trying to find stereo
floor all the way to outer end.

After breakfast some of men taken
from (44) to filling benches.

Tomb (43)

Almost finished for drawing
work in right niche on side
chamber. Stereo seems set higher
than in chamber.

Clear door & remove another course of stone.

Tomb (8)

all pots removed yesterday. Lower
level of vials being cleaned.

Tomb (42)

Begin to take out pots etc.
from chamber. A good sword
found in heap to left. Lots of
LH flanged half & central row
of 6 vials.

Monday June 4

36 men -

- 2 in Tomb (8)
- 1 " " (42)
- 2 " " (43)
- 11 " " (44)
- 3 in E H tomb (9)
- 1 sifting in Temple (49) & (50)
- 10 digging about temple
- 3 filling benches
- 1 washing pottery
- 1 pot mender
- 1 water man

(172) Tomb (44)

5 men digging with kump make rapid progress through soft wet clay. Many pots now appear almost all in fragments. To right we see & have L.H. III remains. Complete skeleton for Saturday & beyond his feet large mass of pots: yellow (2 at least) & large stumpy bases, a huge jar & many smaller pots. Most of pottery also extends out toward middle of chamber. Against wall at right back is at least one small L.H. I pot.

At left back remains of a skeleton apparently in situ - contracted. w. head to NW (left) lying on its side. Skull represented only by teeth. These bones lie on layer of clay 5 cm thick above limit layer. Wk is very black & is 1-2 cm thick. In front of this skeleton & beyond its head are scattered 7 or 8 shattered L.H. I pots all small. Also frag. of larger vessels in pt. 3 bronze arrowheads here also frag. of curious coarse pot with regular hollows around its rim.

In outer left corner there is a group of bones which may be a much contracted skeleton. Head toward back of tomb lies parallel to side wall but on right side. One against wall beyond legs is a whole stumpy base L.H. III.

In centre of chamber a group of bones not yet clear also many frag. of pottery. The skeleton along right side is much the highest in level & not belong to last interment.

Tomb (44)

173

Digging now cleared footed for almost entire length 15-19 m. Steeply sloping floor at outer end more gradual slope toward inner.

EH Tomb (9)

we go on digging to SE of area 14. covered in 1905. entire area left to porch road are two layers of earth underneath. It contains a good many potsherds, apparently mostly medieval - red iron & brown like Theraian First Period.

Tomb (43)

cleaning finished today - ready for drawing. J.H.C. begins sketching.

174

Tomb (44)

In centre of Tomb we have clear evidence of 2 successive burnings - not from whole floor.

First layer is just above stairs not very thick nor continuous - black earth & coals here & there & some reddened clay above. Then ca. 0.6" of yellow clay. Then thick black layer 1 to 2 in. thick very black.

Photographs

AH. Film Pack O

- 568 (5) Wall closing side chamber of Tomb (43)
- 569 (6) Dromos of Tomb (44) from outside
- 570 (7) Dromos of Tomb (44) near view
- 571 (8) Front end of dromos of Tomb (44)
- 572 (9) Dromos of Tomb (44) from inside chamber
- 573 (10) Gen view of Herakium Hill from outside dromos of Tomb (44)
- 574 (11) Region of E H Tomb (9) hollow or chamber in wall SE section
- 575 (12) E H Tomb (9) NW section showing oval ring of stones on stairs

Film Pack P

- 577 (1) Dromos & door of Tomb (44) cleaned
- 576 (2) Dromos & door of Tomb (42) "

Thursday June 5

175

37 men

- 10 trenching E of Temple
- 8 in Tomb (44)
- 3 " E H Tomb (9)
- 8 filling trenches
- 1 in Tomb (42)
- 2 sifting in (42)
- 2 in Tomb (8)
- 1 washing pottery
- 1 pot mender
- 1 water man

176

Tomb (44)

4 men working with knives. Rapid progress.

Five skeletons of amethyst (lentoid) in against side wall at back in left area. One stored floor. Has fig. 1 a lion in much contorted attitude! Very fine work.

Alongside skeleton on right side of chamber on left side of skeleton just below left forearm (lower part of bones missing) is a gold ring with bezel carved in design of 2 snuffing storks facing each other in a column between. The column bears spiral fluting, diminishes toward top & has a double sort of capital. Good work of LH III (?) Heavy fabric.

The skeleton lies ca. 10 cm. above the burnt layer. Below the skeleton bones of earlier skeleton appear, but mostly clear if in order.

Opposite the feet of the skeleton & ca. 1 m. out into the chamber from the side wall in a small space found:

- 1 large bead of gold - spherical w. granulated dec.
- 1 tiny plain gold bead 1 tiny cluster bead of gold
- 4 long olive pit beads of green with spiral flutings.
- 3 spherical carnelian beads
- 1 rosette & fragments of paste
- 2 round beads space of paste
- 1 olive pit bead of carnelian

near the wall an arrowhead of flint ca. 40 farther from the wall bits of lead wire
All these beads etc on floor, or just above.

Near them a small scallop (?) of bronze ca. 3 cm. above floor. all of these objects (except scallop) in a layer of whitish clay beneath burnt layer.

EH Tomb (9)

177

In this area we go on all day calculating our pit toward the E. Two are same conditions as before: layer of earth under ledge of soft rock. The earth is first red ca. .60 m thick then black - about 2 layers ca. 20-30 thick, then gray & somewhat ash. Probably so in all 3 layers mainly Neolithic, but a few may be EH.

I In E part of our area in a small hollow ca. 45 deep - found no stone in it. .75 m in diam. Rock found at ca. 2.30 below present surface of the ground.

Tomb (43)

cleaning finished & DHC begins drawing

178

Photographs - Film Pack (P)

- A.H. 578 (3) Skeleton on right side of chamber of Tomb (44)
 579 (4) Pots etc left side back of chamber Tomb (44) from outer right corner
 580 (5) Pots etc right side back of chamber Tomb (44) from outer left corner
 581 (6) Pots etc center of chamber Tomb (44) from outside door
 June 7
 582 (7) Pots etc. on right side of chamber of Tomb (43) lower level
 583 (8) House wall, corner, from W. in Trench 108 E of Temple
 584 (9) House wall etc trench 108 from S.W.
 585 (10) House walls + drain, Trench 108, from S.E.
 586 (11) Trench 108, E of "altar", from W.
 587 (12) Trench 108, E of "altar", from East

Film Pack (9)

- 588 (1) Side chamber of Tomb (43) cleaned from left side of chamber
 589 (2) E.H. Neolithic grave (9) w. hollow V
 590 (3) same as (2) V
 591 (4) E.H. Neolithic grave 2nd hollow
 east IV

Wednesday June 6

179

36 men

- 16 trenching E of Temple
 7 filling trenches
 8 in Tomb (44) 2 sifting
 3 in E.H. tomb (9)
 5 in Tomb (43) 2 sifting
 1 washing pottery
 1 mending "
 1 water man

This evening we paid off 16 men & G. Alexopoulos left. We are continuing tomorrow with 21 men.

Tomb 444

Cleaning for drawing almost finished by breakfast

4 more small gold beads for on right side in area where beads were for yesterday

Tomb ready for drawing after breakfast and C begins drawing

Note at the head end of the skeleton on right side of chamber. Skull rests .20 m above floor on yellow clay above red burnt clay above burnt layer. Under right shoulder is another skull, burnt black & some burnt bones to S of it resting at .12-.15m above floor. Still lower here in the same area - projecting from under latest skull is a third layer of bones - not burnt resting at 3-5cm above the floor. So we clearly have 3 layers 1st unburnt, 2nd burnt, 3rd unburnt

In centre front of chamber a number of bones in rotten condition. Same at 15-16 above floor not burnt. Burnt layer here at 8-11cm above floor also includes bones just inside door is a broken pot with rosette design - above burnt layer. Burnt layer not very clear just here. A little farther in a stumpy vase. Think in burnt layer. Then 2 cylinder stems above burnt layer. Still farther in a shallow cup or dish in burnt layer.

4 or 5 pots at back of chamber left are mostly on burnt layer - black is beneath them

E.H. tomb 9

Digging here all day with 3 men

In E part of one area we find 2 more hollows in rock like the one for yesterday. One of them roughly oval in shape ca 0.70 long by 0.60 wide & 0.40 deep. Found to contain some bones: a fragment of a burned skull charred & blackened & a few small bones with small stones upon & among them. Certainly a grave. No getting for. Shards from strata above were heathen. Perhaps this is a grave of the Achaic period.

IV

III

The third hollow is also roughly oval 0.90 x 0.78 m & ca 0.40 deep. Nothing for in it.

The fragments of skull in 2nd hollow are at centre among bones around them. Traces of burning skull frags. charred

II

A fourth similar hollow to west - empty. Oval in shape ca .90m x .73m .30 m deep.

Photographs

Film 9.

592

Sundial

593

" "

Thursday June 7

183

21 men

6 trenching E of Temple

2 filling trenches E x IX

5 in Tomb (43)

3 " " (44)

3 " E H Tomb (9)

1 pot grinder

1 water man

Tomb 44
DHC finishes drawing & we remove
pots etc.

E.H. Tomb 9

A fifth hollow now fd to west
of others - just under tunnel we dug
in 1915. It is larger than the
others - not yet fully cleared
like them a basin cut in strata
ca. 40 to 80 deep (strata to west
is) In this hollow a few
bones among & under small stones
Fragments of skull in center
Some under to arm & leg bones.
Bones show traces of burning
Above this grave as above # 2 (p. 181)
was a fairly thick black burnt layer (0.25
above bones & 0.15 thick) 2 persons
fd above grave - red monochrome (=
Thasian or First Period). One Christian
black fd at level of bones at E end
of grave.

April 1, 1929. Skulls etc. to Sordani by Butler
Box 5 Skull from T. 31 Platform & Skull from T. 22

5 }
7 } Skeleton from Tomb 44
7a }
8 }
8a } Skeleton from Tomb 8
9 } 2 Skulls from Tomb 51
10 } 3 " " " "
11 } 2 " " " "
12 } 2 " " " "

No.	Description	Locality	Tomb	No.
906	Small perforated lid	LH III	Tomb 42	No. 23
907	" pitcher	"	"	" 27
908	Unpainted jug 2 side holes	"	"	" 34
909	" amphora	"	"	" 39
910	" cylix	"	"	" 40
911	Thin cup	"	"	Shots
912	Sm. shallow cup 1 hole	"	"	"
913	Thin pitcher (frag)	"	"	"
914	Large jar or amphora	LH I	Tomb 52	No. 4
915	Small amphora	LH III	Tomb 43	" 44
916	Large feeding bottle	"	"	" 50
917	Unpt. large bell-shaped basin	"	"	" 37
918	Shallow cup	"	"	" 41
919	Unpt. jug 2 side holes	"	"	" 65
920	Large jug, bands, 1 hole	"	"	" 66
921	Amphora	"	"	" 70
922	Shallow cup	"	"	" 10
923	Small stirrup vase	"	"	" 11
924	Tall amphora	"	"	" 13
925	Small "	"	"	" 14
926	Large high necked jug	"	"	" 15
927	" "	"	"	" 2
928	Unpt'd cylix	"	"	" 18
929	Large amphora tall	"	"	" 19
930	Unpt'd jug 1 hole	"	"	" 75
931	Alabasteron vertic. side	"	"	" 38
932	Shallow cup	"	"	" 40
933	Sm. cup 2 rim holes	"	"	" 54
934	Stirrup vase	"	"	" 55
935	Sm. "	"	"	" 57
936	Feeding bottle red	"	"	" 58
937	Bell-shaped cup 1 hole	"	"	" 59
938	Sm. stirrup vase	"	"	" 72
939	Unpt'd cylix angular	"	"	" 3
940	Large stirrup vase	"	"	" 4
941	Large "	"	"	" 5
942	Small "	"	"	" 6
943	Unpt'd cylix 2 holes	"	"	" 7
944	Shallow cup	"	"	" 23
945	Thin jug vertic. 2 side holes	"	"	" 30
946	Sm. figuine disc type	"	"	" 32
947	" " " "	"	"	" 52
948	Stirrup vase 7 base	"	"	" 46
949	Small alabasteron	"	"	" 47
950	Unpt'd jug 1 hole	"	"	" 48

861	Small crater or deep bowl	Tomb (34)	No. 95
862	Small jug w. high neck	"	" 96
863	Deep dish or bowl Roman period	Kephylai Hill (23)	
864	Unft'd. feet bottomed juglet (Cynthian)	Tomb (40)	No. 13
865	TC fig. crescent	Tomb (43)	" 8
866	Shallow cup or saucer 1 hole side spout	"	" 9
867	TC fig. disk type	"	" 17
868	Low jar Geometric Period	from EXIX Tr (4)	5 cur
869	Unft'd. tall jug w. 2 holes	Tomb (25)	No. 36
870	Loaf pot badly damaged - LH I	"	" 38
871	Small jug geometric ?	ft below Temple in ravine	
872	Small stirrup vase LH III	Echerb Tomb (25)	No. (Shds)
873	Small jug w. 1 hole	Tomb (32)	" 10
874	" bowl w. cup w. side spout N. ch.	Tomb (25)	Shds
875	Feeding bottle fragmentary N. ch.	"	"
876	Ephyraean goblet (stem missing)	Tomb (28)	No. 23
877	Unft'd. handleless cup	"	" 18
878	Ephyraean jug	Tomb (29)	" 25
879	Small red cup 1 hole	Tomb (17)	" 20
880	Tiny pitcher	"	" 21
881	Small unft'd. calyx	"	" 11
882	Shallow unft'd. red cup 1 hole	Tomb (25)	" 4
883	Stirrup vase 1/2 (Shds) w. down	"	" 14
884	Unft'd. calyx	"	" 5
885	Fr. of amphora	"	" 7
886	Unft'd. shallow cup 1 hole (Shds. N. ch.)	"	"
887	Squat stirrup vase fragmentary N. ch.	"	Shds
888	Jug w. high neck 1 hole	Tomb (22)	" 16
889	Sm. straight sided alabaston	Tomb (52)	" 2
890	Squat alabaston LH III	Tomb (43)	" 63
891	Jug 1 hole LH III	"	" 64
892	Plain jug 2 holes Tomb	Tomb (50)	" 14
893	Shallow cup 1 hole	"	" 13
894	Plain jug 2 holes	"	" 1
895	Plain jug 3 holes	"	" 12
896	Large jug - high neck LH III	Tomb (42)	" 35
897	Small amphora	"	" 58
898	" alabaston	"	" fallen from door
899	Tall amphora	"	" No. 1
900	Plain calyx	"	" 7
901	Large amphora	"	" 8
902	" plain calyx (3)	"	" 15
903	Unpainted amphora	"	" 17
904	Foot of calyx unft'd.	"	" 20
905	Large unft'd. shallow cup 1 hole - spft	"	" 22

		187	
		Tomb (8)	No. 23
816	Small red jug 1 hole	"	" 23
817	TC figurine	"	" 24
818	Spreading cup	"	" 25
819	Tiny jug w. 3 holes	"	" 19
820	Straight sided cup deep hole	"	" 20
821	Shallow cup or saucer 1 hole	"	" 26
822	Tiny jug w. 1 hole	"	" 32
823	" squat jar (loaf)	"	" 33
824	Shallow cup w. 1 hole	"	" 11
825	Small red jug	"	" 12
826	Large jug w. 1 hole	"	" 13
827	Red feeding bottle	"	" 14
828	Small jug w. 1 hole (bands)	"	" 8
829	" " " (common)	"	" 9
830	" loaf pot	"	" 16
831	Squat stirrup vase	"	" 3
832	Shallow cup or saucer 1 hole	"	" 34
833	Large unft'd. jug w. 2 holes	"	" 2
834	Cylindrical pyxis	"	" 48
835	Lid of "	"	" 49
836	jug w. 1 hole (banded)	"	" 16
837	Tall oval jug 1 hole	"	" 15
838	Straight sided squat jar	"	" 18
839	Unft'd. calyx (Shds)	"	" 35
840	Shallow cup or saucer	"	" 28
841	Small loaf pot	"	" 29
842	" feeding bottle	"	" 46
843	Unft'd. calyx amphora 1 hole	"	" 47
844	Tall jar, red, w. 3 holes	"	" 6
845	Goblet unft'd. on short stem 1 hole	Tomb (52)	" 7
846	Unft'd. jug w. 3 holes	Tomb (49)	" 16
847	High necked jug w. 1 hole	"	" 19
848	Small jug 1 hole Gray Myrian	Grave XXIV	" 1
849	Shallow cup or saucer (red)	Tomb (42)	" 29
850	Tiny pitcher	"	" 31
851	Small pitcher	"	" 32
852	3 legged pot (colander type)	"	" 33
853	Shallow cup or saucer high hole	"	" 28
854	Small amphora LH III	"	" 37
855	Shallow dish handleless	"	" 21
856	" cup or saucer	"	" 25
857	Small loaf pot	"	" 24
858	Small amphora	"	" 36
859	Very large water bottle "paganini"	"	" 30
860	Shallow cup 1 hole unft'd	"	" 18

681	Small saucer w. stripes	Tomb (34)	No. 59
682	Tiny stirrup base	" "	" 31
683	Large shallow cup or saucer 1 hole	" "	" 47
684	Small unptd jug w 2 holes	" "	" 49
685	Jug w. spiral form decoration 1 hole	" "	" 54
686	Unptd cylx w high hole	" "	" 50+71
687	Small althgation LH III ?	" "	" 62
688	Large shallow cup or saucer w. 1 high hole	" "	" 68
689	Unptd cylx w 1 hole	Tomb (38)	" 6
690	Small jug w spirals	" "	" 7
691	TC fig. crescent shape	" "	" 8
692	" " " "	" "	" 15
693	Small jug - 1 hole - red	" "	" 4
694	TC fig. crescent shape	" "	" 16
695	Small bird ansos	" "	" 34
696	Small jug w. 1 hole	Tomb (34)	" 91
697	Small unptd jug	Grave XXVI	" 3
698	" " " "	" "	" 7
699	" TC spool or wheel	" "	" 6
700	TC wheel or button	Grave XXX	" "
701	Large amphora LH III	Tomb (38)	" 2
702	Small mouthed bowl or jar LH III	Tomb (37)	" 1
703	Large jug or ewer w high neck	" "	" 9
704	Leaf shaped pot Early LH III	" "	" 24
705	Fragments of large jug w handles LH III	" "	" 13
706	" amphora w cross hatching	" "	" 14
707	Large jug w bands LH III	" "	" 29
708	Elaborate feeding bottle w spirals LH III	" "	" 30
709	Squat leaf pot LH II - III	" "	" 34
710	Plain cylx 1 high handle	" "	" 31
711	Small plain cylx 1 hole	" "	" 32
712	Large cylx w 2 high holes	" "	" 25
713	Small unptd cylx 1 hole angular	" "	" 35
714	" " " " " "	" "	" 36
715	Small red cylx w 2 holes	" "	" 37
716	" " jug w. 1 hole	" "	" 38
717	Unpt. dish w 2 pinched out sides	" "	" 19
718	" saucer without holes	" "	" 26
719	Small " " "	" "	" 27
720	Unptd cylx w 2 holes	" "	" 17
721	Teapot w. sure spout LH III	" "	" 5
722	Spreading cup LH III	" "	" 3
723	Stem of goblet broad & low LH II	" "	" 7
724	Stem of cylx unptd	" "	" 8
725	TC animal figure	" "	" 39

626	Tiny leaf pot LH III	Tomb (45)	No. 14
637	Tiny jug LH III	" "	" 15
638	Shallow saucer w. side spout LH III	" "	" 16
639	Small stirrup vase LH III	" "	" 28
640	Small stirrup vase striped	" "	" 36
641	Double dish (Salt pepper dish) LH III	" "	" 27
642	Small leaf pot LH III	Tomb (34)	" 14
643	" unptd amphora	" "	" 19
644	" amphora	" "	" 21
645	" pitcher & 2 neck handles	" "	" 22
646	Saucer w high hole	" "	" 15
647	Jug w. 2 holes	" "	" 38
648	Small leaf pot	" "	" 78
649	" unptd jug " 2 holes	" "	" 79
650	Small amphora LH III	" "	" 34
651	" stirrup vase LH III	" "	" 44
652	Squat jar LH III	" "	" 45
653	Small jug w. black stripes	" "	" 72
654	" squat jar (leaf)	" "	" 73
655	Large high red cup tankard	" "	" 74
656	Small red cylx	" "	" 76
657	Unptd jug w 2 holes	" "	" 67
658	Leaf pot small LH III	" "	" 69
659	" " " dots	" "	" 70
660	Small flat leaf pot	" "	" 55
661	Unptd cup without holes	" "	" 58
662	Teapot w spirals (feeding bottle)	" "	" 63
663	Unptd jug w. 1 hole	" "	" 64
664	Shallow cup w. 1 hole	" "	" 39
665	Unptd jug w. 1 hole	" "	" 41
666	Large jug w. 2 lateral holes	" "	" 35
667	Jug w. spirals 1 hole	" "	" 36
668	" w bands 1 hole	" "	" 32
669	Tall stirrup vase	" "	" 33
670	Shallow cup or saucer 1 hole	" "	" 77
671	Frag. of jug (unwashed)	" "	" 80
672	Jug w. 1 hole	" "	" 40
673	Stirrup vase (bad condition)	" "	" 53
674	Unptd shallow cup or dish	" "	" 13
675	Tiny jug w 2 holes & high neck	" "	" 16
676	Shallow cup or saucer bands & spirals	" "	" 17
677	Large unpt shallow cup w high hole	" "	" 18
678	Jug w. 2 holes + high neck	" "	" 28
679	Unptd shallow cup without holes	" "	" 29
680	Spotted beaker	" "	" 30

591	Small unpt. jug w. 1 hole
592	" mottled cup w. side hole
593	Sm. shallow Myanmar cup
594	Unpt. shallow cup w. 1 hole LH III
595	" cup without holes
596	Sm. jug w. bands
597	" unpt. cup w. 1 hole
598	Unpt. jug w. 2 holes
599	Sm. red striped jug
600	Unpt. jug w. 1 hole
601	Small amphora LH III
602	Ephyraean jug LH III
603	Animal figure of TC
604	Unpt. jug w. 2 holes
605	Shallow cup stippled shds
606	Unpt. shallow cup
607	Sm. striped pot stirrup (?) shds.
608	LH I shallow cup spirals (incomplete)
609	Small crescent fig. of TC
610	" disk fig. of TC
611	" squat jug racquet patt.
612	Geometric oenochoe
613	Ptolemaic sherd
614	Large amphora LH III
615	Jug w. cut-away neck LH III
616	Coarse red cup without holes LH III
617	Small leaf pot LH III
618	" jug LH III
619	" stirrup vase LH III
620	Greece lamp
621	Tall jar amphora LH III
622	Tall stirrup vase " "
623	Squat jar wave pattern LH III
624	Large amphora w. spirals LH III
625	Spreading cup LH III
626	Shallow cup stippled LH III
627	Alabasteron
628	Shallow squat w. shade ing. leaves
629	Small squat jug
630	Unptd. cup without holes (1/2)
631	Large stirrup vase LH III
632	Small table on 3 legs LH III
633	Small jug LH III
634	Small stirrup vase LH III
635	TC figurine Oinochoe type

Grave XIX	No. 8
Grave XX	No. 7
Tomb (36)	" 12
" "	" 14
" "	" 26
" "	" 21
" "	" 43
Tomb (48)	" 6
Tomb (39)	" 1
Tomb (47)	" 2
Tomb (46)	" 3
" "	" 4
" "	" 5
" "	" 13
" "	" 27
" "	" 26
" "	" 33
" "	" 35
Tomb (36)	" 5
" "	" 9
" "	" 25
Tomb (34)	" 3
" "	" 5
" "	" 1
Tomb (36)	No. 3
Tomb (48)	" 1
" "	" 2
" "	" 9
" "	" 11
Tomb (43)	door
Tomb (34)	No. 56
" "	" 42
" "	" 51
" "	" 61
" "	" 60
" "	" 93
" "	" 57
(MH) Grave XXI	No. 7
" "	" 8
" "	" 10
Tomb (45)	No. 17
" "	" 31
" "	" 32
" "	" 33
" "	" 34

596	Tring amphora 3 holes LH III	Tomb (40)	No. 7
597	Tring jug w. 1 hole	" "	" 5
598	Sm. unptd. jug (geometric)	Tomb (34)	" 4
599	" cup without holes (")	" "	" 6
599	Very large jug w. 2 holes (geometric)	" "	" 2
599	" " " " " "	" "	" 1
599	Unptd. jug w. 2 holes	Tomb (48)	" 21
599	" " " " " "	" "	" 4
599	Sm. leaf pot LH III	" "	" 10
599	" unptd. cup without holes	" "	" 14
599	" amphora LH III	" "	" 25
599	Unptd. jug w. 2 holes LH III	" "	" 8
599	Unptd. cup w. handle on side MH	Grave XXI	" 11
599	Mottled jug w. tall neck	" "	" 12
599	Achaean "terracotta" LH III early	Grave XXV	" "
599	Sm. broad jug w. 2 holes LH III	Tomb (36)	" 28
599	" " " spirals	" "	" 31
599	Unptd. shallow cup without holes	" "	" 32
599	Small dish	" "	" 33
599	Unptd. cup w. side hole MH	Grave XIX	" 1
599	" jug w. 1 hole	" "	" 3
599	Mottled " " " " "	" "	" 4
599	Unptd. " " " " "	" "	" 6
599	Mottled jug w. 1 hole spiral	Grave XX	" 5
599	" " " " " " "	" "	" 6
599	Small unptd. cup w. side hole	" "	" 8
599	" " " " " 1 hole	" "	" 10
599	" Mottled jug " " " "	" "	" 9
599	" " cup w. side hole	" "	" 11
599	" unptd. jug w. 1 hole	" "	" 12
599	" MH pot jug	" "	" 1
599	" " " cup w. side hole	" "	" 3
599	" " " " " " "	" "	" 4
599	Small unptd. jug " 1 hole	Grave XVIII	" 1
599	Large Mottled " " " "	" "	" 2
599	Small unpt. cup w. side hole	" "	" 3
599	Sm. unpt. jug w. 1 hole	" "	" 5
599	(once pot) " " " "	" "	" 4
599	Small Myanmar goblet	Grave XIII	" 1
599	" mottled cup w. side hole	" "	" 2
599	Small " " " " " "	Grave XVI	No. 1
599	" " cup w. side hole	" "	" 2
599	" " " " " " "	Grave XIX	" 2
599	" unpt. cup " " " "	" "	" 5
599	Small mottled jug w. 1 hole	" "	" 7

Inventories of Pottery 1929

501	Small Matt-pd jug from grave XII				
502	T.C. figurine	Tomb	(36)	No.	7
503	"	"	"	"	8
504	Squat jar LH III	"	"	"	6
505	Small stirrup vase	"	"	"	1
506	Small jug (ptd shape)	Tomb	(39)	"	5
507	Large unptd jug	"	"	"	6
508	Small stirrup vase	Tomb	(36)	"	44
509	Small jug	Tomb	(39)	"	4
510	Large unptd. jug (2 holes)	"	"	"	3
511	Unpainted jug	Roman Grave	2 A		
512	" spherical jug	"	1 A		
513	T.C. figurine	Tomb	(35)	No.	6
514	" with infant	"	"	"	7
515	"	"	"	"	9
516	Broad usp w. 2 holes LH III	"	"	"	10
517	T.C. figurine	"	"	"	13
518	Thin pitcher LH III	"	"	"	12
519	Small cup	"	"	"	14
520	Small jar w. 2 holes LH III	Tomb	(47)	"	7
521	Small shallow cup EH? MH?	Grave	XVII	"	3
522	Small Matt-pd jug	"	"	"	4
523	Unptd. cup without holes	Tomb	(36)	"	39
524	Shallow cup w. 1 hole LH III	"	"	"	40
525	Unptd. goblet on stem	"	"	"	42
526	Squat jar (small) LH III	"	"	"	41
527	Unptd. handleless cup	"	"	"	38
528	Ptd goblet on stem LH III	"	"	"	37
529	Mingled dish on 3 legs	"	"	"	38
530	LH III unptd jug w. 2 holes	"	"	"	2
531	Figurine on hollow stem T.C.	"	"	"	4
532	Fedric bottle LH III	"	"	"	45
533	Small amphora LH III	"	"	"	46
534	Large unptd jug w. 2 holes LH III	"	"	"	42
535	Small stirrup vase LH III	"	"	"	44
536	Large jug w. animal paws LH III	Tomb	(35)	No.	4
537	T.C. figurine	"	"	"	3
538	Small jug LH III	"	"	"	11
539	" unptd. jug w. 2 holes LH III	"	"	"	8
540	" " " " 1 hole	"	"	"	5
541	Water flask LH III	Tomb	(40)	"	9
542	Unptd. jug w. 1 hole	"	"	"	12
543	Flat loaf-pot LH III	"	"	"	10
544	Small " " "	"	"	"	3
545	Cup without holes unptd	"	"	"	4

To 661

195

(37)	37
(38)	12 pots
(36)	34 pots
(37)	
(38)	
(39)	5 pots
(40)	7 pots
(41)	
(42)	
(43)	1
(44)	
(45)	11
(46)	8 pots
(47)	2 pots
(48)	11 pots
(49)	

36 661

(X1)	1
XII	
(XIII)	2 pots
XIV	
XV	
(XVI)	2 pots
(XVII)	2 pots
(XVIII)	5 "
(XIX)	8 pots
(XX)	11 "
(XXI)	5 pots
XXII	
XXIII	
XXIV	
(XXV)	1 pot

Roman 2 pots

Cash acct.

Trip to Naupha for finds of 1927 automobile	494.50	
To Petrides: Expense of shipping finds } Naupha to Athens	300.00	
Carpenter: National Museum for shelves	379.	
Tools - 25 picks 25 spades 50 baskets } small picks	3540.	
Shipment to Mycenae }	126.	
Miss Cox for work on Heracleum drawings } = \$100.	223.	
Miss Cox for work on Heracleum drawings }	4524.	
Miss Cox for Nemea drawings }	2262.	
Notes books - 10 @ 31.65	316.50	
Advance to Uncle George	150.	
Coffee pot	240.	
Pencils, pens, ink, labels }	6350.	
+ stickers }	1250.	
Photographic supplies, films, }		
matr. sticks, steel tape, etc }	2025.	
Two plumb lines	100.	
From G. & M. \$500.	37,750.	
1 roll of cloth for bags	570.	
string for bags	40.	
card board boxes (90)	130.	
Telegram to Naupha Hotel	2650.	
	18297.50	
knives, forks & spoons	390.	
Apr 21 Pay roll April 21	7001.	
Foreman's acct supplies	763.60	
Cook's acct. equipment	419.	
" " food supplies	451.	
Food supplies from Athens	650.	
Tea pot & teakettle	185.	
To Miss Cox	500.	
To Sotiri	500.	
To Spyros	500.	
Apr 28 Payroll Apr 28	12346.	
Foreman's acct	1027.80	
Purchase Egypt. scrub	1000.	
Cook's acct	1218.	
	45250.90	

Returned by Spyros	577.50	45250.90
3 basins for pot washing	500.	
Food supplies during week to Apr 28	75.	
From G. & M. \$500. @ 16.10	38250.	365.
Advance to chauffeur Naupha	1000.	
Hotel bill Naupha Apr. 17-29	8355.	
From Mr. Spyros for Hotel bill	200.	
drinks	600.	
meat & lamb	200.	
food at dig	1500.	
From H.T. Sample on acct	5000.	
food supplies	161.	
" "	84.	
" "	34.	
May 1 Payroll May 1-	12744.	
1/2 day workman G. Aloucy.	25.	
food at dig to date	1196.	
Return by George Alexopoulos	150.	
	851.95.	69264.90
Coffee	50.	
Balance to chauffeur Naupha	1380.	
Advance to Dem. Bakouris for Nemea	2500.	
card board box	18.	
To Sotiri	500.	
Tips at hotel	100.	
From Mrs. Hack	2000.	
" Mrs. Rawson	2000.	
Food bought in Naupha & Myra	231.	
Small tent	425.	
May 12 Payroll	13076.25	
Foreman's acct	321.	
Advance to Foreman on work	2000.	
Cook's acct to May 12	1359.	
	89150.	91225.15
To Miss Cox	500.	
From Mrs. Hack	6000.	
" Mrs. Rawson	4500.	
To Sotiri	500.	
May 16 Balance to Sotiri for 1 month	10000.	
Loan from Kostas	12000.	
From Mr. Sample	3000.	
Payroll May 19	13417.	
Cart to Naupha with Soudal	100.	
wooden labels	9.20	
Food supplies during week	1231.	
Cook's acct to May 19	114630.	1171.59

Forward
Recd May 19 \$500

114650
3826150

Hotel bill to May 12	871950
Payroll May 26	12282
Cook's acct May 26	98850
alcohol for mending	4120
Candies & cotton	62
Hydrochloric acid	210
Food supplies & May 26	29000
Drawing paper	150

Recd May 27 \$500.

38300.

Repaid to Kontos	12000
Hotel bill May 12-19	5253
" " 20-26	650250
Advance to Chambert	4000
To Mrs Rawson	500
Payroll June 2	10252
Damages to land	1400
Cook's acct to June 2	95750
Damages to land	225
" " "	175
" " "	120
" " "	195

Food supplies for dig
Cost of sealing up ^{Cost of equipment}
Loan from Kontos 3000.

Cook's acct June 8	109750
Food supplies for dig to June 8	36230
Hydrochl. acid & alcohol	27820
29 boxes & string	38350
Food supplies for dig to June 8	26650
Duster for Athanasios	8000
Tip to Chambert	500
" " " "	250
To DHC	500
AH	750
MR	250

Ball for automobile to dig	3700
Wages of cable by 12 June 8	3250
Loan from Kontos	5000
Tip at Nauphia hotel	250
Cartons for laundry from Nauphia	300
Photograph of fossils & prints	34750
From 2 P13 for board & other	2360
Payroll June 8	1730
From JTH for board	1132890
check	8000
Repaid Kontos	7650
Hotel bill taken	7650

To left, 6 km

499

Just to left of road at 6 km
Just on road to Scharnchor &
Kaparelli in a small rocky
mountain. E.H. patches fairly numerous
a few medicinal & modern also
Noi post E.H. sheds of me here
Hill called "Magonia".

Just to right of road at 7 km post 7 is an
E.H. site on opposite slope of hill to NE.
Hill called Skala. Chamid on road
below hill

To right above road at 8 km post
again high hill with some soil
& E.H. sheds

(Kontos to pay 4400.)

Total payroll
June 6-8
7490.75

185	11450	783
	1275	
	1550	
	1780	
	700	

KEOMATOL

Gold from 1 comb (40)

- 20 small lily beads
- 5 broader " "
- 2 melon " "
- 3 rackets
- 14 brackets
- 22 sequins
- 1 cylinder
- 1 carnelian & gold
- 1 malachite " "
- 1 crystal " "
- 500 of gold leaf

12332
2715
14977

Wages 4250 due of May

Forward
Recd. May

200

T 20

Hotel bill 6th
Payroll May
Cook's acct
alcohol for
candles
Hydrochloric
Food supplies

Dorms.
ca. 5.10 km
2.25 deep at dawn
low ca. 1.15 high

Draining pa
Recd. May

W. B. Sping
Guaranty Trust Co.
Rue de Stations
Paris
France

Replied to
Hotel bill 11th


Advanced to
To Mrs Rau
Payroll June
Damages to
Cook's acct
Damages to

Food supplies
Cost of sea
Locust from K
Cook's acct
Food supplies
Hydrochl. a
27 boxes of S
Food supplies
Doctor for A
Tip to char

34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51

To DHC
A H
M R


Bal for auto
Wages D. cab
Loan from
Tim at Nam
Carton for box
Photograph desk
From 2 1/3 for
Payroll June
From JTH for
check
Rigid front
bill




1 - a = 1.37
1 - b = 1.85
10 - a = 1.78
10 - b = 1.35

11650

139
170
1250
6250



1 - 4 = 3.95
10 - 3 = 3.75
10 - 4 = 4.65
10 - 5 = 5.07
10 - 6 = 4.82
10 - 7 = 3.94
3 - 6 = 4.31
3 - 7 = 4.98
3 - 8 = 5.01
3 - 9 = 4.85
1 - 5 = 4.80
1 - 6 = 5.04
1 - 7 = 4.67
1 - 8 = 3.70
8 - 2 = 4.94
- 3 = 5.04
- 4 = 5.04
- 5 = 4.58



AMERICAN SCHOOL
OF CLASSICAL STUDIES
ATHENS, GREECE

Microfilmed: 14 NOV 1972



6a / Table ~~II~~ - 16 & 17
of Nos 5 & 6

Utrecht, April 27 1928

Emmalaan, 33

Dear Sir, Almost immediately after I had written you, I received a very kind letter of M^r Bertos. He assures me that I can get Alexopoulos as my foreman, as soon as I come. I am very glad to know this.

Yours sincerely

W. Volgraff

BRIEFKAART

Grèce



M^r C. W. Blegen

Αρτογραφία Παιών



Αρτογρ. Παιών

No. 35 - Tomb 11

36 - " "

149 - Tomb 2

145 - " "

146 - " "

138 - Tomb 3

" "

130 - Tomb 5

3867

" "

